National Grid ESO
Faraday House, Gallows Hill
Warwick, CV34 6DA

All Recipients of the Serviced Grid Code

Rachel.beaufoy@nationalgrideso.com
Mob: 07970992890
www.nationalgrideso.com

18 March 2021

Dear Sir/Madam

THE SERVICED GRID CODE – ISSUE 6 REVISION 1

Issue 6 Revision 1 of the Grid Code has been approved by the Authority for implementation on **18 March 2021.**

In order to ensure your copy of the Grid Code remains up to date, you will need to replace the section affected with the revised version available on the National Grid Electricity System Operator website.

The revisions document provides an overview of the changes made to the Grid Code since the previous issue.

Yours faithfully

Rachel Beaufoy

Frameworks Officer

Code Administrator

Markets

nationalgridESO

THE GRID CODE – ISSUE 6 REVISION 1

INCLUSION OF REVISED SECTIONS

- Glossary Definitions
- Operating Code 2
- Data Registration Code
- General Conditions

SUMMARY OF CHANGES

The changes arise from the implementation of modifications proposed in the following Consultation Paper:

- **GC0130 – OC2 Change for simplifying 'output useable' data submission and utilising REMIT data**

Summary of GC0130 and Impact:

This modification is responding to feedback from the industry on the current use of the OC2 process to provide Generator Output Useable (GOU) and outage data. The proposed solution will simplify the data submission process such that Generators/Interconnectors will be able to submit OC2 data either via REMIT, or a new National Grid Electricity System Operator (NGESO) platform (previously TOGA-GOAMP), removing duplication for many. Changes to the OC2 requirements will lead to improved data quality on which calculations of Margin and Surplus will be made and reported to industry.

Impact:

Low: Most Generators who already meet REMIT obligations would no longer also need to submit data to the NGESO platform. Generators/Interconnectors can submit data via the new NGESO platform if they do not have REMIT obligations.

The process of moving Generators to either the new NGESO platform or REMIT system is a separate process which is being managed outside the Grid Code

When OC2 is updated, data can be submitted by Generators either via REMIT or the new NGESO platform. This will create simplifications for both NGESO and Generators.

THE GRID CODE

ISSUE 6

REVISION 1

18 March 2021

GLOSSARY & DEFINITIONS
(GD)

GD.1 In the Grid Code the following words and expressions shall, unless the subject matter or context otherwise requires or is inconsistent therewith, bear the following meanings:

Access Group	A group of **Connection Points** within which a **User** declares under the **Planning Code** (a) An interconnection and/or (b) A need to redistribute **Demand** between those **Connection Points** either pre-fault or post-fault Where a single **Connection Point** does not form part of an **Access Group** in accordance with the above, that single **Connection Point** shall be considered to be an **Access Group** in its own right.
Access Period	A period of time in respect of which each **Transmission Interface Circuit** is to be assessed as whether or not it is capable of being maintained as derived in accordance with PC.A.4.1.4. The period shall commence and end on specified calendar weeks.
Act	The Electricity Act 1989 (as amended by the Utilities Act 2000 and the Energy Act 2004).
Active Energy	The electrical energy produced, flowing or supplied by an electric circuit during a time interval, being the integral with respect to time of the instantaneous power, measured in units of watt-hours or standard multiples thereof, ie: 1000 Wh = 1 kWh 1000 kWh = 1 MWh 1000 MWh = 1 GWh 1000 GWh = 1 TWh
Active Power	The product of voltage and the in-phase component of alternating current measured in units of watts and standard multiples thereof, ie: 1000 Watts = 1 kW 1000 kW = 1 MW 1000 MW = 1 GW 1000 GW = 1 TW

Additional BM Unit	Has the meaning as set out in the **BSC**
Affiliate	In relation to any person, any holding company or subsidiary of such person or any subsidiary of a holding company of such person, in each case within the meaning of Section 736, 736A and 736B of the Companies Act 1985 as substituted by section 144 of the Companies Act 1989 and, if that latter section is not in force at the **Transfer Date**, as if such section were in force at such date.
AF Rules	Has the meaning given to "allocation framework" in section 13(2) of the Energy Act 2013.
Agency	As defined in **The Company's Transmission Licence.**
Aggregator	A **BM Participant** who controls one or more **Additional BM Units** or **Secondary BM Units**.
Aggregator Impact Matrix	Defined for an **Additional BM Unit** or a **Secondary BM Unit**. Provides data allowing **The Company** to model the result of a **Bid-Offer Acceptance** on each of the **Grid Supply Points** within the **GSP Group** over which the **Additional BM Unit** or **Secondary BM Unit** is defined.
Alternate Member	Shall mean an alternate member for the **Panel Members** elected or appointed in accordance with this GR.7.2(a) or (b).
Ancillary Service	A **System Ancillary Service** and/or a **Commercial Ancillary Service**, as the case may be. An **Ancillary Service** may include one or more **Demand Response Services**.
Ancillary Services Agreement	An agreement between a **User** and **The Company** for the payment by **The Company** to that **User** in respect of the provision by such **User** of **Ancillary Services**.
Annual Average Cold Spell Conditions or **ACS Conditions**	A particular combination of weather elements which gives rise to a level of peak **Demand** within a **Financial Year** which has a 50% chance of being exceeded as a result of weather variation alone.
Apparatus	Other than in **OC8**, means all equipment in which electrical conductors are used, supported or of which they may form a part. In **OC8**, it means **High Voltage** electrical circuits forming part of a **System** on which **Safety Precautions** may be applied to allow work and/or testing to be carried out on a **System**.
Apparent Power	The product of voltage and of alternating current measured in units of voltamperes and standard multiples thereof, ie: 1000 VA = 1 kVA 1000 kVA = 1 MVA
Approved Fast Track Proposal	Has the meaning given in GR.26.7, provided that no objection is received pursuant to GR.26.12.

Approved Grid Code Self-Governance Proposal	Has the meaning given in GR.24.10.
Approved Modification	Has the meaning given in GR.22.7
Authorised Certifier	An entity that issues **Equipment Certificates** and **Power Generating Module Documents** and whose accreditation is given by the national affiliate of the European cooperation for Accreditation ('EA'), established in accordance with Regulation (EC) No 765/2008 of the European Parliament and of the Council (1).
Authorised Electricity Operator	Any person (other than **The Company**) who is authorised under the **Act** to generate, participate in the transmission of, distribute or supply electricity which shall include any **Interconnector Owner** or **Interconnector User**.
Authority-Led Modification	A **Grid Code Modification Proposal** in respect of a **Significant Code Review**, raised by the Authority pursuant to GR.17
Authority-Led Modification Report	Has the meaning given in GR.17.4.
Authority for Access	An authority which grants the holder the right to unaccompanied access to sites containing exposed **HV** conductors.
Authority, The	The **Authority** established by section 1 (1) of the Utilities Act 2000.
Automatic Voltage Regulator or **AVR**	The continuously acting automatic equipment controlling the terminal voltage of a **Synchronous Generating Unit** or **Synchronous Power Generating Module** by comparing the actual terminal voltage with a reference value and controlling by appropriate means the output of an **Exciter**, depending on the deviations.
Auxiliaries	Any item of **Plant** and/or **Apparatus** not directly a part of the boiler plant or **Power Generating Module** or **Generating Unit** or **DC Converter** or **HVDC Equipment** or **Power Park Module**, but required for the boiler plant's or **Power Generating Module's** or **Generating Unit's** or **DC Converter's** or **HVDC Equipment's** or **Power Park Module's** functional operation.
Auxiliary Diesel Engine	A diesel engine driving a **Power Generating Module** or **Generating Unit** which can supply a **Unit Board** or **Station Board**, which can start without an electrical power supply from outside the **Power Station** within which it is situated.
Auxiliary Gas Turbine	A **Gas Turbine Unit**, which can supply a **Unit Board** or **Station Board**, which can start without an electrical power supply from outside the **Power Station** within which it is situated.
Average Conditions	That combination of weather elements within a period of time which is the average of the observed values of those weather elements during equivalent periods over many years (sometimes referred to as normal weather).
Back-Up Protection	A **Protection** system which will operate when a system fault is not cleared by other **Protection**.

Balancing and Settlement Code or **BSC**	The code of that title as from time to time amended.
Balancing Code or **BC**	That portion of the Grid Code which specifies the **Balancing Mechanism** process.
Balancing Mechanism	Has the meaning set out in **The Company's Transmission Licence**
Balancing Mechanism Reporting Agent or **BMRA**	Has the meaning set out in the **BSC**.
Balancing Mechanism Reporting Service or **BMRS**	Has the meaning set out in the **BSC**.
Balancing Principles Statement	A statement prepared by **The Company** in accordance with Condition C16 of **The Company's Transmission Licence**.
Baseline Forecast	Has the meaning given to the term 'baseline forecast' in Section G of the **BSC**.
Bid-Offer Acceptance	(a) A communication issued by **The Company** in accordance with BC2.7; or (b) an **Emergency Instruction** to the extent provided for in BC2.9.2.3.
Bid-Offer Data	Has the meaning set out in the **BSC**.
Bilateral Agreement	Has the meaning set out in the **CUSC**.
Black Start	The procedure necessary for a recovery from a **Total Shutdown** or **Partial Shutdown**.
Black Start Capability	In the case of a **Black Start Station**, is the ability for at least one of its **Gensets** to **Start-Up** from **Shutdown** and to energise a part of the **System** and be **Synchronised** to the **System** upon instruction from **The Company**, within two hours, without an external electrical power supply. In the case of a **Black Start HVDC System** is the ability of an **HVDC System** to **Start-Up** from **Shutdown** and to energise a part of the **System** and be **Synchronised** to the **System** upon instruction from **The Company**, within two hours, without an external electrical power supply from the **GB Synchronous Area**.
Black Start Contract	An agreement between a **Black Start Service Provider** and **The Company** under which the **Black Start Service Provider** provides **Black Start Capability** and other associated services;
Black Start HVDC System	An **HVDC System** or **DC Converter Station** which are registered, pursuant to the **Bilateral Agreement** with a **User**, as having a **Black Start Capability**.
Black Start HVDC Test	A **Black Start Test** carried out by an **HVDC System Owner** or **DC Converter Station Owner** with a **Black Start HVDC System** while the **Black Start HVDC System** is disconnected from all external electrical power supplies from the **GB Synchronous Area**.
Black Start Service Provider	A **Generator** with a **Black Start Station** or an **HVDC System Owner** or **DC Converter Station Owner** with a **Black Start HVDC System**.

Black Start Stations	**Power Stations** which are registered, pursuant to the **Bilateral Agreement** with a **User**, as having a **Black Start Capability**.
Black Start Station Test	**A Black Start Test** carried out by a **Generator** with a **Black Start Station** while the **Black Start Station** is disconnected from all external electrical power supplies from the **GB Synchronous Area**.
Black Start Test	A **Black Start Test** carried out by a **Black Start Service Provider** on the instructions of **The Company**, in order to demonstrate that a **Black Start Station** or a **Black Start HVDC System** has a **Black Start Capability**. For the avoidance of doubt, a **Black Start Test** could comprise a **Black Start Station Test**, a **Black Start Unit Test** or **Black Start HVDC Test.**
Black Start Unit Test	A **Black Start Test** carried out on a **Generating Unit** or a **CCGT Unit** or a **Power Generating Module**, as the case may be, at a **Black Start Station** while the **Black Start Station** remains connected to an external alternating current electrical supply.
Block Loading Capability	The incremental **Active Power** steps, from no load to **Rated MW**, which a **Generating Unit** or **Power Generating Module** or **Power Park Module** or **HVDC System** or **DC Converter Station** can instantaneously supply without causing it to trip or go outside the **Frequency** range of 47.5Hz – 52Hz (or an otherwise agreed **Frequency** range). The time between each incremental step shall also be provided.
BM Participant	A person who is responsible for and controls one or more **BM Units** or where a **Bilateral Agreement** specifies that a **User** is required to be treated as a **BM Participant** for the purposes of the Grid Code. For the avoidance of doubt, it does not imply that they must be active in the **Balancing Mechanism**.
BM Unit	Has the meaning set out in the **BSC**, except that for the purposes of the Grid Code the reference to "Party" in the **BSC** shall be a reference to **User**.
BM Unit Data	The collection of parameters associated with each **BM Unit**, as described in Appendix 1 of **BC1**.
Boiler Time Constant	Determined at **Registered Capacity** or **Maximum Capacity** (as applicable), the boiler time constant will be construed in accordance with the principles of the IEEE Committee Report "Dynamic Models for Steam and Hydro Turbines in Power System Studies" published in 1973 which apply to such phrase.
British Standards or **BS**	Those standards and specifications approved by the British Standards Institution.
BSCCo	Has the meaning set out in the **BSC**.
BSC Panel	Has meaning set out for "Panel" in the **BSC**.
Black Start Unit Test	A **Black Start Test** carried out on a **Generating Unit** or a **CCGT Unit** or a **Power Generating Module**, as the case may be, at a **Black Start Station** while the **Black Start Station** remains connected to an external alternating current electrical supply.
Business Day	Any week day (other than a Saturday) on which banks are open for domestic business in the City of London.

Cancellation of National Electricity Transmission System Warning	The notification given to **Users** when a **National Electricity Transmission System Warning** is cancelled.
Capacity Market Documents	The **Capacity Market Rules**, The **Electricity Capacity Regulations** 2014 and any other Regulations made under Chapter 3 of Part 2 of the Energy Act 2013 which are in force from time to time.
Capacity Market Rules	The rules made under section 34 of the Energy Act 2013 as modified from time to time in accordance with that section and The Electricity Capacity Regulations 2014.
Cascade Hydro Scheme	Two or more hydro-electric **Generating Units**, owned or controlled by the same **Generator**, which are located in the same water catchment area and are at different ordnance datums and which depend upon a common source of water for their operation, known as: (a) Moriston (b) Killin I Garry (d) Conon (e) Clunie (f) Beauly which will comprise more than one **Power Station**.
Cascade Hydro Scheme Matrix	The matrix described in Appendix 1 to **BC1** under the heading **Cascade Hydro Scheme Matrix**.
Category 1 Intertripping Scheme	A **System to Generator Operational Intertripping Scheme** arising from a Variation to Connection Design following a request from the relevant **User** which is consistent with the criteria specified in the **Security and Quality of Supply Standard**.
Category 2 Intertripping Scheme	A System to Generator Operational Intertripping Scheme which is:- (i) required to alleviate an overload on a circuit which connects the **Group** containing the **User's Connection Site** to the **National Electricity Transmission System**; and (ii) installed in accordance with the requirements of the planning criteria of the **Security and Quality of Supply Standard** in order that measures can be taken to permit maintenance access for each transmission circuit and for such measures to be economically justified, and the operation of which results in a reduction in **Active Power** on the overloaded circuits which connect the **User's Connection Site** to the rest of the **National Electricity Transmission System** which is equal to the reduction in **Active Power** from the **Connection Site** (once any system losses or third party system effects are discounted).
Category 3 Intertripping Scheme	A **System to Generator Operational Intertripping Scheme** which, where agreed by **The Company** and the **User**, is installed to alleviate an overload on, and as an alternative to, the reinforcement of a third party system, such as the **Distribution System** of a **Public Distribution System Operator**.

Category 4 Intertripping Scheme	A **System to Generator Operational Intertripping Scheme** installed to enable the disconnection of the **Connection Site** from the **National Electricity Transmission System** in a controlled and efficient manner in order to facilitate the timely restoration of the **National Electricity Transmission System**.
Caution Notice	A notice conveying a warning against interference.
CENELEC	European Committee for Electrotechnical Standardisation.
Citizens Advice	Means the National Association of Citizens Advice Bureaux.
Citizens Advice Scotland	Means the Scottish Association of Citizens Advice Bureaux.
CfD Counterparty	A person designated as a "CfD counterparty" under section 7(1) of the Energy Act 2013.
CfD Documents	The **AF Rules**, The Contracts for Difference (Allocation) Regulations 2014, The Contracts for Difference (Definition of Eligible Generator) Regulations 2014 and The Contracts for Difference (Electricity Supplier Obligations) Regulations 2014 and any other regulations made under Chapter 2 of Part 2 of the Energy Act 2013 which are in force from time to time.
CfD Settlement Services Provider	means any person: (i) appointed for the time being and from time to time by a **CfD Counterparty**; or (ii) who is designated by virtue of Section C1.2.1B of the Balancing and Settlement Code, in either case to carry out any of the CFD settlement activities (or any successor entity performing CFD settlement activities).
CCGT Module Matrix	The matrix described in Appendix 1 to BC1 under the heading **CCGT Module Matrix**.
CCGT Module Planning Matrix	A matrix in the form set out in Appendix 3 of OC2 showing the combination of **CCGT Units** within a **CCGT Module** which would be running in relation to any given MW output.
Closed Distribution System or **CDSO**	A distribution system classified pursuant to Article 28 of Directive 2009/72/EC as a **Closed Distribution System** by the **Authority** which distributes electricity within a geographically confined industrial, commercial or shared services site and does not supply household **Customers**, without prejudice to incidental use by a small number of households located within the area served by the **System** and with employment or similar associations with the owner of the **System**.
CM Administrative Parties	The **Secretary of State**, the **CM Settlement Body**, and any **CM Settlement Services Provider**.
CM Settlement Body	the Electricity Settlements Company Ltd or such other person as may from time to time be appointed as Settlement Body under regulation 80 of the Electricity Capacity Regulations 2014.

CM Settlement Services Provider	any person with whom the **CM Settlement Body** has entered into a contract to provide services to it in relation to the performance of its functions under the **Capacity Market Documents**.
Code Administration Code of Practice	Means the code of practice approved by the **Authority** and: (a) developed and maintained by the code administrators in existence from time to time; and (b) amended subject to the **Authority's** approval from time to time; and (c) re-published from time to time;
Code Administrator	Means **The Company** carrying out the role of **Code Administrator** in accordance with the General Conditions.
Combined Cycle Gas Turbine Module or **CCGT Module**	A collection of **Generating Units** (registered as a **CCGT Module** (which could be within a **Power Generating Module**) under the **PC**) comprising one or more **Gas Turbine Units** (or other gas based engine units) and one or more **Steam Units** where, in normal operation, the waste heat from the **Gas Turbines** is passed to the water/steam system of the associated **Steam Unit** or **Steam Units** and where the component units within the **CCGT Module** are directly connected by steam or hot gas lines which enable those units to contribute to the efficiency of the combined cycle operation of the **CCGT Module**.
Combined Cycle Gas Turbine Unit or **CCGT Unit**	A **Generating Unit** within a **CCGT Module**.
Commercial Ancillary Services	**Ancillary Services**, other than **System Ancillary Services**, utilised by **The Company** in operating the **Total System** if a **User** (or other person such as a **Demand Response Provider**) has agreed to provide them under an **Ancillary Services Agreement** or under a **Bilateral Agreement** with payment being dealt with under an **Ancillary Services Agreement** or in the case of **Externally Interconnected System Operators** or **Interconnector Users**, under any other agreement (and in the case of **Externally Interconnected System Operators** and **Interconnector Users** includes **Ancillary Services** equivalent to or similar to **System Ancillary Services**).
Commercial Boundary	Has the meaning set out in the **CUSC**
Committed Level	The expected **Active Power** output from a **BM Unit** after accepting a **Bid-Offer Acceptance** or **RR Instruction** or a combination of **Bid-Offer Acceptances** and **RR Instructions**.
Committed Project Planning Data	Data relating to a **User Development** once the offer for a **CUSC Contract** is accepted.
Common Collection Busbar	A busbar within a **Power Park Module** to which the higher voltage side of two or more **Power Park Unit** generator transformers are connected.

Completion Date	Has the meaning set out in the **Bilateral Agreement** with each **User** to that term or in the absence of that term to such other term reflecting the date when a **User** is expected to connect to or start using the **National Electricity Transmission System**. In the case of an **Embedded Medium Power Station** or **Embedded DC Converter Station** or **Embedded HVDC System** having a similar meaning in relation to the **Network Operator's System** as set out in the **Embedded Development Agreement**.
Complex	A **Connection Site** together with the associated **Power Station** and/or **Network Operator** substation and/or associated **Plant** and/or **Apparatus**, as appropriate.
Compliance Processes or **CP**	That portion of the Grid Code which is identified as the **Compliance Processes**.
Compliance Statement	A statement completed by the relevant **User** confirming compliance with each of the relevant Grid Code provisions, and the supporting evidence in respect of such compliance, of its: **Generating Unit(s)**; or, **Power Generating Modules** (including **DC Connected Power Park Modules** and/or **Electricity Storage Modules**); or, **CCGT Module(s)**; or, **Power Park Module(s)**; or, **DC Converter(s)**; or **HVDC Systems**; or **Plant** and **Apparatus** at an **EU Grid Supply Point** owned or operated by a **Network Operator**; or **Network Operator's** entire distribution **System** where such **Network Operator's** distribution **System** comprises solely of **Plant** and **Apparatus** procured on or after 7 September 2018 and was connected to the **National Electricity Transmission System** on or after 18 August 2019. In this case, all connections to the **National Electricity Transmission System** would comprise only of **EU Grid Supply Points**; or **Plant** and **Apparatus** at an **EU Grid Supply Point** owned or operated by a **Non-Embedded Customer** where such **Non-Embedded Customer** is defined as an **EU Code User**; In the form provided by **The Company** to the relevant **User** or another format as agreed between the **User** and **The Company**.
Configuration 1 AC Connected Offshore Power Park Module	One or more **Offshore Power Park Modules** that are connected to an AC **Offshore Transmission System** and that AC **Offshore Transmission System** is connected to only one **Onshore** substation and which has one or more **Transmission Interface Points**.
Configuration 2 AC Connected Offshore Power Park Module	One or more **Offshore Power Park Modules** that are connected to a meshed AC **Offshore Transmission System** and that **AC Offshore Transmission System** is connected to two or more **Onshore** substations at its **Transmission Interface Points**.

Configuration 1 DC Connected Power Park Module	One or more **DC Connected Power Park Modules** that are connected to an **HVDC System** or **Transmission DC Converter** and that **HVDC System** or **Transmission DC Converter** is connected to only one **Onshore** substation and which has one or more **Transmission Interface Points**.
Configuration 2 DC Connected Power Park Module	One or more **DC Connected Power Park Modules** that are connected to an **HVDC System** or **Transmission DC Converter** and that **HVDC System** or **Transmission DC Converter** is connected to more than one **Onshore** substation at its **Transmission Interface Points**.
Connection Conditions or **CC**	That portion of the Grid Code which is identified as the **Connection Conditions** being applicable to **GB Code Users**.
Connection Entry Capacity	Has the meaning set out in the **CUSC**.
Connected Planning Data	Data which replaces data containing estimated values assumed for planning purposes by validated actual values and updated estimates for the future and by updated forecasts for **Forecast Data** items such as **Demand**.
Connection Point	A **Grid Supply Point** or **Grid Entry Point**, as the case may be.
Connection Site	A **Transmission Site** or **User Site**, as the case may be.
Construction Agreement	Has the meaning set out in the **CUSC**
Consumer Representative	Means the person appointed by the **Citizens Advice** or the **Citizens Advice Scotland** (or any successor body) representing all categories of customers, appointed in accordance with GR.4.2(b)
Contingency Reserve	The margin of generation over forecast **Demand** which is required in the period from 24 hours ahead down to real time to cover against uncertainties in **Large Power Station** availability and against both weather forecast and **Demand** forecast errors.
Control Calls	A telephone call whose destination and/or origin is a key on the control desk telephone keyboard at a **Control Centre** and which, for the purpose of **Control Telephony**, has the right to exercise priority over (ie. disconnect) a call of a lower status.
Control Centre	A location used for the purpose of control and operation of the **National Electricity Transmission System** or **DC Converter Station** owner's **System** or **HVDC System Owner's System** or a **User System** other than a **Generator's System** or an **External System**.
Control Engineer	A person nominated by the relevant party for the control of its **Plant** and **Apparatus**.
Control Person	The term used as an alternative to "**Safety Co-ordinator**" on the **Site Responsibility Schedule** only.
Control Phase	The **Control Phase** follows on from the **Programming Phase** and covers the period down to real time.

Control Point	The point from which:- (a) A **Non-Embedded Customer's Plant** and **Apparatus** is controlled; or (b) A **BM Unit** at a **Large Power Station** or at a **Medium Power Station** or representing a **Cascade Hydro Scheme** or with a **Demand Capacity** with a magnitude of: (i) 50MW or more in **NGET's Transmission Area**; or (ii) 30MW or more in **SPT's Transmission Area**; or (iii) 10MW or more in **SHETL's Transmission Area**, (iv) 10MW or more which is connected to an **Offshore Transmission System** is physically controlled by a **BM Participant**; or (c) In the case of any other **BM Unit** or **Generating Unit** (which could be part of a **Power Generating Module**), data submission is co-ordinated for a **BM Participant** and instructions are received from **The Company**, as the case may be. For a **Generator**, this will normally be at a **Power Station** but may be at an alternative location agreed with **The Company**. In the case of a **DC Converter Station** or **HVDC System**, the **Control Point** will be at a location agreed with **The Company**. In the case of a **BM Unit** of an **Interconnector User**, the **Control Point** will be the **Control Centre** of the relevant **Externally Interconnected System Operator**.
Control Telephony	The principal method by which a **User's Responsible Engineer/Operator** and **The Company's Control Engineer(s)** speak to one another for the purposes of control of the **Total System** in both normal and emergency operating conditions.
Core Industry Document	As defined in the **Transmission Licence**
Core Industry Document Owner	In relation to a **Core Industry Document**, the body(ies) or entity(ies) responsible for the management and operation of procedures for making changes to such document
CUSC	Has the meaning set out in **The Company's Transmission Licence**
CUSC Contract	One or more of the following agreements as envisaged in Standard Condition C1 of **The Company's Transmission Licence**: (a) the **CUSC Framework Agreement**; (b) a **Bilateral Agreement**; (c) a **Construction Agreement** or a variation to an existing **Bilateral Agreement** and/or **Construction Agreement**;
CUSC Framework Agreement	Has the meaning set out in **The Company's Transmission Licence**.
CUSC Party	As defined in the **The Company's** Transmission Licence and "CUSC Parties" shall be construed accordingly.

Customer	A person to whom electrical power is provided (whether or not he is the same person as the person who provides the electrical power).
Customer Demand Management	Reducing the supply of electricity to a **Customer** or disconnecting a **Customer** in a manner agreed for commercial purposes between a **Supplier** and its **Customer**.
Customer Demand Management Notification Level	The level above which a **Supplier** has to notify **The Company** of its proposed or achieved use of **Customer Demand Management** which is 12 MW in England and Wales and 5 MW in Scotland.
Customer Generating Plant	A **Power Station** or **Generating Unit** or **Power Generating Module** of a **Customer** to the extent that it operates the same exclusively to supply all or part of its own electricity requirements, and does not export electrical power to any part of the **Total System**.
Data Registration Code or **DRC**	That portion of the Grid Code which is identified as the **Data Registration Code**.
Data Validation, Consistency and Defaulting Rules	The rules relating to validity and consistency of data, and default data to be applied, in relation to data submitted under the **Balancing Codes**, to be applied by **The Company** under the **Grid Code** as set out in the document "Data Validation, Consistency and Defaulting Rules" - Issue 8, dated 25th January 2012. The document is available on the National Grid website or upon request from **The Company**.
DC Connected Power Park Module	A **Power Park Module** that is connected to one or more **HVDC Interface Points**.
DC Converter	Any **Onshore DC Converter** or **Offshore DC Converter** as applicable to **GB Code User's**.
DC Converter Station	An installation comprising one or more **Onshore DC Converters** connecting a direct current interconnector: to the **National Electricity Transmission System**; or, (if the installation has a rating of 50MW or more) to a **User System**, and it shall form part of the **External Interconnection** to which it relates.
DC Network	All items of **Plant** and **Apparatus** connected together on the direct current side of a **DC Converter** or **HVDC System**.
DCUSA	The Distribution Connection and Use of System Agreement approved by the **Authority** and required to be maintained in force by each **Electricity Distribution Licence** holder.
Defence Service Provider	A **User** with a legal or contractual obligation to provide a service contributing to one or several measures of the **System Defence Plan.**
De-Load	The condition in which a **Genset** has reduced or is not delivering electrical power to the **System** to which it is **Synchronised**.
Δf	Deviation from **Target Frequency**
Demand	The demand of MW and MVAr of electricity (i.e. both **Active** and **Reactive Power**), unless otherwise stated.

Demand Aggregation	A process where one or more **Demand Facilities** or **Closed Distribution Systems** can be controlled by a **Demand Response Provider** either as a single facility or **Closed Distribution System** for the purposes of offering one or more **Demand Response Services.**
Demand Capacity	Has the meaning as set out in the **BSC**.
Demand Control	Any or all of the following methods of achieving a **Demand** reduction: (a) **Customer** voltage reduction initiated by **Network Operators** (other than following an instruction from **The Company**); (b) **Customer Demand** reduction by **Disconnection** initiated by **Network Operators** (other than following an instruction from **The Company**); (c) **Demand** reduction instructed by **The Company**; (d) automatic low **Frequency Demand Disconnection**; (e) emergency manual **Demand Disconnection**.
Demand Control Notification Level	The level above which a **Network Operator** has to notify **The Company** of its proposed or achieved use of **Demand Control** which is 12 MW in England and Wales and 5 MW in Scotland.
Demand Facility	A facility which consumes electrical energy and is connected at one or more **Grid Supply Points** to the **National Electricity Transmission System** or connection points to a **Network Operator's System**. A **Network Operator's System** and/or auxiliary supplies of a **Power Generating Module** do no constitute a **Demand Facility**.
Demand Facility Owner	A person who owns or operates one or more **Demand Units** within a **Demand Facility**. A **Demand Facility Owner** who owns or operates a **Demand Facility** which is directed connected to the **Transmission System** shall be treated as a **Non-Embedded Customer**.
Demand Response Active Power Control	**Demand** within a **Demand Facility** or **Closed Distribution System** that is available for modulation by **The Company** or **Network Operator** or **Relevant Transmission Licensee**, which results in an **Active Power** modification.
Demand Response Provider	A party (other than **The Company**) who owns, operates, controls or manages **Main Plant and Apparatus** (excluding storage equipment) which was first connected to the **Total System** on or after 18 August 2019 and who had placed **Purchase Contracts** for its **Main Plant and Apparatus** on or after 7 September 2018 or is the subject of a **Substantial Modification** on or after 18 August 2019 and has an agreement with **The Company** to provide a **Demand Response Service**(s). The party may be one or more **Customers**, a **Network Operator** or **Non-Embedded Customer** or **EU Code User** contracting bilaterally with **The Company** for the provision of services, or may be a third party providing **Demand Aggregation** from many individual **Customers**.
Demand Response Reactive Power Control	A **Demand Response Service** derived from **Reactive Power** or **Reactive Power** compensation devices in a **Demand Facility** or **Closed Distribution System** that are available for modulation by **The Company** or **Network Operator** or **Relevant Transmission Licensee**.
Demand Response Transmission Constraint Management	A **Demand Response Service** derived from **Demand** within a **Demand Facility** or **Closed Distribution System** that is available for modulation by **The Company** or **Network Operator** or **Relevant Transmission Licensee** to manage transmission constraints within the **System**.

Demand Response Service	A **Demand Response Service** includes one of more of the following services: (a) **Demand Response Active Power Control**; (b) **Demand Response Reactive Power Control**; (c) **Demand Response Transmission Constraint Management**; (d) **Demand Response System Frequency Control**; (e) **Demand Response Very Fast Active Power Control**. The above **Demand Response Services** are not exclusive and do not preclude **Demand Response Providers** from negotiating other services for demand response capability with **The Company**. Where such services are negotiated they would still be treated as a **Demand Response Service**.
Demand Response Services Code (DRSC)	That portion of the Grid Code which is identified as the **Demand Response Services Code** being applicable to **Demand Response Providers**.
Demand Response System Frequency Control	A **Demand Response Service** derived from a **Demand** within one or more **Demand Facilities** or **Closed Distribution Systems** that is available for the reduction or increase in response to **Frequency** fluctuations, made by an autonomous response from those **Demand Facilities** or **Closed Distribution Systems** to diminish these fluctuations.
Demand Response Unit Document (DRUD)	A document, issued either by the **Non-Embedded Customer**, **Demand Facility Owner** or the **CDSO** to **The Company** or the **Network Operator** (as the case may be) for **Demand Units** with demand response and providing a **Demand Response Service** which confirms the compliance of the **Demand Unit** with the technical requirements set out in the Grid Code and provides the necessary data and statements, including a statement of compliance.
Demand Response Very Fast Active Power Control	A **Demand Response Service** derived from **a Demand** within a **Demand Facility** or **Closed Distribution System** that can be modulated very fast in response to a **Frequency** deviation, which results in a very fast **Active Power** modification.
Demand Unit	An indivisible set of installations containing equipment which can be actively controlled at one or more sites by a **Demand Response Provider**, **Demand Facility Owner**, **CDSO** or by a **Non Embedded Customer**, either individually or commonly as part of **Demand Aggregation** through a third party who has agreed to provide **Demand Response Services**.
Designed Minimum Operating Level	The output (in whole MW) below which a **Genset** or a **DC Converter** at a **DC Converter Station** (in any of its operating configurations) has no **High Frequency Response** capability.
De-Synchronise	(a) The act of taking a **Power Generating Module** (including a **DC Connected Power Park Module**), **Generating Unit**, **Power Park Module**, **HVDC System** or **DC Converter** off a **System** to which it has been **Synchronised**, by opening any connecting circuit breaker; or (b) The act of ceasing to consume electricity at an importing **BM Unit**; and the term "**De-Synchronising**" shall be construed accordingly.
De-synchronised Island(s)	Has the meaning set out in OC9.5.1(a).
Detailed Planning Data	Detailed additional data which **The Company** requires under the **PC** in support of **Standard Planning Data**, comprising **DPD I** and **DPD II**.
Detailed Planning Data Category I or **DPD I**	The **Detailed Planning Data** categorised as such in the **DRC**, and submitted in accordance with PC.4.4.2 or PC.4.4.4 as applicable.

Detailed Planning Data Category II or **DPD II**	The **Detailed Planning Data** categorised as such in the **DRC**, and submitted in accordance with PC.4.4.2 or PC.4.4.4 as applicable.
Disconnection	The physical separation of **Users** (or **Customers**) from the **National Electricity Transmission System** or a **User System** as the case may be.
Discrimination	The quality where a relay or protective system is enabled to pick out and cause to be disconnected only the faulty **Apparatus**.
Disputes Resolution Procedure	The procedure described in the **CUSC** relating to disputes resolution.
Distribution Code	The distribution code required to be drawn up by each **Electricity Distribution Licence** holder and approved by the **Authority**, as from time to time revised with the approval of the **Authority**.
Droop	The ratio of the per unit steady state change in speed (or **Frequency**), to the per unit steady state change in **Active Power** output. Whilst not mandatory, it is often common practice to express **Droop** in percentage terms.
Dynamic Parameters	Those parameters listed in Appendix 1 to **BC1** under the heading **BM Unit Data** – **Dynamic Parameters**.
E&W Offshore Transmission System	An **Offshore Transmission System** with an **Interface Point** in England and Wales.
E&W Offshore Transmission Licensee	A person who owns or operates an **E&W Offshore Transmission System** pursuant to a **Transmission Licence**.
E&W Transmission System	Collectively **NGET's Transmission System** and any **E&W Offshore Transmission Systems**.
E&W User	A **User** in **England** and **Wales** or any **Offshore User** who owns or operates **Plant** and/or **Apparatus** connected (or which will at the **OTSUA Transfer Time** be connected) to an **E&W Offshore Transmission System**.
Earth Fault Factor	At a selected location of a three-phase **System** (generally the point of installation of equipment) and for a given **System** configuration, the ratio of the highest root mean square phase-to-earth power **Frequency** voltage on a sound phase during a fault to earth (affecting one or more phases at any point) to the root mean square phase-to-earth power **Frequency** voltage which would be obtained at the selected location without the fault.

Earthing	A way of providing a connection between conductors and earth by an **Earthing Device** which is either: (a) Immobilised and **Locked** in the earthing position. Where the **Earthing Device** is **Locked** with a **Safety Key**, the **Safety Key** must be secured in a **Key Safe** and the **Key Safe Key** must be, where reasonably practicable, given to the authorised site representative of the **Requesting Safety Co-ordinator** and is to be retained in safe custody. Where not reasonably practicable the **Key Safe Key** must be retained by the authorised site representative of the **Implementing Safety Co-ordinator** in safe custody; or (b) maintained and/or secured in position by such other method which must be in accordance with the **Local Safety Instructions** of **NGET** or the **Safety Rules** of the **Relevant Transmission Licensee** or that **User**, as the case may be.
Earthing Device	A means of providing a connection between a conductor and earth being of adequate strength and capability.
Elected Panel Members	Shall mean the following **Panel Members** elected in accordance with GR4.2(a): (a) the representative of the **Suppliers**; (b) the representative of the **Onshore Transmission Licensees**; (c) the representative of the **Offshore Transmission Licensees**; and (d) the representatives of the **Generators**
Electrical Standard	A standard listed in the Annex to the **General Conditions**.
Electricity Council	That body set up under the Electricity Act, 1957.
Electricity Distribution Licence	The licence granted pursuant to Section 6(1) (c) of the **Act**.
Electricity Regulation	As defined in the **Transmission Licence.**
Electricity Storage	The conversion of electrical energy into a form of energy which can be stored, the storing of that energy, and the subsequent reconversion of that energy back into electrical energy.
Electricity Storage Module	Is either one or more **Synchronous Electricity Storage Unit**(s) or **Non-Synchronous Electricity Storage Unit**(s) which could also be part of a **Power Generating Module**. For the avoidance of doubt, **Non-Controllable Electricity Storage Equipment** would not be considered to be classed as an **Electricity Storage Module** or as an **Electricity Storage Unit**.
Electricity Storage Unit	A **Synchronous Electricity Storage Unit** or **Non-Synchronous Electricity Storage Unit**.
Electricity Supply Industry Arbitration Association	The unincorporated members' club of that name formed inter alia to promote the efficient and economic operation of the procedure for the resolution of disputes within the electricity supply industry by means of arbitration or otherwise in accordance with its arbitration rules.
Electricity Supply Licence	The licence granted pursuant to Section 6(1) (d) of the **Act**.

Electromagnetic Compatibility Level	Has the meaning set out in **Engineering Recommendation** G5.
Embedded	Having a direct connection to a **User System** or the **System** of any other **User** to which **Customers** and/or **Power Stations** are connected, such connection being either a direct connection or a connection via a busbar of another **User** or of a **Relevant Transmission Licensee** (but with no other connection to the **National Electricity Transmission System**).
Embedded Development	Has the meaning set out in PC.4.4.3(a).
Embedded Development Agreement	An agreement entered into between a **Network Operator** and an **Embedded Person**, identifying the relevant site of connection to the **Network Operator's System** and setting out other site specific details in relation to that use of the **Network Operator's System**.
Embedded Person	The party responsible for a **Medium Power Station** not subject to a **Bilateral Agreement** or **DC Converter Station** not subject to a **Bilateral Agreement** or **HVDC System** not subject to a **Bilateral Agreement** connected to or proposed to be connected to a **Network Operator's System**.
Emergency Deenergisation Instruction	An **Emergency Instruction** issued by **The Company** to **De-Synchronise** a **Power Generating Module** (including a **DC Connected Power Park Module**), **Generating Unit**, **Power Park Module, HVDC System** or **DC Converter** in circumstances specified in the **CUSC**.
Emergency Instruction	An instruction issued by **The Company** in emergency circumstances, pursuant to BC2.9, to the **Control Point** of a **User**. In the case of such instructions applicable to a **BM Unit**, it may require an action or response which is outside the **Dynamic Parameters** or **Other Relevant Data**, and may include an instruction to trip a **Genset**.
EMR Administrative Parties	Has the meaning given to "administrative parties" in The Electricity Capacity Regulations 2014 and each **CfD Counterparty** and **CfD Settlement Services Provider**.
EMR Documents	The Energy Act 2013, The Electricity Capacity Regulations 2014, the **Capacity Market Rules**, The Contracts for Difference (Allocation) Regulations 2014, The Contracts for Difference (Definition of Eligible Generator) Regulations 2014, The Contracts for Difference (Electricity Supplier Obligations) Regulations 2014, The Electricity Market Reform (General) Regulations 2014, the **AF Rules** and any other regulations or instruments made under Chapter 2 (contracts for difference), Chapter 3 (capacity market) or Chapter 4 (investment contracts) of Part 2 of the Energy Act 2013 which are in force from time to time.
EMR Functions	Has the meaning given to "EMR functions" in Chapter 5 of Part 2 of the Energy Act 2013.
Engineering Recommendations	The documents referred to as such and issued by the Energy Networks Association or the former Electricity Council.
Engineering Recommendation G5	Means Engineering Recommendation G5/5.

Energisation Operational Notification or **EON**	A notification (in respect of **Plant** and **Apparatus** (including **OTSUA**) which is directly connected to the **National Electricity Transmission System**) from **The Company** to a **User** confirming that the **User** can in accordance with the **Bilateral Agreement** and/or **Construction Agreement**, energise such **User's Plant** and **Apparatus** (including **OTSUA**) specified in such notification.
Equipment Certificate	A document issued by an **Authorised Certifier** for equipment used by a **Power Generating Module**, **Demand Unit**, **Network Operators System**, **Non-Embedded Customers System**, **Demand Facility** or **HVDC System**. The **Equipment Certificate** defines the scope of its validity at a national or other level at which a specific value is selected from the range allowed at a European level. For the purpose of replacing specific parts of the compliance process, the **Equipment Certificate** may include models or equivalent information that have been verified against actual test results.
Estimated Registered Data	Those items of **Standard Planning Data** and **Detailed Planning Data** which either upon connection will become **Registered Data**, or which for the purposes of the **Plant** and/or **Apparatus** concerned as at the date of submission are **Registered Data**, but in each case which for the seven succeeding **Financial Years** will be an estimate of what is expected.

EU Code User	A **User** who is any of the following:- (a) A **Generator** in respect of a **Power Generating Module** (excluding a **DC Connected Power Park Module**) or **OTSDUA** (in respect of an AC **Offshore Transmission System**) whose **Main Plant and Apparatus** is connected to the **System** on or after 27 April 2019 and who concluded **Purchase Contracts** for its **Main Plant and Apparatus** on or after 17 May 2018 (b) A **Generator** in respect of any **Type C** or **Type D Power Generating Module** which is the subject of a **Substantial Modification** which is effective on or after 27 April 2019. (c) A **Generator** in respect of any **DC Connected Power Park Module** whose **Main Plant and Apparatus** is connected to the **System** on or after 8 September 2019 and who had concluded **Purchase Contracts** for its **Main Plant and Apparatus** on or after 28 September 2018. (d) A **Generator** in respect of any **DC Connected Power Park Module** which is the subject of a **Substantial Modification** which is effective on or after 8 September 2019. (e) An **HVDC System Owner** or **OTSDUA** (in respect of a DC **Offshore Transmission System** including a **Transmission DC Converter**) whose **Main Plant and Apparatus** is connected to the **System** on or after 8 September 2019 and who had concluded **Purchase Contracts** for its **Main Plant and Apparatus** on or after 28 September 2018. (f) An **HVDC System Owner** or **OTSDUA** (in respect of a DC **Offshore Transmission System** including a **Transmission DC Converter**) whose **HVDC System** or DC **Offshore Transmission System** including a **Transmission DC Converter**) is the subject of a **Substantial Modification** on or after 8 September 2019. (g) A **User** which the **Authority** has determined should be considered as an **EU Code User**. (h) A **Network Operator** whose entire distribution **System** was first connected to the **National Electricity Transmission System** on or after 18 August 2019 and who had placed **Purchase Contracts** for its **Main Plant** and **Apparatus** in respect of its entire distribution **System** on or after 7 September 2018. For the avoidance of doubt, a **Network Operator** will be an **EU Code User** if its entire distribution **System** is connected to the **National Electricity Transmission System** at **EU Grid Supply Points** only. (i) A **Non Embedded Customer** whose **Main Plant and Apparatus** at each **EU Grid Supply Point** was first connected to the **National Electricity Transmission System** on or after 18 August 2019 and who had placed **Purchase Contracts** for its **Main Plant and Apparatus** at each **EU Grid Supply Point** on or after 7 September 2018 or is the subject of a **Substantial Modification** on or after 18 August 2019. (j) A **Storage User** in respect of an **Electricity Storage Module** whose **Main Plant** and **Apparatus** is connected to the **System** on or after 20 May 2020 and who concluded **Purchase Contracts** for its **Main Plant** and **Apparatus** on or after 20 May 2019.

EU Generator	A **Generator** or **OTSDUA** who is also an **EU Code User**.
EU Grid Supply Point	A **Grid Supply Point** where either:- (i) (a) the **Network Operator** or **Non-Embedded Customer** had placed **Purchase Contracts** for all of its **Plant** and **Apparatus** at that **Grid Supply Point** on or after 7 September 2018, and (b) All of the **Network Operator's** or **Non-Embedded Customer's Plant** and **Apparatus** at that **Grid Supply Point** was first connected to the **Transmission System** on or after 18 August 2019; or (ii) the **Network Operator's** or **Non-Embedded Customer's Plant** and **Apparatus** at a **Grid Supply Point** is the subject of a **Substantial Modification** which is effective on or after 18 August 2019.
EU Transparency Availability Data	Such data as **Customers** and **Generators** are required to provide under Articles 7.1(a) and 7.1(b) and Articles 15.1(a), 15.1(b), 15.1(c), 15.1(d) of European Commission Regulation (EU) No. 543/2013 respectively (known as the Transparency Regulation), and which also forms part of **DRC** Schedule 6 (**User**s' Outage Data).
European Compliance Processes or **ECP**	That portion of the Grid Code which is identified as the **European Compliance Processes**.
European Connection Conditions or **ECC**	That portion of the Grid Code which is identified as the **European Connection Conditions** being applicable to **EU Code Users**.
European Regulation (EU) 2016/631	**Commission Regulation (EU) 2016/631** of 14 April 2016 establishing a Network Code on Requirements of Generators.
European Regulation (EU) 2016/1388	**Commission Regulation (EU) 2016/1388** of 17 August 2016 establishing a Network Code on Demand Connection.
European Regulation (EU) 2016/1447	**Commission Regulation (EU) 2016/1447** of 26 August 2016 establishing a network code on requirements for Grid Connection of High Voltage Direct Current Systems and Direct Current-connected Power Park Modules.
European Regulation (EU) 2017/1485	**Commission Regulation (EU) 2017/1485** establishing a guideline on electricity transmission system operation.
European Regulation (EU) 2017/2195	**Commission Regulation (EU) 2017/2195** of 17 December 2017 establishing a guideline on electricity balancing.
European Regulation (EU) 2017/2196	**Commission Regulation (EU) 2017/2196** of 24 November 2017 establishing a network code on emergency and restoration.
European Specification	A common technical specification, a **British Standard** implementing a European standard or a European technical approval. The terms "common technical specification", "European standard" and "European technical approval" shall have the meanings respectively ascribed to them in the **Regulations**.

Event	An unscheduled or unplanned (although it may be anticipated) occurrence on, or relating to, a **System** (including **Embedded Power Stations**) including, without limiting that general description, faults, incidents and breakdowns and adverse weather conditions being experienced.
Exciter	The source of the electrical power providing the field current of a synchronous machine.
Excitation System	The equipment providing the field current of a machine, including all regulating and control elements, as well as field discharge or suppression equipment and protective devices.
Excitation System No-Load Negative Ceiling Voltage	The minimum value of direct voltage that the **Excitation System** is able to provide from its terminals when it is not loaded, which may be zero or a negative value.
Excitation System Nominal Response	Shall have the meaning ascribed to that term in **IEC** 34-16-1:1991 [equivalent to **British Standard BS**4999 Section 116.1: 1992]. The time interval applicable is the first half-second of excitation system voltage response.
Excitation System On-Load Positive Ceiling Voltage	Shall have the meaning ascribed to the term 'Excitation system on load ceiling voltage' in **IEC** 34-16-1:1991[equivalent to **British Standard BS**4999 Section 116.1: 1992].
Excitation System No-Load Positive Ceiling Voltage	Shall have the meaning ascribed to the term 'Excitation system no load ceiling voltage' in **IEC** 34-16-1:1991[equivalent to **British Standard BS**4999 Section 116.1: 1992].
Exemptable	Has the meaning set out in the **CUSC**.
Existing AGR Plant	The following nuclear advanced gas cooled reactor plant (which was commissioned and connected to the **Total System** at the **Transfer Date**):- (a) Dungeness B (b) Hinkley Point B (c) Heysham 1 (d) Heysham 2 (e) Hartlepool (f) Hunterston B (g) Torness

Existing AGR Plant Flexibility Limit	In respect of each **Genset** within each **Existing AGR Plant** which has a safety case enabling it to so operate, 8 (or such lower number which when added to the number of instances of reduction of output as instructed by **The Company** in relation to operation in **Frequency Sensitive Mode** totals 8) instances of flexibility in any calendar year (or such lower or greater number as may be agreed by the Nuclear Installations Inspectorate and notified to **The Company**) for the purpose of assisting in the period of low **System NRAPM** and/or low **Localised NRAPM** provided that in relation to each **Generating Unit** each change in output shall not be required to be to a level where the output of the reactor is less than 80% of the reactor thermal power limit (as notified to **The Company** and which corresponds to the limit of reactor thermal power as contained in the "Operating Rules" or "Identified Operating Instructions" forming part of the safety case agreed with the Nuclear Installations Inspectorate).
Existing Gas Cooled Reactor Plant	Both **Existing Magnox Reactor Plant** and **Existing AGR Plant**.
Existing Magnox Reactor Plant	The following nuclear gas cooled reactor plant (which was commissioned and connected to the **Total System** at the **Transfer Date**):- (a) Calder Hall (b) Chapelcross (c) Dungeness A (d) Hinkley Point A (e) Oldbury-on-Severn (f) Bradwell (g) Sizewell A (h) Wylfa
Export and Import Limits	Those parameters listed in Appendix 1 to **BC1** under the heading **BM Unit Data** – **Export and Import Limits**.
External Interconnection	**Apparatus** for the transmission of electricity to or from the **National Electricity Transmission System** or a **User System** into or out of an **External System**. For the avoidance of doubt, a single **External Interconnection** may comprise several circuits operating in parallel.
External Interconnection Circuit	**Plant** or **Apparatus** which comprises a circuit and which operates in parallel with another circuit and which forms part of the **External Interconnection**.
Externally Interconnected System Operator or **EISO**	A person who operates an **External System** which is connected to the **National Electricity Transmission System** or a **User System** by an **External Interconnection**.
External System	In relation to an **Externally Interconnected System Operator** means the transmission or distribution system which it owns or operates which is located outside **the National Electricity Transmission System Operator Area** any **Apparatus** or **Plant** which connects that system to the **External Interconnection** and which is owned or operated by such **Externally Interconnected System Operator**.

Fast Fault Current	A current delivered by a **Power Park Module** or **HVDC System** during and after a voltage deviation caused by an electrical fault within the **System** with the aim of identifying a fault by network **Protection** systems at the initial stage of the fault, supporting **System** voltage retention at a later stage of the fault and **System** voltage restoration after fault clearance.
Fault Current Interruption Time	The time interval from fault inception until the end of the break time of the circuit breaker (as declared by the manufacturers).
Fault Ride Through	The capability of **Power Generating Modules** (including **DC Connected Power Park Modules**) and **HVDC Systems** to be able to remain connected to the **System** and operate through periods of low voltage at the **Grid Entry Point** or **User System Entry Point** caused by secured faults.
Fast Start	A start by a **Genset** with a **Fast Start Capability**.
Fast Start Capability	The ability of a **Genset** to be **Synchronised** and **Loaded** up to full **Load** within 5 minutes.
Fast Track Criteria	A proposed Grid Code Modification Proposal that, if implemented, (a) would meet the **Self-Governance Criteria**; and (b) is properly a housekeeping modification required as a result of some error or factual change, including but not limited to: (i) updating names or addresses listed in the **Grid Code**; (ii) correcting any minor typographical errors; (iii) correcting formatting and consistency errors, such as paragraph numbering; or (iv) updating out of date references to other documents or paragraphs
Fault Current Interruption Time	The time interval from fault inception until the end of the break time of the circuit breaker (as declared by the manufacturers).
Fault Ride Through	The capability of **Power Generating Modules** (including **DC Connected Power Park Modules**) and **HVDC Systems** to be able to remain connected to the **System** and operate through periods of low voltage at the **Grid Entry Point** or **User System Entry Point** caused by secured faults.
Final Generation Outage Programme	An outage programme as agreed by **The Company** with each **Generator** and each **Interconnector Owner** at various stages through the **Operational Planning Phase** and **Programming Phase** which does not commit the parties to abide by it, but which at various stages will be used as the basis on which **National Electricity Transmission System** outages will be planned.

Final Operational Notification or **FON**	A notification from **The Company** to a **Generator** or **DC Converter Station** owner or **HVDC System Owner** or **Network Operator** or **Non-Embedded Customer** confirming that the **User** has demonstrated compliance: (a) with the Grid Code, (or where they apply, that relevant derogations have been granted), and (b) where applicable, with Appendices F1 to F5 of the **Bilateral Agreement**, in each case in respect of the **Plant** and **Apparatus** specified in such notification.
Final Physical Notification Data	Has the meaning set out in the **BSC**.
Final Report	A report prepared by the **Test Proposer** at the conclusion of a **System Test** for submission to **The Company** (if it did not propose the **System Test**) and other members of the **Test Panel**.
Financial Year	Bears the meaning given in Condition A1 (Definitions and Interpretation) of **The Company's Transmission Licence**.
Fixed Proposed Implementation Date	The proposed date(s) for the implementation of a **Grid Code Modification Proposal** or **Workgroup Alternative Grid Code Modification** such date to be a specific date by reference to an assumed date by which a direction from the **Authority** approving the **Grid Code Modification Proposal** or **Workgroup Alternative Grid Code Modification** is required in order for the **Grid Code Modification Proposal** or any **Workgroup Alternative Grid Code Modification**, if it were approved, to be implemented by the proposed date.
Flicker Severity (Long Term)	A value derived from 12 successive measurements of **Flicker Severity** (**Short Term**) (over a two hour period) and a calculation of the cube root of the mean sum of the cubes of 12 individual measurements, as further set out in **Engineering Recommendation** P28 as current at the **Transfer Date**.
Flicker Severity (Short Term)	A measure of the visual severity of flicker derived from the time series output of a flickermeter over a 10 minute period and as such provides an indication of the risk of **Customer** complaints.
Forecast Data	Those items of **Standard Planning Data** and **Detailed Planning Data** which will always be forecast.
Frequency	The number of alternating current cycles per second (expressed in Hertz) at which a **System** is running.
Frequency Containment Reserves (FCR)	means, in the context of **Balancing Services**, the **Active Power** reserves available to contain **System Frequency** after the occurrence of an imbalance.
Frequency Response Deadband	An interval used intentionally to make the **Frequency** control unresponsive. In the case of mechanical governor systems, the **Frequency Response Deadband** is the same as **Frequency Response Insensitivity**.

Frequency Response Insensitivity	The inherent feature of the control system specified as the minimum magnitude of change in the **Frequency** or input signal that results in a change of output power or output signal.
Frequency Restoration Reserves (FRR)	Means, in the context of **Balancing Services**, the **Active Power** reserves available to restore **System Frequency** to the nominal **Frequency**.
Frequency Sensitive AGR Unit	Each **Generating Unit** in an **Existing AGR Plant** for which the **Generator** has notified **The Company** that it has a safety case agreed with the Nuclear Installations Inspectorate enabling it to operate in **Frequency Sensitive Mode**, to the extent that such unit is within its **Frequency Sensitive AGR Unit Limit**. Each such **Generating Unit** shall be treated as if it were operating in accordance with BC3.5.1 provided that it is complying with its **Frequency Sensitive AGR Unit Limit**.
Frequency Sensitive AGR Unit Limit	In respect of each **Frequency Sensitive AGR Unit**, 8 (or such lower number which when added to the number of instances of flexibility for the purposes of assisting in a period of low **System** or **Localised NRAPM** totals 8) instances of reduction of output in any calendar year as instructed by **The Company** in relation to operation in **Frequency Sensitive Mode** (or such greater number as may be agreed between **The Company** and the **Generator**), for the purpose of assisting with **Frequency** control, provided the level of operation of each **Frequency Sensitive AGR Unit** in **Frequency Sensitive Mode** shall not be outside that agreed by the Nuclear Installations Inspectorate in the relevant safety case.
Frequency Sensitive Mode	A **Genset**, or **Type C Power Generating Module** or **Type D Power Generating Module** or **DC Connected Power Park Module** or **HVDC System** operating mode which will result in **Active Power** output changing, in response to a change in **System Frequency**, in a direction which assists in the recovery to **Target Frequency**, by operating so as to provide **Primary Response** and/or **Secondary Response** and/or **High Frequency Response**.
Fuel Security Code	The document of that title designated as such by the **Secretary of State**, as from time to time amended.
Gas Turbine Unit	A **Generating Unit** driven by a gas turbine (for instance by an aero-engine).
Gas Zone Diagram	A single line diagram showing boundaries of, and interfaces between, gas-insulated **HV Apparatus** modules which comprise part, or the whole, of a substation at a **Connection Site** (or in the case of **OTSDUW Plant and Apparatus**, **Transmission Interface Site**), together with the associated stop valves and gas monitors required for the safe operation of the **National Electricity Transmission System** or the **User System**, as the case may be.
Gate Closure	Has the meaning set out in the **BSC**.

GB Code User	A **User** in respect of:- (a) A **Generator** or **OTSDUA** whose **Main Plant and Apparatus** (excluding a **DC Connected Power Park Module**) is connected to the **System** before 27 April 2019, or who had concluded **Purchase Contracts** for its **Main Plant and Apparatus** before 17 May 2018, or whose **Plant and Apparatus** is not the subject of a **Substantial Modification** which is effective on or after 27 April 2019; or (b) A **DC Converter Station** owner whose **Main Plant and Apparatus** is connected to the **System** before 8 September 2019, or who had concluded **Purchase Contracts** for its **Main Plant and Apparatus** before 28 September 2018, or whose **Plant and Apparatus** is not the subject of a **Substantial Modification** which is effective on or after 8 September 2019; or (c) A **Non-Embedded Customer** whose **Main Plant and Apparatus** was connected to the **National Electricity Transmission System** at a **GB Grid Supply Point** before 18 August 2019 or who had placed **Purchase Contracts** for its **Main Plant and Apparatus** before 7 September 2018 or that **Non-Embedded Customer** is not the subject of a **Substantial Modification** which is effective on or after 18 August 2019; or (d) A **Network Operator** whose entire distribution **System** was connected to the **National Electricity Transmission System** at one or more **GB Grid Supply Points** before 18 August 2019 or who had placed **Purchase Contracts** for its **Main Plant and Apparatus** in respect of its entire distribution **System** before 7 September 2018 or its entire distribution **System** is not the subject of a **Substantial Modification** which is effective on or after 18 August 2019. For the avoidance of doubt, a **Network Operator** would still be classed as a **GB Code User** where its entire distribution **System** was connected to the **National Electricity Transmission System** at one or more **GB Grid Supply Points**, even where that entire distribution **System** may have one or more **EU Grid Supply Points** but still comprises of **GB Grid Supply Points**.
GB Generator	A **Generator,** or **OTSDUA**, who is also a **GB Code User**.
GB Grid Supply Point	A **Grid Supply Point** which is not an **EU Grid Supply Point**.
GB Synchronous Area	The AC power **System** in **Great Britain** which connects **User's**, **Relevant Transmission Licensee's** whose AC **Plant** and **Apparatus** is considered to operate in synchronism with each other at each **Connection Point** or **User System Entry Point** and at the same **System Frequency**.
GCDF	Means the Grid Code Development Forum.
General Conditions or **GC**	That portion of the Grid Code which is identified as the **General Conditions**.
Generating Plant Demand Margin	The difference between **Output Usable** and forecast **Demand**.
Generating Unit	An **Onshore Generating Unit** and/or an **Offshore Generating Unit** which could also be part of a **Power Generating Module**.

Generating Unit Data	The **Physical Notification**, **Export and Import Limits** and **Other Relevant Data** only in respect of each **Generating Unit** (which could be part of a **Power Generating Module**): (a) which forms part of the **BM Unit** which represents that **Cascade Hydro Scheme**; (b) at an **Embedded Exemptable Large Power Station**, where the relevant **Bilateral Agreement** specifies that compliance with **BC1** and/or **BC2** is required: (i) to each **Generating Unit**, or (ii) to each **Power Park Module** where the **Power Station** comprises **Power Park Modules**.
Generation Capacity	Has the meaning set out in the **BSC**.
Generation Planning Parameters	Those parameters listed in Appendix 2 of **OC2**.
Generator	A person who generates electricity or undertakes **Electricity Storage** under licence or exemption under the **Act**, acting in its capacity as a generator in **Great Britain** or **Offshore**. The term **Generator** includes a **EU Generator** and a **GB Generator**.
Generator Performance Chart	A diagram which shows the MW and MVAr capability limits within which a **Generating Unit** will be expected to operate under steady state conditions.
Genset	A **Power Generating Module** (including a **DC Connected Power Park Module** and/or **Electricity Storage Module**), **Generating Unit**, **Power Park Module** or **CCGT Module** at a **Large Power Station** or any **Power Generating Module** (including a **DC Connected Power Park Module**), **Generating Unit**, **Power Park Module** or **CCGT Module** which is directly connected to the **National Electricity Transmission System**.
Good Industry Practice	The exercise of that degree of skill, diligence, prudence and foresight which would reasonably and ordinarily be expected from a skilled and experienced operator engaged in the same type of undertaking under the same or similar circumstances.
Governance Rules or **GR**	That portion of the **Grid Code** which is identified as the **Governance Rules**.
Governor Deadband	An interval used intentionally to make the **frequency** control unresponsive.
Great Britain or **GB**	The landmass of England and Wales and Scotland, including internal waters.
Grid Code Fast Track Proposals	A proposal to modify the **Grid Code** which is raised pursuant to GR.26 and has not yet been approved or rejected by the **Grid Code Review Panel**.
Grid Code Modification Fast Track Report	A report prepared pursuant to GR.26
Grid Code Modification Register	Has the meaning given in GR.13.1.

Grid Code Modification Report	Has the meaning given in GR.22.1.
Grid Code Modification Procedures	The procedures for the modification of the **Grid Code** (including the implementation of **Approved Modifications**) as set out in the **Governance Rules**.
Grid Code Modification Proposal	A proposal to modify the **Grid Code** which is not yet rejected pursuant to GR.15.5 or GR.15.6 and has not yet been implemented.
Grid Code Modification Self- Governance Report	Has the meaning given in GR.24.5
Grid Code Objectives	Means the objectives referred to in Paragraph 1b of Standard Condition C14 of **The Company's Transmission Licence**.
Grid Code Review Panel or **Panel**	The panel with the functions set out in GR.1.2.
Grid Code Review Panel Recommendation Vote	The vote of **Panel Members** undertaken by the **Panel Chairman** in accordance with Paragraph GR.22.4 as to whether in their view they believe each proposed **Grid Code Modification Proposal**, or **Workgroup Alternative Grid Code Modification** would better facilitate achievement of the **Grid Code Objective(s)** and so should be made.
Grid Code Review Panel Self-Governance Vote	The vote of **Panel Members** undertaken by the **Panel Chairman** in accordance with GR.24.9 as to whether they believe each proposed Grid Code Modification Proposal, as compared with the then existing provisions of the **Grid Code** and any **Workgroup Alternative Grid Code Modification** set out in the **Grid Code Modification Self-Governance Report**, would better facilitate achievement of the **Grid Code Objective(s)**.
Grid Code Self-Governance Proposals	**Grid Code Modification Proposals** which satisfy the **Self Governance Criteria**.
Grid Entry Point	An **Onshore Grid Entry Point** or an **Offshore Grid Entry Point**.
Grid Supply Point	A point of supply from the **National Electricity Transmission System** to **Network Operators** or **Non-Embedded Customers** which could be a **GB Grid Supply Point** or an **EU Grid Supply Point**.
Group	Those **National Electricity Transmission System** sub-stations bounded solely by the faulted circuit(s) and the overloaded circuit(s) excluding any third party connections between the **Group** and the rest of the **National Electricity Transmission System**, the faulted circuit(s) being a **Secured Event**.
GSP Group	Has the meaning as set out in the **BSC**.
Headroom	The **Power Available** (in MW) less the actual **Active Power** exported from the **Power Park Module** (in MW).

High Frequency Response	An automatic reduction in **Active Power** output in response to an increase in **System Frequency** above the **Target Frequency** (or such other level of **Frequency** as may have been agreed in an **Ancillary Services Agreement**). This reduction in **Active Power** output must be in accordance with the provisions of the relevant **Ancillary Services Agreement** which will provide that it will be released increasingly with time over the period 0 to 10 seconds from the time of the **Frequency** increase on the basis set out in the **Ancillary Services Agreement** and fully achieved within 10 seconds of the time of the start of the **Frequency** increase and it must be sustained at no lesser reduction thereafter. The interpretation of the **High Frequency Response** to a + 0.5 Hz frequency change is shown diagrammatically in Figure CC.A.3.3 and Figure ECC.A.3.3.
High Voltage or **HV**	For **E&W Transmission Systems**, a voltage exceeding 650 volts. For **Scottish Transmission Systems**, a voltage exceeding 1000 volts.
Historic Frequency Data	**System Frequency** data at a maximum of one second intervals for the whole month, published by **The Company** as detailed in OC3.4.4.
Houseload Operation	Operation which ensures that a **Power Station** is able to continue to supply its in-house load in the event of **System** faults resulting in **Power-Generating Modules** being disconnected from the **System** and tripped onto their auxiliary supplies
HP Turbine Power Fraction	Ratio of steady state mechanical power delivered by the HP turbine to the total steady state mechanical power delivered by the total steam turbine at **Registered Capacity** or **Maximum Capacity**.
HV Connections	**Apparatus** connected at the same voltage as that of the **National Electricity Transmission System**, including **Users'** circuits, the higher voltage windings of **Users'** transformers and associated connection **Apparatus**.
HVDC Converter	Any **EU Code User Apparatus** used to convert alternating current electricity to direct current electricity, or vice versa. An **HVDC Converter** is a standalone operative configuration at a single site comprising one or more converter bridges, together with one or more converter transformers, reactors, converter control equipment, essential protective and switching devices and auxiliaries, if any, used for conversion. In a bipolar arrangement, an **HVDC Converter** represents the bipolar configuration.
HVDC Converter Station	Part of an **HVDC System** which consists of one or more **HVDC Converters** installed in a single location together with buildings, reactors, filters reactive power devices, control, monitoring, protective, measuring and auxiliary equipment.
HVDC Equipment	Collectively means an **HVDC System** and a **DC Connected Power Park Module** and a **Remote End HVDC Converter Station**.
HVDC Interface Point	A point at which **HVDC Plant** and **Apparatus** is connected to an AC **System** at which technical specifications affecting the performance of the **Plant** and **Apparatus** can be prescribed.
HVDC System	An electrical power system which transfers energy in the form of high voltage direct current between two or more alternating current (AC) buses and comprises at least two **HVDC Converter Stations** with DC **Transmission** lines or cables between the **HVDC Converter Stations**.
HVDC System Owner	A party who owns and is responsible for an **HVDC System**. For the avoidance of doubt a **DC Connected Power Park Module** owner would be treated as a **Generator**.

IEC	International Electrotechnical Commission.
IEC Standard	A standard approved by the International Electrotechnical Commission.
Implementation Date	Is the date and time for implementation of an **Approved Modification** as specified in accordance with Paragraph GR.25.3.
Implementing Safety Co-ordinator	The **Safety Co-ordinator** implementing **Safety Precautions**.
Import Usable	That portion of **Registered Import Capacity** which is expected to be available and which is not unavailable due to a **Planned Outage**.
Incident Centre	A centre established by **The Company** or a **User** as the focal point in **The Company** or in that **User**, as the case may be, for the communication and dissemination of information between the senior management representatives of **The Company**, or of that **User**, as the case may be, and the relevant other parties during a **Joint System Incident** in order to avoid overloading **The Company's**, or that **User's**, as the case may be, existing operational/control arrangements.
Independent Back-Up Protection	A **Back-Up Protection** system which utilises a discrete relay, different current transformers and an alternate operating principle to the **Main Protection** systems(s) such that it can operate autonomously in the event of a failure of the **Main Protection**.
Independent Main Protection	A **Main Protection** system which utilises a physically discrete relay and different current transformers to any other **Main Protection**.
Indicated Constraint Boundary Margin	The difference between a constraint boundary transfer limit and the difference between the sum of **BM Unit** Maximum Export Limits and the forecast of local **Demand** within the constraint boundary.
Indicated Imbalance	The difference between the sum of **Physical Notifications** for **BM Units** comprising **Generating Units** or **CCGT Modules** or **Power Generating Modules** and the forecast of **Demand** for the whole or any part of the **System**.
Indicated Margin	The difference between the sum of **BM Unit** Maximum Export Limits submitted and the forecast of **Demand** for the whole or any part of the **System**.
Installation Document	A simple structured document containing information about a **Type A Power Generating Module** or a **Demand Unit**, with demand response connected below 1000 V, and confirming its compliance with the relevant requirements
Instructor Facilities	A device or system which gives certain **Transmission Control Centre** instructions with an audible or visible alarm, and incorporates the means to return message acknowledgements to the **Transmission Control Centre**.
Integral Equipment Test or **IET**	A test on equipment, associated with **Plant** and/or **Apparatus**, which takes place when that **Plant** and/or **Apparatus** forms part of a **Synchronised System** and which, in the reasonable judgement of the person wishing to perform the test, may cause an **Operational Effect**.

Intellectual Property" or "IPRs	Patents, trade marks, service marks, rights in designs, trade names, copyrights and topography rights (whether or not any of the same are registered and including applications for registration of any of the same) and rights under licences and consents in relation to any of the same and all rights or forms of protection of a similar nature or having equivalent or similar effect to any of the same which may subsist anywhere in the world.
Interconnection Agreement	An agreement made between **The Company** and an **Externally Interconnected System Operator** and/or an **Interconnector User** and/or other relevant persons for the **External Interconnection** relating to an **External Interconnection** and/or an agreement under which an **Interconnector User** can use an **External Interconnection**.
Interconnector Export Capacity	In relation to an **External Interconnection** means the (daily or weekly) forecast value (in MW) at the time of the (daily or weekly) peak demand, of the maximum level at which the **External Interconnection** can export to the **Grid Entry Point**.
Interconnector Import Capacity	In relation to an **External Interconnection** means the (daily or weekly) forecast value (in MW) at the time of the (daily or weekly) peak demand of the maximum level at which the **External Interconnection** can import from the **Grid Entry Point**.
Interconnector Owner	Has the meaning given to the term in the **Connection and Use of System Code**.
Interconnector User	Has the meaning set out in the **BSC**.
Interface Agreement	Has the meaning set out in the **CUSC**.
Interface Point	As the context admits or requires either; (a) the electrical point of connection between an **Offshore Transmission System** and an **Onshore Transmission System**, or (b) the electrical point of connection between an **Offshore Transmission System** and a **Network Operator's User System**.
Interface Point Capacity	The maximum amount of **Active Power** transferable at the **Interface Point** as declared by a **User** under the **OTSDUW Arrangements** expressed in whole MW.
Interface Point Target Voltage/Power factor	The nominal target voltage/power factor at an **Interface Point** which a **Network Operator** requires **The Company** to achieve by operation of the relevant **Offshore Transmission System**.

Interim Operational Notification or **ION**	A notification from **The Company** to a **Generator** or **DC Converter Station** owner or **HVDC System Owner** or **Network Operator** or **Non-Embedded Customer** acknowledging that the **User** has demonstrated compliance, except for the **Unresolved Issues**; (a) with the Grid Code, and (b) where applicable, with Appendices F1 to F5 of the **Bilateral Agreement**, in each case in respect of the **Plant** and **Apparatus** (including **OTSUA**) specified in such notification and provided that in the case of the **OTSDUW Arrangements** such notification shall be provided to a **Generator** in two parts dealing with the **OTSUA** and **Generator's Plant** and **Apparatus** (called respectively "**Interim Operational Notification Part A**" or "**ION A**" and "**Interim Operational Notification Part B**" or "**ION B"**) as provided for in the **CP** or **ECP**.
Intermittent Power Source	The primary source of power for a **Generating Unit** or **Power Generating Module** that cannot be considered as controllable, e.g. wind, wave or solar. For the avoidance of doubt, the output from an **Electricity Storage Module** would not be considered to be an **Intermittent Power Source**.
Intertripping	(a) The tripping of circuit-breaker(s) by commands initiated from **Protection** at a remote location independent of the state of the local **Protection**; or (b) **Operational Intertripping**.
Intertrip Apparatus	**Apparatus** which performs **Intertripping**.
IP Turbine Power Fraction	Ratio of steady state mechanical power delivered by the IP turbine to the total steady state mechanical power delivered by the total steam turbine at **Registered Capacity** or **Maximum Capacity**.
Isolating Device	A device for achieving **Isolation**.

Isolation	The disconnection of **HV Apparatus** (as defined in OC8A.1.6.2 and OC8B.1.7.2) from the remainder of the **System** in which that **HV Apparatus** is situated by either of the following: (a) an **Isolating Device** maintained in an isolating position. The isolating position must either be: (i) maintained by immobilising and **Locking** the **Isolating Device** in the isolating position and affixing a **Caution Notice** to it. Where the **Isolating Device** is **Locked** with a **Safety Key**, the **Safety Key** must be secured in a **Key Safe** and the **Key Safe Key** must be, where reasonably practicable, given to the authorised site representative of the **Requesting Safety Co-Ordinator** and is to be retained in safe custody. Where not reasonably practicable the **Key Safe Key** must be retained by the authorised site representative of the **Implementing Safety Co-ordinator** in safe custody; or (ii) maintained and/or secured by such other method which must be in accordance with the **Local Safety Instructions** or the **Safety Rules** of the **Relevant Transmission Licensee** or that **User**, as the case may be; or (b) an adequate physical separation which must be in accordance with and maintained by the method set out in the **Local Safety Instructions** or the **Safety Rules** of the **Relevant Transmission Licensee** or that **User**, as the case may be.
Joint System Incident	An **Event** wherever occurring (other than on an **Embedded Medium Power Station** or an **Embedded Small Power Station**) which, in the opinion of **The Company** or a **User**, has or may have a serious and/or widespread effect, in the case of an **Event** on a **User(s) System(s)** (other than on an **Embedded Medium Power Station** or **Embedded Small Power Station**), on the **National Electricity Transmission System**, and in the case of an **Event** on the **National Electricity Transmission System**, on a **User(s) System(s)** (other than on an **Embedded Medium Power Station** or **Embedded Small Power Station**).
Key Safe	A device for the secure retention of keys.
Key Safe Key	A key unique at a **Location** capable of operating a lock, other than a control lock, on a **Key Safe**.

Large Power Station	A **Power Station** which is (a) directly connected to: (i) **NGET's Transmission System** where such **Power Station** has a **Registered Capacity** of 100MW or more; or (ii) **SPT's Transmission System** where such **Power Station** has a **Registered Capacity** of 30MW or more; or (iii) **SHETL's Transmission System** where such **Power Station** has a **Registered Capacity** of 10MW or more; or (iv) an **Offshore Transmission System** where such **Power Station** has a **Registered Capacity** of 10MW or more; or, (b) **Embedded** within a **User System** (or part thereof) where such **User System** (or part thereof) is connected under normal operating conditions to: (i) **NGET's Transmission System** and such **Power Station** has a **Registered Capacity** of 100MW or more; or (ii) **SPT's Transmission System** and such **Power Station** has a **Registered Capacity** of 30MW or more; or (iii) **SHETL's Transmission System** and such **Power Station** has a **Registered Capacity** of 10MW or more; or, (c) **Embedded** within a **User System** (or part thereof) where the **User System** (or part thereof) is not connected to the **National Electricity Transmission System**, although such **Power Station** is in: (i) **NGET's Transmission Area** where such **Power Station** has a **Registered Capacity** of 100MW or more; or (ii) **SPT's Transmission Area** where such **Power Station** has a **Registered Capacity** of 30MW or more; or (iii) **SHETL's Transmission Area** where such **Power Station** has a **Registered Capacity** of 10MW or more; For the avoidance of doubt, a **Large Power Station** could comprise of **Type A**, **Type B**, **Type C** or **Type D Power Generating Modules**.
Legal Challenge	Where permitted by law, a judicial review in respect of the **Authority's** decision to approve or not to approve a **Grid Code Modification Proposal**.
Licence	Any licence granted to **The Company** or a **Relevant Transmission Licensee** or a **User**, under Section 6 of the **Act**.
Licence Standards	Those standards set out or referred to in Condition C17 of **The Company's Transmission Licence** and/or Condition D3 and/or Condition E16 of a **Relevant Transmission Licensee's Transmission Licence**.

Limited Frequency Sensitive Mode	A mode whereby the operation of the **Genset** or **Power Generating Module** (or **DC Converter** at a **DC Converter Station** or **HVDC Systems** exporting **Active Power** to the **Total System)** is **Frequency** insensitive except when the **System Frequency** exceeds 50.4Hz, from which point **Limited High Frequency Response** must be provided. For **Power Generating Modules** (including **DC Connected Power Park Modules**) and **HVDC Systems**, operation in **Limited Frequency Sensitive Mode** would require **Limited Frequency Sensitive Mode – Overfrequency (LFSM-O)** capability and **Limited Frequency Sensitive Mode – Underfrequency (LFSM-U)** capability.
Limited Frequency Sensitive Mode – Overfrequency or **LFSM-O**	A **Power Generating Module** (including a **DC Connected Power Park Module**) or **HVDC System** operating mode which will result in **Active Power** output reduction in response to a change in **System Frequency** above a certain value.
Limited Frequency Sensitive Mode – Underfrequency or **LFSM-U**	A **Power Generating Module** (including a **DC Connected Power Park Module**) or **HVDC System** operating mode which will result in **Active Power** output increase in response to a change in **System Frequency** below a certain value.
Limited High Frequency Response	A response of a **Genset** (or **DC Converter** at a **DC Converter Station** exporting **Active Power** to the **Total System)** to an increase in **System Frequency** above 50.4Hz leading to a reduction in **Active Power** in accordance with the provisions of BC3.7.2.1.
Limited Membership Workgroup	A **Workgroup** having less than five (5) but more than two (2) persons that have nominated themselves for membership in addition to the **Code Administrator** representative and the chair of the **Workgroup**. Members of a **Limited Membership Workgroup** where employed by companies that are considered to be an **Affiliate** of each other will be considered to be a single workgroup member for the purposes of fulfilling this minimum requirement.
Limited Operational Notification or **LON**	A notification from **The Company** to a **Generator** or **DC Converter Station** owner or **HVDC System Owner** or **Network Operator** or **Non-Embedded Customer** stating that the **User's Plant** and/or **Apparatus** specified in such notification may be, or is, unable to comply: (a) with the provisions of the Grid Code specified in the notice, and (b) where applicable, with Appendices F1 to F5 of the **Bilateral Agreement** , and specifying the **Unresolved Issues**.
Load	The **Active**, **Reactive** or **Apparent Power**, as the context requires, generated, transmitted or distributed.
Loaded	Supplying electrical power to the **System**.
Load Factor	The ratio of the actual output of a **Generating Unit** or **Power Generating Module** to the possible maximum output of that **Generating Unit** or **Power Generating Module**.
Load Management Block	A block of **Demand** controlled by a **Supplier** or other party through the means of radio teleswitching or by some other means.

Local Joint Restoration Plan	A plan produced under OC9.4.7.12 detailing the agreed method and procedure by which a **Black Start Service Provider** will energise part of the **Total System** and meet complementary blocks of local **Demand** so as to form a **Power Island**. In Scotland, the plan may also: cover more than one **Black Start Service Provider**; including **Gensets** other than those at a **Black Start Station** and cover the creation of one or more **Power Islands**.
Local Safety Instructions	For safety co-ordination in England and Wales, instructions on each **User Site** and **Transmission Site**, approved by **NGET's** or **User's** relevant manager, setting down the methods of achieving the objectives of **NGET's** or the **User's Safety Rules**, as the case may be, to ensure the safety of personnel carrying out work or testing on **Plant** and/or **Apparatus** on which his **Safety Rules** apply and, in the case of a **User**, any other document(s) on a **User Site** which contains rules with regard to maintaining or securing the isolating position of an **Isolating Device**, or maintaining a physical separation or maintaining or securing the position of an **Earthing Device**.
Local Switching Procedure	A procedure produced under OC7.6 detailing the agreed arrangements in respect of carrying out of **Operational Switching** at **Connection Sites** and parts of the **National Electricity Transmission System** adjacent to those **Connection Sites**.
Localised Negative Reserve Active Power Margin or **Localised NRAPM**	That margin of **Active Power** sufficient to allow transfers to and from a **System Constraint Group** (as the case may be) to be contained within such reasonable limit as **The Company** may determine.
Location	Any place at which **Safety Precautions** are to be applied.
Locked	A condition of **HV Apparatus** that cannot be altered without the operation of a locking device.
Locking	The application of a locking device which enables **HV Apparatus** to be **Locked**.
Low Frequency Relay	Has the same meaning as **Under Frequency Relay**.
Low Voltage or **LV**	For **E&W Transmission Systems** a voltage not exceeding 250 volts. For **Scottish Transmission Systems**, a voltage exceeding 50 volts but not exceeding 1000 volts.
LV Side of the Offshore Platform	Unless otherwise specified in the **Bilateral Agreement**, the busbar on the **Offshore Platform** (typically 33kV) at which the relevant **Offshore Grid Entry Point** is located.

Main Plant and Apparatus	In respect of a **Power Station** (including **Power Stations** comprising of **DC Connected Power Park Modules** and **Electricity Storage Modules**) is one or more of the principal items of **Plant** or **Apparatus** required to convert or re-convert the primary source of energy into electricity. In respect of **HVDC Systems** or **DC Converters** or **Transmission DC Converters** is one of the principal items of **Plant** or **Apparatus** used to convert high voltage direct current to high voltage alternating current or vice versa. In respect of a **Network Operator's** equipment or a **Non-Embedded Customer's** equipment, is one of the principal items of **Plant** or **Apparatus** required to facilitate the import or export of **Active Power** or **Reactive Power** to or from a **Network Operator's** or **Non-Embedded Customer's System**.
Main Protection	A **Protection** system which has priority above other **Protection** in initiating either a fault clearance or an action to terminate an abnormal condition in a power system.
Manufacturer's Data & Performance Report	A report submitted by a manufacturer to **The Company** relating to a specific version of a **Power Park Unit** demonstrating the performance characteristics of such **Power Park Unit** in respect of which **The Company** has evaluated its relevance for the purposes of the **Compliance Processes**.
Manufacturer's Test Certificates	A certificate prepared by a manufacturer which demonstrates that its **Power Generating Module** has undergone appropriate tests and conforms to the performance requirements expected by **The Company** in satisfying its compliance requirements and thereby satisfies the appropriate requirements of the Grid Code and **Bilateral Agreement**.
Market Operation Data Interface System (MODIS)	A computer system operated by **The Company** and made available for use by **Customers** connected to or using the **National Electricity Transmission System** for the purpose of submitting **EU Transparency Availability Data** to **The Company**.
Market Suspension Threshold	Has the meaning given to the term 'Market Suspension Threshold' in Section G of the **BSC**.
Material Effect	An effect causing **The Company** or a **Relevant Transmission Licensee** to effect any works or to alter the manner of operation of **Transmission Plant** and/or **Transmission Apparatus** at the **Connection Site** (which term shall, in this definition and in the definition of "**Modification**" only, have the meaning ascribed thereto in the **CUSC**) or the site of connection or a **User** to effect any works or to alter the manner of operation of its **Plant** and/or **Apparatus** at the **Connection Site** or the site of connection which in either case involves that party in expenditure of more than £10,000.
Materially Affected Party	Any person or class of persons designated by the **Authority** as such.
Maximum Export Capability	The maximum continuous **Active Power** that a **Network Operator** or **Non-Embedded Customer** can export to the **Transmission System** at the **Grid Supply Point**, as specified in the **Bilateral Agreement**.
Maximum Export Capacity	The maximum continuous **Apparent Power** expressed in MVA and maximum continuous **Active Power** expressed in MW which can flow from an **Offshore Transmission System** connected to a **Network Operator's User System**, to that **User System**.

Maximum Capacity or P_{max}	The maximum continuous **Active Power** which a **Power Generating Module** can supply to the **Total System**, less any demand associated solely with facilitating the operation of that **Power Generating Module** and not fed into the **System**. In the case of an **Electricity Storage Module**, the **Maximum Capacity** is the maximum continuous **Active Power** which an **Electricity Storage Module** can export to the **Total System** less any demand associated with facilitating the operation of that **Electricity Storage Module** when fully charged and operating in a mode analogous to **Generation**.
Maximum Generation Service or MGS	A service utilised by **The Company** in accordance with the **CUSC** and the **Balancing Principles Statement** in operating the **Total System**.
Maximum Generation Service Agreement	An agreement between a **User** and **The Company** for the payment by **The Company** to that **User** in respect of the provision by such **User** of a **Maximum Generation Service**.
Maximum HVDC Active Power Transmission Capacity (PHmax)	The maximum continuous **Active Power** which an **HVDC System** can exchange with the network at each **Grid Entry Point** or **User System Entry Point** as specified in the **Bilateral Agreement** or as agreed between **The Company** and the **HVDC System Owner**.
Maximum Import Capability	The maximum continuous **Active Power** that a **Network Operator** or **Non-Embedded Customer** can import from the **Transmission System** at the **Grid Supply Point**, as specified in the **Bilateral Agreement**.
Maximum Import Capacity	The maximum continuous **Apparent Power** expressed in MVA and maximum continuous **Active Power** expressed in MW which can flow to an **Offshore Transmission System** connected to a **Network Operator's User System**, from that **User System**.
Maximum Import Power	The maximum continuous **Active Power** which an **Electricity Storage Module** can import from the **Total System**, when fully discharged and operating in a mode analogous to **Demand**.
Medium Power Station	A **Power Station** which is (a) directly connected to **NGET's Transmission System** where such **Power Station** has a **Registered Capacity** of 50MW or more but less than 100MW; or, (b) **Embedded** within a **User System** (or part thereof) where such **User System** (or part thereof) is connected under normal operating conditions to **NGET's Transmission System** and such **Power Station** has a **Registered Capacity** of 50MW or more but less than 100MW; or, (c) **Embedded** within a **User System** (or part thereof) where the **User System** (or part thereof) is not connected to the **National Electricity Transmission System**, although such **Power Station** is in **NGET's Transmission Area** and such **Power Station** has a **Registered Capacity** of 50MW or more but less than 100MW. For the avoidance of doubt a **Medium Power Station** could comprise of **Type A**, **Type B**, **Type C** or **Type D Power Generating Modules**.

Medium Voltage or **MV**	For **E&W Transmission Systems** a voltage exceeding 250 volts but not exceeding 650 volts.
Mills	Milling plant which supplies pulverised fuel to the boiler of a coal fired **Power Station**.
Minimum Generation	The minimum output (in whole MW) which a **Genset** can generate or **DC Converter** at a **DC Converter Station** or **Electricity Storage Module** can import or export to the **Total System** under stable operating conditions, as registered with **The Company** under the **PC** (and amended pursuant to the **PC**). For the avoidance of doubt, the output may go below this level as a result of operation in accordance with BC3.7.
Minimum Active Power Transmission Capacity (PHmin)	The minimum continuous **Active Power** which an **HVDC System** can exchange with the **System** at each **Grid Entry Point** or **User System Entry Point** as specified in the **Bilateral Agreement** or as agreed between **The Company** and the **HVDC System Owner**.
Minimum Import Capacity	The minimum input (in whole MW) into a **DC Converter** at a **DC Converter Station** or **HVDC System** at an **HVDC Converter** (in any of its operating configurations) at the **Onshore Grid Entry Point** (or in the case of an **Embedded DC Converter** or an **Embedded HVDC Converter** at the **User System Entry Point**) at which a **DC Converter** or **HVDC Converter** can operate in a stable manner, as registered with **The Company** under the **PC** (and amended pursuant to the **PC**).
Minimum Regulating Level	The minimum **Active Power**, as specified in the **Bilateral Agreement** or as agreed between **The Company** and the **Generator** or **HVDC System Owner**, down to which the **Power Generating Module** (including a **DC Connected Power Park Module**) or **HVDC System** can control **Active Power**.
Minimum Stable Operating Level	The minimum **Active Power**, as specified in the **Bilateral Agreement** or as agreed between **The Company** and the **Generator**, at which the **Power Generating Module** can be operated stably for an unlimited time.
Modification	Any actual or proposed replacement, renovation, modification, alteration or construction by or on behalf of a **User** or **The Company** to either that **User's Plant** or **Apparatus** or **Transmission Plant** or **Apparatus**, as the case may be, or the manner of its operation which has or may have a **Material Effect** on **The Company** or a **User**, as the case may be, at a particular **Connection Site**.
Mothballed DC Connected Power Park Module	A **DC Connected Power Park Module** that has previously generated which the **Generator** plans not to use to generate for the remainder of the current **Financial Year** but which could be returned to service.
Mothballed DC Converter at a DC Converter Station	A **DC Converter** at a **DC Converter Station** that has previously imported or exported power which the **DC Converter Station Owner** plans not to use to import or export power for the remainder of the current **Financial Year** but which could be returned to service.
Mothballed HVDC System	An **HVDC System** that has previously imported or exported power which the **HVDC System Owner** plans not to use to import or export power for the remainder of the current **Financial Year** but which could be returned to service.

Mothballed HVDC Converter	An **HVDC Converter** which is part of an **HVDC System** that has previously imported or exported power which the **HVDC System Owner** plans not to use to import or export power for the remainder of the current **Financial Year** but which could be returned to service.
Mothballed Generating Unit	A **Generating Unit** that has previously generated which the **Generator** plans not to use to generate for the remainder of the current **Financial Year** but which could be returned to service. For the avoidance of doubt a **Mothballed Generating Unit** could be part of a **Power Generating Module**.
Mothballed Power Generating Module	A **Power Generating Module** that has previously generated which the **Generator** plans not to use to generate for the remainder of the current **Financial Year** but which could be returned to service.
Mothballed Power Park Module	A **Power Park Module** that has previously generated which the **Generator** plans not to use to generate for the remainder of the current **Financial Year** but which could be returned to service.
Multiple Point of Connection	A double (or more) **Point of Connection**, being two (or more) **Points of Connection** interconnected to each other through the **User's System**.
MSID	Has the meaning a set out in the **BSC**, covers Metering System Identifier.
National Demand	The amount of electricity supplied from the **Grid Supply Points** plus:- • that supplied by **Embedded Large Power Stations**, and • **National Electricity Transmission System Losses**, minus:- • the **Demand** taken by **Station Transformers** and, **Pumped Storage Units'** and **Electricity Storage Modules'**. and, for the purposes of this definition, does not include:- • any exports from the **National Electricity Transmission System** across **External Interconnections**.
National Electricity Transmission System	The **Onshore Transmission System** and, where owned by **Offshore Transmission Licensees**, **Offshore Transmission Systems**.
National Electricity Transmission System Demand	The amount of electricity supplied from the **Grid Supply Points** plus:- • that supplied by **Embedded Large Power Stations**, and • exports from the **National Electricity Transmission System** across **External Interconnections**, and • **National Electricity Transmission System Losses**, and, for the purposes of this definition, includes:- • the **Demand** taken by **Station Transformers** and, **Pumped Storage Units** and **Electricity Storage Modules'.**
National Electricity Transmission System Losses	The losses of electricity incurred on the **National Electricity Transmission System**.

National Electricity Transmission System Operator Area	Has the meaning set out in Schedule 1 of **The Company's Transmission Licence**.
National Electricity Transmission System Study Network Data File	A computer file produced by **The Company** which in **The Company's** view provides an appropriate representation of the **National Electricity Transmission System** for a specific point in time. The computer file will contain information and data on **Demand** on the **National Electricity Transmission System** and on **Large Power Stations** including **Genset** power output consistent with **Output Usable** and **The Company's** view of prevailing system conditions.
National Electricity Transmission System Warning	A warning issued by **The Company** to **Users** (or to certain **Users** only) in accordance with OC7.4.8.2, which provides information relating to **System** conditions or **Events** and is intended to: (a) alert **Users** to possible or actual **Plant** shortage, **System** problems and/or **Demand** reductions; (b) inform of the applicable period; (c) indicate intended consequences for **Users**; and (d) enable specified **Users** to be in a state of readiness to receive instructions from **The Company**.
National Electricity Transmission System Warning - Demand Control Imminent	A warning issued by **The Company**, in accordance with OC7.4.8.7, which is intended to provide short term notice, where possible, to those **Users** who are likely to receive **Demand** reduction instructions from **The Company** within 30 minutes.
National Electricity Transmission System Warning - High Risk of Demand Reduction	A warning issued by **The Company**, in accordance with OC7.4.8.6, which is intended to alert recipients that there is a high risk of **Demand** reduction being implemented and which may normally result from an **Electricity Margin Notice**.
National Electricity Transmission System Warning - Electricity Margin Notice	A warning issued by **The Company**, in accordance with OC7.4.8.5, which is intended to invite a response from and to alert recipients to a decreased **System Margin**.
National Electricity Transmission System Warning - Risk of System Disturbance	A warning issued by **The Company**, in accordance with OC7.4.8.8, which is intended to alert **Users** of the risk of widespread and serious **System** disturbance which may affect **Users**.
Network Data	The data to be provided by **The Company** to **Users** in accordance with the **PC**, as listed in Part 3 of the Appendix to the **PC**.
Network Operator	A person with a **User System** directly connected to the **National Electricity Transmission System** to which **Customers** and/or **Power Stations** (not forming part of the **User System**) are connected, acting in its capacity as an operator of the **User System**, but shall not include a person acting in the capacity of an **Externally Interconnected System Operator** or a **Generator** in respect of **OTSUA**.
NGET	National Grid Electricity Transmission plc (NO: 2366977) whose registered office is at 1-3 Strand, London, WC2N 5EH.

No-Load Field Voltage	Shall have the meaning ascribed to that term in **IEC** 34-16-1:1991 [equivalent to **British Standard BS**4999 Section 116.1 : 1992].
No System Connection	As defined in OC8A.1.6.2 and OC8B.1.7.2.
Non-Synchronous Electricity Storage Module	A **Power Park Module** comprising soley of one or more **Non-Synchronous Electricity Storage Units**.
Notification of User's Intention to Operate	A notification from a **Network Operator** or **Non-Embedded Customer** to **The Company** informing **The Company** of the date upon which any **Network Operator's** or **Non-Embedded Customer's Plant** and **Apparatus** at an **EU Grid Supply Point** will be ready to be connected to the **Transmission System**.
Notification of User's Intention to Synchronise	A notification from a **Generator** or **DC Converter Station** owner or **HVDC System Owner** to **The Company** informing **The Company** of the date upon which any **OTSUA**, a **Generating Unit**(s), **CCGT Module**(s), **Power Park Module**(s), **Power Generating Module**(s) (including a **DC Connected Power Park Module**(s)), **HVDC System** or **DC Converter**(s) will be ready to be **Synchronised** to the **Total System**.
Non-Controllable Electricity Storage Equipment	An item of storage **Plant**, including but not limited to a **Synchronous Flywheel** or **Synchronous Compensation Equipment** or **Regenerative Braking** whose active output power cannot be independently controlled.
Non-Dynamic Frequency Response Service	A **Demand Response Service** in which the **Demand** is controlled through discrete switching rather than through continuous load changes in response to **System Frequency** changes.
Non-Embedded Customer	A **Customer** in **Great Britain**, except for a **Network Operator** acting in its capacity as such, receiving electricity direct from the **Onshore Transmission System** irrespective of from whom it is supplied.
Non-Synchronous Electricity Storage Module	A **Power Park Module** comprising solely of one or more **Non-Synchronous Electricity Storage Units**.
Non-Synchronous Electricity Storage Unit	A **Power Park Unit** which can produce electrical energy by converting or re-converting another source of energy such that the frequency of the generated voltage is not inherently in synchronism with the frequency of the **System**.
Non-Synchronous Generating Unit	An **Onshore Non-Synchronous Generating Unit** or **Offshore Non-Synchronous Generating Unit** which could form part of a **Power Generating Module**.
Normal CCGT Module	A **CCGT Module** other than a **Range CCGT Module**.
Novel Unit	A tidal, wave, wind, geothermal, or any similar, **Generating Unit**.
OC9 De-synchronised Island Procedure	Has the meaning set out in OC9.5.4.
Offshore	Means wholly or partly in **Offshore Waters**, and when used in conjunction with another term and not defined means that the associated term is to be read accordingly.

Offshore DC Converter	Any **User Apparatus** located **Offshore** used to convert alternating current electricity to direct current electricity, or vice versa. An **Offshore DC Converter** is a standalone operative configuration at a single site comprising one or more converter bridges, together with one or more converter transformers, converter control equipment, essential protective and switching devices and auxiliaries, if any, used for conversion.
Offshore HVDC Converter	Any **User Apparatus** located **Offshore** used to convert alternating current electricity to direct current electricity, or vice versa. An **Offshore HVDC Converter** is a standalone operative configuration at a single site comprising one or more converter bridges, together with one or more converter transformers, converter control equipment, essential protective and switching devices and auxiliaries, if any, used for conversion.
Offshore Development Information Statement	A statement prepared by **The Company** in accordance with Special Condition C4 of **The Company's Transmission Licence**.
Offshore Generating Unit	Unless otherwise provided in the Grid Code, any **Apparatus** located **Offshore** which produces electrical energy by converting or re-converting another source of energy, including, an **Offshore Synchronous Generating Unit** or **Offshore Non-Synchronous Generating Unit** which could also be part of a **Power Generating Module** or **Electricity Storage Module**
Offshore Grid Entry Point	In the case of:- (a) an **Offshore Generating Unit** or an **Offshore Synchronous Power Generating Module** or an **Offshore DC Converter** or an **Offshore HVDC Converter**, as the case may be, which is directly connected to an **Offshore Transmission System**, the point at which it connects to that **Offshore Transmission System**, or; (b) an **Offshore Power Park Module** which is directly connected to an **Offshore Transmission System**, the point where one **Power Park String** (registered by itself as a **Power Park Module**) or the collection of points where a number of **Offshore Power Park Strings** (registered as a single **Power Park Module**) connects to that **Offshore Transmission System**, or; (c) an **External Interconnection** which is directly connected to an **Offshore Transmission System**, the point at which it connects to that **Offshore Transmission System**.
Offshore Non-Synchronous Generating Unit	An **Offshore Generating Unit** that is not an **Offshore Synchronous Generating Unit** including for the avoidance of doubt a **Power Park Unit** or **Non-Synchronous Electricity Storage Unit** located **Offshore**.
Offshore Platform	A single structure comprising of **Plant** and **Apparatus** located **Offshore** which includes one or more **Offshore Grid Entry Points**.

Offshore Power Park Module	A collection of one or more **Offshore Power Park Strings** (registered as a **Power Park Module** under the **PC**). There is no limit to the number of **Power Park Strings** within the **Power Park Module**, so long as they either: (a) connect to the same busbar which cannot be electrically split; or (b) connect to a collection of directly electrically connected busbars of the same nominal voltage and are configured in accordance with the operating arrangements set out in the relevant **Bilateral Agreement**.
Offshore Power Park String	A collection of **Offshore Generating Units** or **Power Park Units** or **Non-Synchronous Electricity Storage Unit** that are powered by an **Intermittent Power Source**, joined together by cables forming part of a **User System** with a single point of connection to an **Offshore Transmission System**. The connection to an **Offshore Transmission System** may include a **DC Converter** or **HVDC Converter**.
Offshore Synchronous Generating Unit	A **Generating Unit** or **Synchronous Electricity Storage Unit** located **Offshore** which could be part of an **Offshore Synchronous Power Generating Module** in which, under all steady state conditions, the rotor rotates at a mechanical speed equal to the electrical frequency of the **National Electricity Transmission System** divided by the number of pole pairs of the **Generating Unit**.
Offshore Synchronous Power Generating Module	A **Synchronous Power Generating Module** or **Synchronous Electricity Storage Module** located **Offshore**.
Offshore Tender Process	The process followed by the **Authority** to make, in prescribed cases, a determination on a competitive basis of the person to whom an offshore transmission licence is to be granted.
Offshore Transmission Distribution Connection Agreement	An agreement entered into by **The Company** and a **Network Operator** in respect of the connection to and use of a **Network Operator's User System** by an **Offshore Transmission System**.
Offshore Transmission Licensee	Such person in relation to whose **Transmission Licence** the standard conditions in Section E (offshore transmission owner standard conditions) of such **Transmission Licence** have been given effect, or any person in that prospective role who has acceded to the **STC**.
Offshore Transmission System	A system consisting (wholly or mainly) of high voltage electric lines and used for the transmission of electricity from one **Power Station** to a sub-station or to another **Power Station** or between sub-stations, and includes any **Plant** and **Apparatus** (including **OTSUA**) and meters in connection with the transmission of electricity but does not include any **Remote Transmission Assets**. An **Offshore Transmission System** extends from the **Interface Point**, or the **Offshore Grid Entry Point(s)** and may include **Plant** and **Apparatus** located **Onshore** and **Offshore** and, where the context permits, references to the **Offshore Transmission System** includes **OTSUA**.
Offshore Transmission System Development User Works or **OTSDUW**	In relation to a particular **User** where the **OTSDUW Arrangements** apply, means those activities and/or works for the design, planning, consenting and/or construction and installation of the **Offshore Transmission System** to be undertaken by the **User** as identified in Part 2 of Appendix I of the relevant **Construction Agreement**.

Offshore Transmission System User Assets or **OTSUA**	**OTSDUW Plant and Apparatus** constructed and/or installed by a **User** under the **OTSDUW Arrangements** which form an **Offshore Transmission System** that once transferred to a **Relevant Transmission Licensee** under an **Offshore Tender Process** will become part of the **National Electricity Transmission System**.
Offshore Waters	Has the meaning given to "offshore waters" in Section 90(9) of the Energy Act 2004.
Offshore Works Assumptions	In relation to a particular **User**, means those assumptions set out in Appendix P of the relevant **Construction Agreement** as amended from time to time.
Onshore	Means within **Great Britain**, and when used in conjunction with another term and not defined means that the associated term is to be read accordingly.
Onshore DC Converter	Any **User Apparatus** located **Onshore** with a **Completion Date** after 1st April 2005 used to convert alternating current electricity to direct current electricity, or vice versa. An **Onshore DC Converter** is a standalone operative configuration at a single site comprising one or more converter bridges, together with one or more converter transformers, converter control equipment, essential protective and switching devices and auxiliaries, if any, used for conversion. In a bipolar arrangement, an **Onshore DC Converter** represents the bipolar configuration.
Onshore Generating Unit	Unless otherwise provided in the Grid Code, any **Apparatus** located **Onshore** which produces electrical energy by converting or re-converting another source of energy, including, an **Onshore Synchronous Generating Unit** or **Onshore Non-Synchronous Generating Unit** which could also be part of a **Power Generating Module** or an **Electricity Storage Module**.
Onshore Grid Entry Point	A point at which a **Onshore Generating Unit** or a **CCGT Module** or a **CCGT Unit** or an **Onshore Power Generating Module** or a **Onshore DC Converter** or an **Onshore HVDC Converter** or a **Onshore Power Park Module** or an **Onshore Electricity Storage Module** or an **External Interconnection**, as the case may be, which is directly connected to the **Onshore Transmission System** connects to the **Onshore Transmission System**.
Onshore HVDC Converter	Any **User Apparatus** located **Onshore** used to convert alternating current electricity to direct current electricity, or vice versa. An **Onshore HVDC Converter** is a standalone operative configuration at a single site comprising one or more converter bridges, together with one or more converter transformers, converter control equipment, essential protective and switching devices and auxiliaries, if any, used for conversion. In a bipolar arrangement, an **Onshore HVDC Converter** represents the bipolar configuration.
Onshore Non-Synchronous Generating Unit	A **Generating Unit** located **Onshore** that is not a **Synchronous Generating Unit** or **Synchronous Electricity Storage Unit** including for the avoidance of doubt a **Power Park Unit** or **Non-Synchronous Electricity Storage Unit** located **Onshore**.

Onshore Power Park Module	A collection of **Non-Synchronous Generating Units** that are powered by an **Intermittent Power Source** or connected through power electronic conversion technology or **Non-Synchronous Electricity Storage Units**, joined together by a **System** (registered as a **Power Park Module** under the **PC**) with a single electrical point of connection directly to the **Onshore Transmission System** (or **User System** if **Embedded**) with no intermediate **Offshore Transmission System** connections. The connection to the **Onshore Transmission System** (or **User System** if **Embedded**) may include a **DC Converter** or **HVDC Converter**.
Onshore Synchronous Generating Unit	An **Onshore Generating Unit** or **Onshore Synchronous Electricity Storage Unit** (which could also be part of an **Onshore Power Generating Module**) including, for the avoidance of doubt, a **CCGT Unit** or **Synchronous Electricity Storage Unit** in which, under all steady state conditions, the rotor rotates at a mechanical speed equal to the electrical frequency of the **National Electricity Transmission System** divided by the number of pole pairs of the **Generating Unit**.
Onshore Synchronous Power Generating Module	A **Synchronous Power Generating Module** or **Synchronous Electricity Storage Module** located **Onshore**.
Onshore Transmission Licensee	**NGET**, **SPT**, or **SHETL**.
Onshore Transmission System	The system consisting (wholly or mainly) of high voltage electric lines owned or operated by **Onshore Transmission Licensees** or operated by **The Company** and used for the transmission of electricity from one **Power Station** to a substation or to another **Power Station** or between substations or to or from **Offshore Transmission Systems** or to or from any **External Interconnection**, and includes any **Plant** and **Apparatus** and meters owned or operated by any **Onshore Transmission Licensee** in connection with the transmission of electricity but does not include any **Remote Transmission Assets**.
On-Site Generator Site	A site which is determined by the **BSC Panel** to be a Trading Unit under the **BSC** by reason of having fulfilled the Class 1 or Class 2 requirements as such terms are used in the **BSC**.
Operating Code or **OC**	That portion of the Grid Code which is identified as the **Operating Code**.
Operating Margin	**Contingency Reserve** plus **Operating Reserve**.
Operating Reserve	The additional output from **Large Power Stations** or the reduction in **Demand**, which must be realisable in real-time operation to respond in order to contribute to containing and correcting any **System Frequency** fall to an acceptable level in the event of a loss of generation or a loss of import from an **External Interconnection** or mismatch between generation and **Demand**.
Operation	A scheduled or planned action relating to the operation of a **System** (including an **Embedded Power Station**).
Operational Data	Data required under the **Operating Codes** and/or **Balancing Codes**.
Operational Day	The period from 0500 hours on one day to 0500 on the following day.

Operation Diagrams	Diagrams which are a schematic representation of the **HV Apparatus** and the connections to all external circuits at a **Connection Site** (and in the case of **OTSDUW**, **Transmission Interface Site**), incorporating its numbering, nomenclature and labelling.
Operational Effect	Any effect on the operation of the relevant other **System** which causes the **National Electricity Transmission System** or the **System** of the other **User** or **Users**, as the case may be, to operate (or be at a materially increased risk of operating) differently to the way in which they would or may have operated in the absence of that effect.
Operational Intertripping	The automatic tripping of circuit-breakers to prevent abnormal system conditions occurring, such as over voltage, overload, **System** instability, etc. after the tripping of other circuit-breakers following power **System** fault(s) which includes **System** to **Generating Unit**, **System** to **CCGT Module**, **System** to **Power Park Module**, **System** to **Electricity Storage Module**, **System** to **DC Converter**, **System to Power Generating Module**, **System** to **HVDC Converter** and **System** to **Demand** intertripping schemes.
Operational Notifications	Any **Energisation Operational Notification**, **Interim Operational Notification**, **Final Operational Notification** or **Limited Operational Notification** issued from **The Company** to a **User**.
Operational Planning	Planning through various timescales the matching of generation output with forecast **National Electricity Transmission System Demand** together with a reserve of generation to provide a margin, taking into account outages of certain **Generating Units** or **Power Generating Modules**, of parts of the **National Electricity Transmission System** and of parts of **User Systems** to which **Power Stations** and/or **Customers** are connected, carried out to achieve, so far as possible, the standards of security set out in **The Company's Transmission Licence**, each **Relevant Transmission Licensee's Transmission Licence** or **Electricity Distribution Licence**, as the case may be.
Operational Planning Margin	An operational planning margin set by **The Company**.
Operational Planning Phase	The period from 8 weeks to the end of the 5th year ahead of real time operation.
Operational Procedures	Management instructions and procedures, both in support of the **Safety Rules** and for the local and remote operation of **Plant** and **Apparatus**, issued in connection with the actual operation of **Plant** and/or **Apparatus** at or from a **Connection Site**.
Operational Switching	Operation of **Plant** and/or **Apparatus** to the instruction of the relevant **Control Engineer**. For the avoidance of doubt, the operation of **Transmission Plant** and/or **Apparatus** forming part of the **National Electricity Transmission System** will be to the instruction of the **Relevant Transmission Licensee**.
Other Relevant Data	The data listed in BC1.4.2(f) under the heading **Other Relevant Data**.

OTSDUW Arrangements	The arrangements whereby certain aspects of the design, consenting, construction, installation and/or commissioning of transmission assets are capable of being undertaken by a **User** prior to the transfer of those assets to a **Relevant Transmission Licensee** under an **Offshore Tender Process**.
OTSDUW Data and Information	The data and information to be provided by **Users** undertaking **OTSDUW**, to **The Company** in accordance with Appendix F of the **Planning Code**.
OTSDUW DC Converter	A **Transmission DC Converter** designed and/or constructed and/or installed by a **User** under the **OTSDUW Arrangements** and/or operated by the **User** until the **OTSUA Transfer Time**.
OTSDUW Development and Data Timetable	The timetable for both the delivery of **OTSDUW Data and Information** and **OTSDUW Network Data and Information** as referred to in Appendix F of the **Planning Code** and the development of the scope of the **OTSDUW**.
OTSDUW Network Data and Information	The data and information to be provided by **The Company** to **Users** undertaking **OTSDUW** in accordance with Appendix F of the **Planning Code**.
OTSDUW Plant and Apparatus	**Plant** and **Apparatus**, including any **OTSDUW DC Converter**, designed by the **User** under the **OTSDUW Arrangements**.
OTSUA Transfer Time	The time and date at which the **OTSUA** are transferred to a **Relevant Transmission Licensee**.
Out of Synchronism	The condition where a **System** or **Generating Unit** or **Power Generating Module** cannot meet the requirements to enable it to be **Synchronised**.
Output Usable or **OU**	The (daily or weekly) forecast value (in MW), at the time of the (daily or weekly) peak demand, of the maximum level at which the **Genset** can export to the **Grid Entry Point**, or in the case of **Embedded Power Stations**, to the **User System Entry Point**. In addition, for a **Genset** powered by an **Intermittent Power Source** the forecast value is based upon the **Intermittent Power Source** being at a level which would enable the **Genset** to generate at **Registered Capacity**. For the purpose of OC2 only, the term **Output Usable** shall include the terms **Interconnector Export Capacity** and **Interconnector Import Capacity** where the term **Output Usable** is being applied to an **External Interconnection**.
Over-excitation Limiter	Shall have the meaning ascribed to that term in **IEC** 34-16-1:1991 [equivalent to **British Standard BS**4999 Section 116.1: 1992].
Panel Chairman	A person appointed as such in accordance with GR.4.1.
Panel Member	Any of the persons identified as such in GR.4.
Panel Members' Recommendation	The recommendation in accordance with the "**Grid Code Review Panel Recommendation Vote**".
Panel Secretary	A person appointed as such in accordance with GR.3.1.2(d).

Part 1 System Ancillary Services	**Ancillary Services** which are required for **System** reasons and which must be provided by **Users** in accordance with the **Connection Conditions**. An exhaustive list of **Part 1 System Ancillary Services** is included in that part of CC.8.1 or ECC.8.1 headed Part 1.
Part 2 System Ancillary Services	**Ancillary Services** which are required for **System** reasons and which must be provided by a **User** if the **User** has agreed to provide them under a **Bilateral Agreement**. A non-exhaustive list of **Part 2 System Ancillary Services** is included in that part of CC.8.1 or ECC.8.1 headed Part 2.
Part Load	The condition of a **Genset**, or **Cascade Hydro Scheme** which is **Loaded** but is not running at its Maximum Export Limit.
Permit for Work for proximity work	In respect of **E&W Transmission Systems**, a document issued by the **Relevant E&W Transmission Licensee** or an **E&W User** in accordance with its respective **Safety Rules** to enable work to be carried out in accordance with OC8A.8 and which provides for **Safety Precautions** to be applied and maintained. An example format of a **Relevant E&W Transmission Licensee**'s permit for work is attached as Appendix E to **OC8A**. In respect of **Scottish Transmission Systems**, a document issued by a **Relevant Scottish Transmission Licensee** or a **Scottish User** in accordance with its respective **Safety Rules** to enable work to be carried out in accordance with OC8B.8 and which provides for **Safety Precautions** to be applied and maintained. Example formats of **Relevant Scottish Transmission Licensees'** permits for work are attached as Appendix E to **OC8B**.
Partial Shutdown	The same as a **Total Shutdown** except that all generation has ceased in a separate part of the **Total System** and there is no electricity supply from **External Interconnections** or other parts of the **Total System** to that part of the **Total System** and, therefore, that part of the **Total System** is shutdown, with the result that it is not possible for that part of the **Total System** to begin to function again without **The Company's** directions relating to a **Black Start**.
Pending Grid Code Modification Proposal	A **Grid Code Modification Proposal** in respect of which, at the relevant time, the **Authority** has not yet made a decision as to whether to direct such **Grid Code Modification Proposal** to be made pursuant to the **Transmission Licence** (whether or not a **Grid Code Modification Report** has been submitted in respect of such **Grid Code Modification Proposal**) or, in the case of a **Grid Code Self Governance Proposals**, in respect of which the **Grid Code Review Panel** has not yet voted whether or not to approve.
Phase (Voltage) Unbalance	The ratio (in percent) between the rms values of the negative sequence component and the positive sequence component of the voltage.
Physical Notification	Data that describes the **BM Participant**'s best estimate of the expected input or output of **Active Power** of a **BM Unit** and/or (where relevant) **Generating Unit**, the accuracy of the **Physical Notification** being commensurate with **Good Industry Practice**.
Planning Code or **PC**	That portion of the Grid Code which is identified as the **Planning Code**.

Planned Maintenance Outage	An outage of **The Company's** electronic data communication facilities as provided for in CC.6.5.8 or ECC.6.5.8 and **The Company's** associated computer facilities of which normally at least 5 days notice is given, but in any event of which at least twelve hours notice has been given by **The Company** to the **User** and which is anticipated to last no longer than 2 hours. The length of such an outage may in exceptional circumstances be extended where at least 24 hours notice has been given by **The Company** to the **User**. It is anticipated that normally any planned outage would only last around one hour.
Planned Outage	An outage of a **Large Power Station** or of part of the **National Electricity Transmission System**, or of part of a **User System**, co-ordinated by **The Company** under **OC2**.
Plant	Fixed and movable items used in the generation and/or supply and/or transmission of electricity, other than **Apparatus**.
Point of Common Coupling	That point on the **National Electricity Transmission System** electrically nearest to the **User** installation at which either **Demands** or **Loads** are, or may be, connected.
Point of Connection	An electrical point of connection between the **National Electricity Transmission System** and a **User's System**.
Point of Isolation	The point on **Apparatus** (as defined in OC8A.1.6.2 and OC8B.1.7.2) at which **Isolation** is achieved.
Post-Control Phase	The period following real time operation.
Power Available	A signal prepared in accordance with good industry practice, representing the instantaneous sum of the potential **Active Power** available from each individual **Power Park Unit** within the **Power Park Module** calculated using any applicable combination of electrical or mechanical or meteorological data (including wind speed) measured at each **Power Park Unit** at a specified time. **Power Available** shall be a value between 0MW and **Registered Capacity** or **Maximum Capacity** which is the sum of the potential **Active Power** available of each **Power Park Unit** within the **Power Park Module.** A unit that is not generating or supplying power will be considered as not available. For the avoidance of doubt, the **Power Available** signal would be the **Active Power** output that a **Power Park Module** could reasonably be expected to export at the **Grid Entry Point** or **User System Entry Point** taking all the above criteria into account including **Power Park Unit** constraints such as optimisation modes but would exclude a reduction in the **Active Power** export of the **Power Park Module** instructed by **The Company** (for example) for the purposes selecting a **Power Park Module** to operate in **Frequency Sensitive Mode** or when an **Emergency Instruction** has been issued.
Power Factor	The ratio of **Active Power** to **Apparent Power**.
Power-Generating Module	Either a **Synchronous Power Generating Module**, a **Synchronous Electricity Storage Module**, a **Power Park Module** or a **Non-Synchronous Electricity Storage Module** owned or operated by an **EU Generator**.

Power-Generating Module Document (PGMD)	A document provided by the **Generator** to **The Company** for a **Type B** or **Type C Power Generating Module** which confirms that the **Power Generating Module's** compliance with the technical criteria set out in the Grid Code has been demonstrated and provides the necessary data and statements, including a statement of compliance.
Power Generating Module Performance Chart	A diagram showing the **Real Power** (MW) and **Reactive Power** (MVAr) capability limits within which a **Synchronous Power Generating Module** or **Power Park Module** at its **Grid Entry Point** or **User System Entry Point** will be expected to operate under steady state conditions.
Power Island	**Gensets** at an isolated **Power Station**, together with complementary local **Demand**. In Scotland a **Power Island** may include more than one **Power Station**.
Power Park Module	Any **Onshore Power Park Module** or **Offshore Power Park Module**.
Power Park Module Availability Matrix	The matrix described in Appendix 1 to BC1 under the heading **Power Park Module Availability Matrix**.
Power Park Module Planning Matrix	A matrix in the form set out in Appendix 4 of OC2 showing the combination of **Power Park Units** within a **Power Park Module** which would be expected to be running under normal conditions.
Power Park Unit	A **Generating Unit** within a **Power Park Module**.
Power Station	An installation comprising one or more **Generating Units** or **Power Park Modules** or **Power Generating Modules** or **Electricity Storage Modules** (even where sited separately) owned and/or controlled by the same **Generator**, which may reasonably be considered as being managed as one **Power Station**.
Power System Stabiliser or **PSS**	Equipment controlling the **Exciter** output via the voltage regulator in such a way that power oscillations of the synchronous machines are dampened. Input variables may be speed, frequency or power (or a combination of these).
Preface	The preface to the Grid Code (which does not form part of the Grid Code and therefore is not binding).
Preliminary Notice	A notice in writing, sent by **The Company** both to all **Users** identified by it under OC12.4.2.1 and to the **Test Proposer**, notifying them of a proposed **System Test**.
Preliminary Project Planning Data	Data relating to a proposed **User Development** at the time the **User** applies for a **CUSC Contract** but before an offer is made and accepted.

Primary Response	The automatic increase in **Active Power** output of a **Genset** or, as the case may be, the decrease in **Active Power Demand** in response to a **System Frequency** fall. This increase in **Active Power** output or, as the case may be, the decrease in **Active Power Demand** must be in accordance with the provisions of the relevant **Ancillary Services Agreement** which will provide that it will be released increasingly with time over the period 0 to 10 seconds from the time of the start of the **Frequency** fall on the basis set out in the **Ancillary Services Agreement** and fully available by the latter, and sustainable for at least a further 20 seconds. The interpretation of the **Primary Response** to a – 0.5 Hz frequency change is shown diagrammatically in Figure CC.A.3.2 and Figure ECC.A.3.2
Private Network	A network which connects to a **Network Operator's System** and that network belongs to a **User** who is not classified as a **Generator**, **Network Operator** or **Non-Embedded Customer**.
Programming Phase	The period between the **Operational Planning Phase** and the **Control Phase**. It starts at the 8 weeks ahead stage and finishes at 17:00 on the day ahead of real time.
Proposal Notice	A notice submitted to **The Company** by a **User** which would like to undertake a **System Test**.
Proposal Report	A report submitted by the **Test Panel** which contains: (a) proposals for carrying out a **System Test** (including the manner in which the **System Test** is to be monitored); (b) an allocation of costs (including un-anticipated costs) between the affected parties (the general principle being that the **Test Proposer** will bear the costs); and (c) such other matters as the **Test Panel** considers appropriate. The report may include requirements for indemnities to be given in respect of claims and losses arising from a **System Test**.
Proposed Implementation Date	The proposed date(s) for the implementation of a **Grid Code Modification Proposal** or **Workgroup Alternative Grid Code Modification** such date(s) to be either (i) described by reference to a specified period after a direction from the Authority approving the **Grid Code Modification Proposal** or **Workgroup Alternative Grid Code Modification** or (ii) a **Fixed Proposed Implementation Date**.
Proposer	In relation to a particular **Grid Code Modification Proposal**, the person who makes such **Grid Code Modification Proposal**.
Protection	The provisions for detecting abnormal conditions on a **System** and initiating fault clearance or actuating signals or indications.
Protection Apparatus	A group of one or more **Protection** relays and/or logic elements designated to perform a specified **Protection** function.
Pumped Storage	A hydro unit in which water can be raised by means of pumps and stored to be used for the generation of electrical energy;
Pumped Storage Generating Unit	A **Generating Unit** at a **Pumped Storage Plant**

Pumped Storage Generator	A **Generator** which owns and/or operates any **Pumped Storage Plant**.
Pumped Storage Plant	A **Power Station** comprising **Pumped Storage Generating Units**.
Pumped Storage Unit	A **Generating Unit** within a **Pumped Storage Plant**. For the avoidance of doubt, a **Pumped Storage Unit** is not considered to form part of an **Electricity Storage Unit** unless specifically declared by the **Generator**.
Purchase Contracts	A final and binding contract for the purchase of the **Main Plant and Apparatus**.
Q/Pmax	The ratio of **Reactive Power** to the **Maximum Capacity**. The relationship between **Power Factor** and **Q/Pmax** is given by the formula:- **Power Factor** = Cos [arctan[$\frac{Q}{Pmax}$]] For example, a **Power Park Module** with a Q/P value of +0.33 would equate to a **Power Factor** of Cos(arctan0.33) = 0.95 **Power Factor** lag.
Quick Resynchronisation Capability	The capability of a **Type C** or **Type D Power Generating Module** as defined in ECC.6.3.5.6. For the avoidance of doubt this requirement only applies to **EU Code Generators** who own or operate a **Type C** or **Type D Power Generating Module**.
Quick Resynchronisation Unit Test	A test undertaken on **Generating Unit** forming part of a **Type C** or **Type D Power Generating Module** as detailed in OC5.7.1 and OC5.7.4 necessary to determine its ability to demonstrate a **Quick Resynchronisation Capability**.
Range CCGT Module	A **CCGT Module** where there is a physical connection by way of a steam or hot gas main between that **CCGT Module** and another **CCGT Module** or other **CCGT Modules**, which connection contributes (if open) to efficient modular operation, and which physical connection can be varied by the operator.
Rated Field Voltage	Shall have the meaning ascribed to that term in **IEC** 34-16-1:1991 [equivalent to **British Standard BS**4999 Section 116.1: 1992].

Rated MW	The "rating-plate" MW output of a **Power Generating Module**, **Generating Unit**, **Power Park Module**, **Electricity Storage Module**, **HVDC Converter** or **DC Converter**, being: (a) that output up to which the **Generating Unit** was designed to operate (Calculated as specified in **British Standard BS** EN 60034 – 1: 1995); or (b) the nominal rating for the MW output of a **Power Park Module** or **Power Generating Module** being the maximum continuous electric output power which the **Power Park Module** or **Power Generating Module** was designed to achieve under normal operating conditions; or (c) the nominal rating for the MW import capacity and export capacity (if at a **DC Converter Station** or **HVDC Converter Station**) of a **DC Converter** or **HVDC Converter**. (d) in an importing mode, is that input up to which an **Electricity Storage Module** was designed to operate being the maximum continuous electric input which the **Electricity Storage Module** was designed to achieve under normal operating conditions. In an exporting mode is:- (i) that output up to which the **Synchronous Electricity Storage Unit** was designed to operate (Calculated as specified in **British Standard BS** EN 60034 – 1: 1995); or (ii) the nominal rating for the MW output of a **Non-Synchronous Electricity Storage Module** being the maximum continuous electric output power which the **Non-Synchronous Electricity Storage Module** was designed to achieve under normal operating conditions.
Reactive Despatch Instruction	Has the meaning set out in the **CUSC**.
Reactive Despatch Network Restriction	A restriction placed upon an **Embedded Power Generating Module**, **Embedded Generating Unit**, **Embedded Power Park Module** or **DC Converter** at an **Embedded DC Converter Station** or **HVDC Converter** at an **Embedded HVDC Converter Station** by the **Network Operator** that prevents the **Generator** or **DC Converter Station** owner or **HVDC System Owner** in question (as applicable) from complying with any **Reactive Despatch Instruction** with respect to that **Power Generating Module**, **Generating Unit**, **Power Park Module** or **DC Converter** at a **DC Converter Station** or **HVDC Converter** at a **HVDC Converter Station**, whether to provide MVArs over the range referred to in CC 6.3.2, ECC.6.3.2 or otherwise.
Reactive Despatch to Zero Mvar Network Restriction	A **Reactive Despatch Network Restriction** which prevents an **Embedded Power Generating Module**, an **Embedded Generating Unit**, **Embedded Power Park Module**, **Embedded HVDC System**, **HVDC Converter** at an **Embedded HVDC Converter Station** or **DC Converter** at an **Embedded DC Converter Station** from supplying power at zero MVAr at all **Active Power** output levels up to and including **Rated MW** at the **Grid Entry Point** (or **User System Entry Point** if **Embedded**).
Reactive Energy	The integral with respect to time of the **Reactive Power**.

Reactive Power	The product of voltage and current and the sine of the phase angle between them measured in units of voltamperes reactive and standard multiples thereof, ie: 1000 VAr = 1 kVAr 1000 kVAr = 1 MVAr
Record of Inter-System Safety Precautions or **RISSP**	A written record of inter-system **Safety Precautions** to be compiled in accordance with the provisions of **OC8**.
Regenerative Braking	A method of braking in which energy is extracted from the parts braked, which may be returned directly to the **System** and the purpose of the braking is motion control.

Registered Capacity	(a) In the case of a **Generating Unit** other than that forming part of a **CCGT Module** or **Power Park Module** or **Power Generating Module**, the normal full load capacity of a **Generating Unit** as declared by the **Generator**, less the MW consumed by the **Generating Unit** through the **Generating Unit's Unit Transformer** when producing the same (the resultant figure being expressed in whole MW, or in MW to one decimal place). (b) In the case of a **CCGT Module** or **Power Park Module** owned or operated by a **GB Generator**, the normal full load capacity of the **CCGT Module** or **Power Park Module** (as the case may be) as declared by the **GB Generator**, being the **Active Power** declared by the **GB Generator** as being deliverable by the **CCGT Module** or **Power Park Module** at the **Grid Entry Point** (or in the case of an **Embedded CCGT Module** or **Power Park Module**, at the **User System Entry Point**), expressed in whole MW, or in MW to one decimal place. For the avoidance of doubt **Maximum Capacity** would apply to **Power Generating Modules** which form part of a **Large**, **Medium** or **Small Power Station**. (c) In the case of a **Power Station**, the maximum amount of **Active Power** deliverable by the **Power Station** at the **Grid Entry Point** (or in the case of an **Embedded Power Station** at the **User System Entry Point**), as declared by the **Generator**, expressed in whole MW, or in MW to one decimal place. The maximum **Active Power** deliverable is the maximum amount deliverable simultaneously by the **Power Generating Modules** and/or **Generating Units** and/or **CCGT Modules** and/or **Power Park Modules** less the MW consumed by the **Power Generating Modules** and/or **Generating Units** and/or **CCGT Modules** in producing that **Active Power** and forming part of a **Power Station**. (d) In the case of a **DC Converter** at a **DC Converter Station** or **HVDC Converter** at an **HVDC Converter Station**, the normal full load amount of **Active Power** transferable from a **DC Converter** or **HVDC Converter** at the **Onshore Grid Entry Point** (or in the case of an **Embedded DC Converter Station** or an **Embedded HVDC Converter Station** at the **User System Entry Point**), as declared by the **DC Converter Station** owner or **HVDC System Owner**, expressed in whole MW, or in MW to one decimal place. (e) In the case of a **DC Converter Station** or **HVDC Converter Station**, the maximum amount of **Active Power** transferable from a **DC Converter Station** or **HVDC Converter Station** at the **Onshore Grid Entry Point** (or in the case of an **Embedded DC Converter Station** or **Embedded HVDC Converter Station** at the **User System Entry Point**), as declared by the **DC Converter Station** owner or **HVDC System Owner**, expressed in whole MW, or in MW to one decimal place. (f) In the case of an **Electricity Storage Module**, the normal full load amount of **Active Power** transferable from an **Electricity Storage Module** at the **Grid Entry Point** (or in the case of an **Embedded Electricity Storage Module** at the **User System Entry Point**), as declared by the **Generator**, expressed in whole MW, or in MW to one decimal place.
Registered Data	Those items of **Standard Planning Data** and **Detailed Planning Data** which upon connection become fixed (subject to any subsequent changes).

Registered Import Capability	In the case of a **DC Converter Station** or **HVDC Converter Station** containing **DC Converters** or **HVDC Converters** connected to an **External System**, the maximum amount of **Active Power** transferable into a **DC Converter Station** or **HVDC Converter Station** at the **Onshore Grid Entry Point** (or in the case of an **Embedded DC Converter Station** or **Embedded HVDC Converter Station** at the **User System Entry Point**), as declared by the **DC Converter Station** owner or **HVDC System Owner**, expressed in whole MW. In the case of a **DC Converter** or **HVDC Converter** connected to an **External System** and in a **DC Converter Station** or **HVDC Converter Station**, the normal full load amount of **Active Power** transferable into a **DC Converter** or **HVDC Converter** at the **Onshore Grid Entry Point** (or in the case of an **Embedded DC Converter Station** or **Embedded HVDC Converter Station** at the **User System Entry Point**), as declared by the **DC Converter** owner or **HVDC System Owner**, expressed in whole MW. In the case of an **Electricity Storage Module**, the maximum amount of **Active Power** transferable into an **Electricity Storage Module** at the **Grid Entry Point** (or in the case of an **Embedded Electricity Storage Module** at the **User System Entry Point**), as declared by the **Generator**, expressed in whole MW.
Regulations	The Utilities Contracts Regulations 1996, as amended from time to time.
Regulated Sections	Parts of the Grid Code that are referenced in **Governance Rules** Annex GR.B as amended from time to time with the approval of the **Authority**.
Reheater Time Constant	Determined at **Registered Capacity**, the reheater time constant will be construed in accordance with the principles of the IEEE Committee Report "Dynamic Models for Steam and Hydro Turbines in Power System Studies" published in 1973 which apply to such phrase.
Rejected Grid Code Modification Proposal	A **Grid Code Modification Proposal** in respect of which the **Authority** has decided not to direct **The Company** to modify the **Grid Code** pursuant to **The Company's Transmission Licence** in the manner set out herein or, in the case of a **Grid Code Self Governance Proposals**, in respect of which the **Grid Code Review Panel** has voted not to approve.
Related Person	Means, in relation to an individual, any member of his immediate family, his employer (and any former employer of his within the previous 12 months), any partner with whom he is in partnership, and any company or **Affiliate** of a company in which he or any member of his immediate family controls more than 20% of the voting rights in respect of the shares of the company;
Relevant E&W Transmission Licensee	As the context requires **NGET** and/or an **E&W Offshore Transmission Licensee**.
Relevant Party	Has the meaning given in GR15.10(a).
Relevant Scottish Transmission Licensee	As the context requires **SPT** and/or **SHETL** and/or a **Scottish Offshore Transmission Licensee**.
Relevant Transmission Licensee	Means National Grid Electricity Transmission plc (**NGET)** in its **Transmission Area** or SP Transmission plc (**SPT**) in its **Transmission Area** or Scottish Hydro-Electric Transmission Ltd (**SHETL**) in its **Transmission Area** or any **Offshore Transmission Licensee** in its **Transmission Area**.

Relevant Unit	As defined in the **STC**, Schedule 3.
Remote End HVDC Converter Station	An **HVDC Converter Station** which forms part of an **HVDC System** and is not directly connected to the AC part of the **GB Synchronous Area**.
Remote Transmission Assets	Any **Plant** and **Apparatus** or meters owned by **NGET** which: (a) are **Embedded** in a **User System** and which are not directly connected by **Plant** and/or **Apparatus** owned by **NGET** to a sub-station owned by **NGET**; and (b) are by agreement between **NGET** and such **User** operated under the direction and control of such **User**.
Replacement Reserves (RR)	Means, in the context of **Balancing Services,** the **Active Power** reserves available to restore or support the required level of FRR to be prepared for additional system imbalances, including generation reserves;
Requesting Safety Co-ordinator	The **Safety Co-ordinator** requesting **Safety Precautions**.
Responsible Engineer/ Operator	A person nominated by a **User** to be responsible for **System** control.
Responsible Manager	A manager who has been duly authorised by a **User** or a **Relevant Transmission Licensee** to sign **Site Responsibility Schedules** on behalf of that **User** or **Relevant Transmission Licensee** as the case may be.
Restoration Service Provider	A **Black Start Service Provider** or **User** with a legal or contractual obligation to provide a service contributing to one or several measures of the **System Restoration Plan.**
Re-synchronisation	The bringing of parts of the **System** which have become **Out of Synchronism** with any other **System** back into **Synchronism**, and like terms shall be construed accordingly.
RR Acceptance	The results of the **TERRE** auction for each **BM Participant**.
Restricted	Applies to a **TERRE Bid** which has been marked so that it will be passed to the **TERRE Central Platform** but will not be used in the auction.
RR Instruction	**Replacement Reserve** Instruction – used for instructing **BM Participants** after the results of the **TERRE** auction. An **RR Instruction** has the same format as a **Bid-Offer Acceptance** but has type field indicating it is for **TERRE**.

Safety Co-ordinator	A person or persons nominated by a **Relevant E&W Transmission Licensee** and each **E&W User** in relation to **Connection Points** (or in the case of **OTSUA** operational prior to the **OTSUA Transfer Time**, **Transmission Interface Points**) on an **E&W Transmission System** and/or by the **Relevant Scottish Transmission Licensee** and each **Scottish User** in relation to **Connection Points** (or in the case of **OTSUA** operational prior to the **OTSUA Transfer Time**, **Transmission Interface Points**) on a **Scottish Transmission System** to be responsible for the co-ordination of **Safety Precautions** at each **Connection Point** (or in the case of **OTSUA** operational prior to the **OTSUA Transfer Time**, **Transmission Interface Points**) when work (which includes testing) is to be carried out on a **System** which necessitates the provision of **Safety Precautions** on **HV Apparatus** (as defined in OC8A.1.6.2 and OC8B.1.7.2), pursuant to **OC8**.
Safety From The System	That condition which safeguards persons when work is to be carried out on or near a **System** from the dangers which are inherent in the **System**.
Safety Key	A key unique at the **Location** capable of operating a lock which will cause an **Isolating Device** and/or **Earthing Device** to be **Locked**.
Safety Log	A chronological record of messages relating to safety co-ordination sent and received by each **Safety Co-ordinator** under **OC8**.
Safety Precautions	**Isolation** and/or **Earthing**.
Safety Rules	The rules of the **Relevant Transmission Licensee** or a **User** that seek to ensure that persons working on **Plant** and/or **Apparatus** to which the rules apply are safeguarded from hazards arising from the **System**.
Scottish Offshore Transmission System	An **Offshore Transmission System** with an **Interface Point** in Scotland.
Scottish Offshore Transmission Licensee	A person who owns or operates a **Scottish Offshore Transmission System** pursuant to a **Transmission Licence**.
Scottish Transmission System	Collectively **SPT's Transmission System** and **SHETL's Transmission System** and any **Scottish Offshore Transmission Systems**.
Scottish User	A **User** in Scotland or any **Offshore User** who owns or operates **Plant** and/or **Apparatus** connected (or which will at the **OTSUA Transfer Time** be connected) to a **Scottish Offshore Transmission System**.
Secondary BM Unit	Has the same meaning set out in the **BSC**.
Secondary Response	The automatic increase in **Active Power** output of a **Genset** or, as the case may be, the decrease in **Active Power Demand** in response to a **System Frequency** fall. This increase in **Active Power** output or, as the case may be, the decrease in **Active Power Demand** must be in accordance with the provisions of the relevant **Ancillary Services Agreement** which will provide that it will be fully available by 30 seconds from the time of the start of the **Frequency** fall and be sustainable for at least a further 30 minutes. The interpretation of the **Secondary Response** to a -0.5 Hz frequency change is shown diagrammatically in Figure CC.A.3.2 or Figure ECC.A.3.2.
Secretary of State	Has the same meaning as in the **Act**.

Secured Event	Has the meaning set out in the **Security and Quality of Supply Standard**.
Security and Quality of Supply Standard (SQSS)	The version of the document entitled 'Security and Quality of Supply Standard' established pursuant to the **Transmission Licence** in force at the time of entering into the relevant **Bilateral Agreement**.
Self-Governance Criteria	A proposed **Modification** that, if implemented, (a) is unlikely to have a material effect on: (i) existing or future electricity consumers; and (ii) competition in the generation, storage, distribution, or supply of electricity or any commercial activities connected with the generation, storage, distribution or supply of electricity; and (iii) the operation of the **National Electricity Transmission System**; and (iv) matters relating to sustainable development, safety or security of supply, or the management of market or network emergencies; and (v) the **Grid Code**'s governance procedures or the **Grid Code**'s modification procedures, and (b) is unlikely to discriminate between different classes of Users. (c) other than where the modification meets the **Fast Track Criteria**, will not constitute an amendment to the **Regulated Sections** of the Grid Code.
Self-Governance Modifications	A **Grid Code Modification Proposal** that does not fall within the scope of a **Significant Code Review** and that meets the **Self-Governance Criteria** or which the **Authority** directs is to be treated as such any direction under GR.24.4.
Self-Governance Statement	The statement made by the **Grid Code Review Panel** and submitted to the **Authority**: (a) confirming that, in its opinion, the **Self-Governance Criteria** are met and the proposed **Grid Code Modification Proposal** is suitable for the Self-Governance route; and (b) providing a detailed explanation of the **Grid Code Review Panel**'s reasons for that opinion.
Setpoint Voltage	The value of voltage at the **Grid Entry Point**, or **User System Entry Point** if **Embedded**, on the automatic control system steady state operating characteristic, as a percentage of the nominal voltage, at which the transfer of **Reactive Power** between a **Power Park Module**, **DC Converter**, **HVDC Converter** or **Non-Synchronous Generating Unit** and the **Transmission System**, or **Network Operator's** system if **Embedded**, is zero.
Settlement Period	A period of 30 minutes ending on the hour and half-hour in each hour during a day.

Seven Year Statement	A statement, prepared by **The Company** in accordance with the terms of **The Company's Transmission Licence**, showing for each of the seven succeeding **Financial Years**, the opportunities available for connecting to and using the **National Electricity Transmission System** and indicating those parts of the **National Electricity Transmission System** most suited to new connections and transport of further quantities of electricity.
SF_6 Gas Zone	A segregated zone surrounding electrical conductors within a casing containing SF_6 gas.
SHETL	Scottish Hydro-Electric Transmission Limited.
Shutdown	In the case of a **Generating Unit** is the condition of a **Generating Unit** where the generator rotor is at rest or on barring. In the case of an **HVDC System** or **DC Converter Station**, is the condition of an **HVDC System** or **DC Converter Station** where the **HVDC System** or **DC Converter Station** is de-energised and therefore not importing or exporting **Apparent Power** to or from the **Total System**.
Significant Code Review	Means the period commencing on the start date of a **Significant Code Review** as stated in the notice issued by the **Authority**, and ending in the circumstances described in GR.16.6 or GR.16.7, as appropriate.
Significant Code Review Phase	Means the period commencing on the start date of a **Significant Code Review** as stated in the notice issued by the **Authority**, and ending in the circumstances described in GR.16.6 or GR.16.7, as appropriate.
Significant Event	An **Event**, as defined in OC3.4.1.
Significant Incident	An **Event** which either: (a) was notified by a **User** to **The Company** under **OC7**, and which **The Company** considers has had or may have had a significant effect on the **National Electricity Transmission System**, and **The Company** requires the **User** to report that **Event** in writing in accordance with **OC10** and notifies the **User** accordingly; or (b) was notified by **The Company** to a **User** under **OC7**, and which that **User** considers has had or may have had a significant effect on that **User's System**, and that **User** requires **The Company** to report that **Event** in writing in accordance with the provisions of **OC10** and notifies **The Company** accordingly.
Simultaneous Tap Change	A tap change implemented on the generator step-up transformers of **Synchronised Gensets**, effected by **Generators** in response to an instruction from **The Company** issued simultaneously to the relevant **Power Stations**. The instruction, preceded by advance notice, must be effected as soon as possible, and in any event within one minute of receipt from **The Company** of the instruction.
Single Line Diagram	A schematic representation of a three-phase network in which the three phases are represented by single lines. The diagram shall include (but not necessarily be limited to) busbars, overhead lines, underground cables, power transformers and reactive compensation equipment. It shall also show where **Large Power Stations** are connected, and the points at which **Demand** is supplied.
Single Point of Connection	A single **Point of Connection**, with no interconnection through the **User's System** to another **Point of Connection**.

Site Common Drawings	Drawings prepared for each **Connection Site** (and in the case of **OTSDUW**, **Transmission Interface Site**) which incorporate **Connection Site** (and in the case of **OTSDUW**, **Transmission Interface Site**) layout drawings, electrical layout drawings, common protection/ control drawings and common services drawings.
Site Responsibility Schedule	A schedule containing the information and prepared on the basis of the provisions set out in Appendix 1 of the **CC** and Appendix E1 of the **ECC**.
Slope	The ratio of the steady state change in voltage, as a percentage of the nominal voltage, to the steady state change in **Reactive Power** output, in per unit of **Reactive Power** capability. For the avoidance of doubt, the value indicates the percentage voltage reduction that will result in a 1 per unit increase in **Reactive Power** generation.
Small Participant	Has the meaning given in the **CUSC**.
Small Power Station	A **Power Station** which is (a) directly connected to: (i) **NGET's Transmission System** where such **Power Station** has a **Registered Capacity** of less than 50MW; or (ii) **SPT's Transmission System** where such **Power Station** has a **Registered Capacity** of less than 30MW; or (iii) **SHETL's Transmission System** where such a **Power Station** has a **Registered Capacity** of less than 10 MW; or (iv) an **Offshore Transmission System** where such **Power Station** has a **Registered Capacity** of less than 10MW; or, (b) **Embedded** within a **User System** (or part thereof) where such **User System** (or part thereof) is connected under normal operating conditions to: (i) **NGET's Transmission System** and such **Power Station** has a **Registered Capacity** of less than 50MW; or (ii) **SPT's Transmission System** and such **Power Station** has a **Registered Capacity** of less than 30MW; or (iii) **SHETL's Transmission System** and such **Power Station** has a **Registered Capacity** of less than 10MW; or, (c) **Embedded** within a **User System** (or part thereof) where the **User System** (or part thereof) is not connected to the **National Electricity Transmission System**, although such **Power Station** is in: (i) **NGET's Transmission Area** and such **Power Station** has a **Registered Capacity** of less than 50MW; or (ii) **SPT's Transmission Area** and such **Power Station** has a **Registered Capacity** of less than 30MW; or (iii) **SHETL's Transmission Area** and such **Power Station** has a **Registered Capacity** of less than 10MW; For the avoidance of doubt, a **Small Power Station** could comprise of **Type A**, **Type B**, **Type C** or **Type D Power Generating Modules**.

Speeder Motor Setting Range	The minimum and maximum no-load speeds (expressed as a percentage of rated speed) to which the turbine is capable of being controlled, by the speeder motor or equivalent, when the **Generating Unit** terminals are on open circuit.
SPT	SP Transmission Limited plc
Standard Contract Terms	The standard terms and conditions applicable to **Ancillary Services** provided by **Demand Response Providers** and published on the **Website** from time to time.
Standard Modifications	A **Grid Code Modification Proposal** that does not fall within the scope of a **Significant Code Review** subject to any direction by the **Authority** pursuant to GR.16.3 and GR.16.4, nor meets the **Self-Governance Criteria** subject to any direction by the **Authority** pursuant to GR.24.4 and in accordance with any direction under GR.24.2. A **Grid Code Modification Proposal** that constitutes an amendment to the **Regulated Sections** of the Grid Code shall be a **Standard Modification** except where it is an **Urgent Modification** or where it meets the **Fast Track Criteria**.
Standard Planning Data	The general data required by **The Company** under the **PC**. It is generally also the data which **The Company** requires from a **User** in an application for a **CUSC Contract**, as reflected in the **PC**.
Standard Product	Means a harmonised balancing product defined by all EU TSOs for the exchange of balance services.
Specific Product	Means in the context of Balancing Services a product that is not a standard product.
Start Time	The time named as such in an instruction issued by **The Company** pursuant to the **BC**.
Start-Up	In the case of a **Generating Unit** is the action of bringing a **Generating Unit** from **Shutdown** to **Synchronous Speed**. In the case of an **HVDC System** or **DC Converter Station**, is the action of bringing the **HVDC System** or **DC Converter Station** from **Shutdown** to a state where it is energised.
Statement of Readiness	Has the meaning set out in the **Bilateral Agreement** and/or **Construction Agreement**.
Station Board	A switchboard through which electrical power is supplied to the **Auxiliaries** of a **Power Station**, and which is supplied by a **Station Transformer**. It may be interconnected with a **Unit Board**.
Station Transformer	A transformer supplying electrical power to the **Auxiliaries** of (a) a **Power Station**, which is not directly connected to the **Generating Unit** terminals (typical voltage ratios being 132/11kV or 275/11kV), or (b) a **DC Converter Station** or **HVDC Converter Station**.
STC Committee	The committee established under the **STC**.
Steam Unit	A **Generating Unit** whose prime mover converts the heat-energy in steam to mechanical energy.

Storage User	A **Generator** who owns or operates one or more **Electricity Storage Modules**. For the avoidance of doubt: (a) **European Regulation** (EU) 2016/631, **European Regulation** 2016/1388 and **European Regulation** 2016/1485 shall not apply to **Storage Users**; and (b) the **European Connection Conditions** (**ECC**'s) shall apply to **Storage Users** on the basis set out in Paragraph ECC1.1(d).
Subtransmission System	The part of a **User's System** which operates at a single transformation below the voltage of the relevant **Transmission System**.
Substantial Modification	A **Modification** in relation to modernisation or replacement of the **User's Main Plant and Apparatus** which impacts its technical capabilities, which, following notification by the relevant **User** to **The Company**, results in substantial amendment to the **Bilateral Agreement**.
Supergrid Voltage	Any voltage greater than 200kV.
Supplier	(a) A person supplying electricity under an **Electricity Supply Licence**; or (b) A person supplying electricity under exemption under the **Act**; in each case acting in its capacity as a supplier of electricity to **Customers** in **Great Britain**.
Surplus	A MW figure equal to the total **Output Usable:** (a) minus the forecast of **Active Power Demand**, and (b) minus the **Operational Planning Margin**.
Synchronised	(a) The condition where an incoming **Power Generating Module**, **Generating Unit** or **Power Park Module** or **DC Converter** or **HVDC Converter** or **System** is connected to the busbars of another **System** so that the **Frequencies** and phase relationships of that **Power Generating Module**, **Generating Unit**, **Power Park Module**, **DC Converter**, **HVDC Converter** or **System**, as the case may be, and the **System** to which it is connected are identical, like terms shall be construed accordingly e.g. **"Synchronism"**. (b) The condition where an importing **BM Unit** is consuming electricity.
Synchronous Electricity Storage Module	A **Synchronous Power Generating Module** which can convert or re-convert electrical energy from another source of energy such that the frequency of the generated voltage, the rotor speed and the frequency of network voltage are in a constant ratio and thus in synchronism. For the avoidance of doubt a **Synchronous Electricity Storage Module** could comprise of one or more **Synchronous Electricity Storage Units**.
Synchronous Electricity Storage Unit	A **Synchronous Generating Unit** which can supply or absorb electrical energy such that the frequency of the generated voltage, the rotor speed and the frequency of the equipment are in constant ratio and thus in synchronism with the network.

Synchronising Generation	The amount of MW (in whole MW) produced at the moment of synchronising.
Synchronising Group	A group of two or more **Gensets**) which require a minimum time interval between their **Synchronising** or **De-Synchronising** times.
Synchronous Area	An area covered by synchronously interconnected **Transmission Licensees**, such as the **Synchronous Areas** of Continental Europe, Great Britain, Ireland-Northern Ireland and Nordic and the power systems of Lithuania, Latvia and Estonia, together referred to as 'Baltic' which are part of a wider **Synchronous Area**;
Synchronous Compensation	The operation of rotating synchronous **Apparatus** for the specific purpose of either the generation or absorption of **Reactive Power**.
Synchronous Compensation Equipment	**Apparatus** which has the function of providing **Synchronous Compensation**. For the avoidance of doubt, one or more **Synchronous Compensation** units would not constitute an **Electricity Storage Module** unless it could be operated in a controllable manner.
Synchronous Electricity Storage Module	A **Synchronous Power Generating Module** which can convert and reconvert electrical energy from another source of energy such that the frequency of the generated voltage, the rotor speed and the frequency of network voltage are in a constant ratio and thus in synchronism. For the avoidance of doubt a **Synchronous Electricity Storage Module** could comprise of one or more **Synchronous Electricity Storage Units**.
Synchronous Electricity Storage Unit	A **Synchronous Generating Unit** which can supply and absorb electrical energy such that the frequency of the generated voltage, the rotor speed and the frequency of the equipment are in constant ratio and thus in synchronism with the network.
Synchronous Flywheel	An item of synchronously rotating **Plant** for the specific purpose of contributing inertia to the **System**. One or more **Synchronous Flywheels** would not be considered to form an **Electricity Storage Module** unless it could be operated in a controllable manner for its AC input and output power.
Synchronous Generating Unit	Any **Onshore Synchronous Generating Unit** or **Offshore Synchronous Generating Unit**.
Synchronous Generating Unit Performance Chart	A diagram showing the **Real Power** (MW) and **Reactive Power** (MVAr) capability limits within which a **Synchronous Generating Unit** at its stator terminals (which is part of a **Synchronous Power Generating Module**) will be expected to operate under steady state conditions.
Synchronous Power-Generating Module	An indivisible set of installations which can convert or re-convert electrical energy from another source of energy such that the frequency of the supplied voltage, the rotor speed and the frequency of network voltage are in a constant ratio and thus in synchronism. For the avoidance of doubt, a **Synchronous Power Generating Module** could comprise of one or more **Synchronous Generating Units** or one or more **Synchronous Electricity Storage Units**.
Synchronous Power Generating Module Matrix	The matrix described in Appendix 1 to BC1 under the heading **Synchronous Power Generating Module Matrix**.

Synchronous Power Generating Module Planning Matrix	A matrix in the form set out in Appendix 5 of OC2 showing the combination of **Synchronous Generating Units** within a **Synchronous Power Generating Module** which would be running in relation to any given MW output.
Synchronous Power Generating Unit	Has the same meaning as a **Synchronous Generating Unit** and would be considered to be part of a **Power Generating Module.**
Synchronous Speed	That speed required by a **Generating Unit** to enable it to be **Synchronised** to a **System**.
System	Any **User System** and/or the **National Electricity Transmission System**, as the case may be.
System Ancillary Services	Collectively **Part 1 System Ancillary Services** and **Part 2 System Ancillary Services**.
System Constraint	A limitation on the use of a **System** due to lack of transmission capacity or other **System** conditions.
System Constrained Capacity	That portion of **Registered Capacity** or Regis**tered Import Capacity** not available due to a **System Constraint**.
System Constraint Group	A part of the **National Electricity Transmission System** which, because of **System Constraints**, is subject to limits of **Active Power** which can flow into or out of (as the case may be) that part.
System Defence Plan	A document prepared by **The Company**, as published on its **Website**, outlining how the requirements of the "defence plan" (as provided for in **European Regulation (EU) 2017/2196**) has been implemented within the **GB Synchronous Area**.
System Fault Dependability Index or **Dp**	A measure of the ability of **Protection** to initiate successful tripping of circuit-breakers which are associated with a faulty item of **Apparatus**. It is calculated using the formula: **Dp** = $1 - F_1/A$ Where: A = Total number of **System** faults F_1 = Number of **System** faults where there was a failure to trip a circuit-breaker.
System Incidents Report	A report submitted to the GCRP on a monthly basis, containing, but not limited to, a list of **Significant Events**, as detailed in OC3.4.1.
System Margin	The margin in any period between (a) the sum of Maximum Export Limits and (b) forecast **Demand** and the **Operating Margin**, for that period.
System Negative Reserve Active Power Margin or **System NRAPM**	That margin of **Active Power** sufficient to allow the largest loss of **Load** at any time.

System Operator - Transmission Owner Code or **STC**	Has the meaning set out in **The Company's Transmission Licence**
System Restoration Plan	A document prepared by **The Company**, as published on its **Website**, outlining how the requirements of the "restoration plan" (as defined in **European Regulation (EU) 2017/2196**) has been implemented within the **GB Synchronous Area**.
System Telephony	An alternative method by which a **User's Responsible Engineer/Operator** and **The Company's Control Engineer(s)** speak to one and another for the purposes of control of the **Total System** in both normal operating conditions and where practicable, emergency operating conditions.
System Tests	Tests which involve simulating conditions, or the controlled application of irregular, unusual or extreme conditions, on the **Total System**, or any part of the **Total System**, but which do not include commissioning or recommissioning tests or any other tests of a minor nature.
System to Demand Intertrip Scheme	An intertrip scheme which disconnects **Demand** when a **System** fault has arisen to prevent abnormal conditions occurring on the **System**.
System to Generator Operational Intertripping	A **Balancing Service** involving the initiation by a **System to Generator Operational Intertripping Scheme** of automatic tripping of the **User's** circuit breaker(s), or **Relevant Transmission Licensee's** circuit breaker(s) where agreed by **The Company**, the **User** and the **Relevant Transmission Licensee**, resulting in the tripping of **BM Unit(s)** or (where relevant) **Generating Unit(s)** comprised in a **BM Unit** to prevent abnormal system conditions occurring, such as over voltage, overload, **System** instability, etc, after the tripping of other circuit-breakers following power **System** fault(s).
System to Generator Operational Intertripping Scheme	A **System** to **Generating Unit** or **System** to **CCGT Module** or **System** to **Power Park Module** or **System** to **Power Generating Module** or **System** to **Electricity Storage Module Intertripping Scheme** forming a condition of connection and specified in Appendix F3 of the relevant **Bilateral Agreement**, being either a **Category 1 Intertripping Scheme**, **Category 2 Intertripping Scheme**, **Category 3 Intertripping Scheme** or C**ategory 4 Intertripping Scheme**.
Target Frequency	That **Frequency** determined by **The Company**, in its reasonable opinion, as the desired operating **Frequency** of the **Total System**. This will normally be 50.00Hz plus or minus 0.05Hz, except in exceptional circumstances as determined by **The Company**, in its reasonable opinion when this may be 49.90 or 50.10Hz. An example of exceptional circumstances may be difficulties caused in operating the **System** during disputes affecting fuel supplies.
Technical Specification	In relation to **Plant** and/or **Apparatus**, (a) the relevant **European Specification**; or (b) if there is no relevant **European Specification**, other relevant standards which are in common use in the European Community.

TERRE	Trans European Replacement Reserves Exchange – a market covering the procurement of replacement reserves across Europe as described **European Regulation (EU) 2017/2195** (EBGL) and **European Regulation (EU) 2017/1485** (SOGL).
TERRE Activation Period	A period of time lasting 15 minutes and starting at either 0, 15, 30 or 45 minutes past the hour (e.g. 10:00 to 10:15). There are 4 **TERRE Activation Periods** in one **TERRE Auction Period**.
TERRE Auction Period	A period of time lasting one hour and starting and ending on the hour (e.g. from 10:00 to 11:00). Hence there are 24 **TERRE Auction Periods** in a day.
TERRE Bid	A submission by a **BM Participant** covering the price and MW deviation offered into the **TERRE** auction (please note – in the **Balancing Mechanism** the term bid has a different meaning – in this case a bid can be an upward or downward MW change).
TERRE Central Platform	An IT system which implements the **TERRE** auction.
TERRE Data Validation and Consistency Rules	A document produced by the central **TERRE** project detailing the correct format of submissions for **TERRE**.
TERRE Gate Closure	60 minutes before the start of the **TERRE Auction Period** (note still ongoing discussions if this may become 55 minutes).
TERRE Instruction Guide	Details specific rules for creating an **RR Instruction** from an **RR Acceptance**.
Test Co-ordinator	A person who co-ordinates **System Tests**.
Test Panel	A panel, whose composition is detailed in **OC12**, which is responsible, inter alia, for considering a proposed **System Test**, and submitting a **Proposal Report** and a **Test Programme**.
Test Programme	A programme submitted by the **Test Panel** to **The Company**, the **Test Proposer**, and each **User** identified by **The Company** under OC12.4.2.1, which states the switching sequence and proposed timings of the switching sequence, a list of those staff involved in carrying out the **System Test** (including those responsible for the site safety) and such other matters as the **Test Panel** deems appropriate.
Test Proposer	The person who submits a **Proposal Notice**.
The Company	National Grid Electricity System Operator Limited (NO: 11014226) whose registered office is at 1-3 Strand, London, WC2N 5EH as the person whose **Transmission Licence** Section C of such **Transmission Licence** has been given effect.
The Company Control Engineer	The nominated person employed by **The Company** to direct the operation of the **National Electricity Transmission System** or such person as nominated by **The Company**.
The Company Operational Strategy	**The Company's** operational procedures which form the guidelines for operation of the **National Electricity Transmission System**.

Total Shutdown	The situation existing when all generation has ceased and there is no electricity supply from **External Interconnections** and, therefore, the **Total System** has shutdown with the result that it is not possible for the **Total System** to begin to function again without **The Company's** directions relating to a **Black Start**.
Total System	The **National Electricity Transmission System** and all **User Systems** in the **National Electricity Transmission System Operator Area**.
Trading Point	A commercial and, where so specified in the Grid Code, an operational interface between a **User** and **The Company**, which a **User** has notified to **The Company**.
Transfer Date	Such date as may be appointed by the **Secretary of State** by order under section 65 of the **Act**.
Transmission	Means, when used in conjunction with another term relating to equipment or a site, whether defined or not, that the associated term is to be read as being part of or directly associated with the **National Electricity Transmission System**, and not of or with the **User System**.
Transmission Area	Has the meaning set out in the **Transmission Licence** of a **Transmission Licensee**.
Transmission Connected Demand Facilities	A **Demand Facility** which has a **Grid Supply Point** to the **National Electricity Transmission System**.
Transmission DC Converter	Any **Transmission Licensee Apparatus** (or **OTSUA** that will become **Transmission Licensee Apparatus** at the **OTSUA Transfer Time**) used to convert alternating current electricity to direct current electricity, or vice versa. A **Transmission Network DC Converter** (which could include an **HVDC System** owned by an **Offshore Transmission Licensee** or **Generator** in respect of **OTSUA**) is a standalone operative configuration at a single site comprising one or more converter bridges, together with one or more converter transformers, converter control equipment, essential protective and switching devices and auxiliaries, if any, used for conversion.
Transmission Entry Capacity	Has the meaning set out in the **CUSC**.
Transmission Interface Circuit	In **NGET's Transmission Area**, a **Transmission** circuit which connects a **System** operating at a voltage above 132kV to a **System** operating at a voltage of 132kV or below In **SHETL's Transmission Area** and **SPT's Transmission Area**, a **Transmission** circuit which connects a **System** operating at a voltage of 132kV or above to a **System** operating at a voltage below 132kV.
Transmission Interface Point	Means the electrical point of connection between the **Offshore Transmission System** and an **Onshore Transmission System**.
Transmission Interface Site	The site at which the **Transmission Interface Point** is located.
Transmission Licence	A licence granted under Section 6(1)(b) of the **Act**.

Transmission Licensee	**The Company** and any **Onshore Transmission Licensee** or **Offshore Transmission Licensee**.
Transmission Site	Means a site owned (or occupied pursuant to a lease, licence or other agreement) by a **Relevant Transmission Licensee** in which there is a **Connection Point**. For the avoidance of doubt, a site owned by a **User** but occupied by the **Relevant Transmission Licensee** as aforesaid, is a **Transmission Site**.
Transmission System	Has the same meaning as the term "licensee's transmission system" in the **Transmission Licence** of a **Transmission Licensee**.
Turbine Time Constant	Determined at **Registered Capacity**, the turbine time constant will be construed in accordance with the principles of the IEEE Committee Report "Dynamic Models for Steam and Hydro Turbines in Power System Studies" published in 1973 which apply to such phrase.
Type A Power Generating Module	A **Power-Generating Module** (including an **Electricity Storage Module**) with a **Grid Entry Point** or **User System Entry Point** below 110 kV and a **Maximum Capacity** of 0.8 kW or greater but less than 1MW;
Type B Power Generating Module	A **Power-Generating Module** (including an **Electricity Storage Module**) with a **Grid Entry Point** or **User System Entry Point** below 110 kV and a **Maximum Capacity** of 1MW or greater but less than 10MW;
Type C Power Generating Module	A **Power-Generating Module** (including an **Electricity Storage Module**) with a **Grid Entry Point** or **User System Entry Point** below 110 kV and a **Maximum Capacity** of 10MW or greater but less than 50MW;
Type D Power Generating Module	A **Power-generating Module**: (including an **Electricity Storage Module**): with a **Grid Entry Point** or **User System Entry Point** at, or greater than, 110 kV; or with a **Grid Entry Point** or **User System Entry Point** below 110 kV and with **Maximum Capacity** of 50MW or greater
Unbalanced Load	The situation where the **Load** on each phase is not equal.
Under-excitation Limiter	Shall have the meaning ascribed to that term in **IEC** 34-16-1:1991 [equivalent to **British Standard BS**4999 Section 116.1: 1992].
Under Frequency Relay	An electrical measuring relay intended to operate when its characteristic quantity (**Frequency**) reaches the relay settings by a decrease in **Frequency**.
Unit Board	A switchboard through which electrical power is supplied to the **Auxiliaries** of a **Generating Unit** and which is supplied by a **Unit Transformer**. It may be interconnected with a **Station Board**.
Unit Transformer	A transformer directly connected to a **Generating Unit's** terminals, and which supplies power to the **Auxiliaries** of a **Generating Unit**. Typical voltage ratios are 23/11kV and 15/6.6kV.
Unit Load Controller Response Time Constant	The time constant, expressed in units of seconds, of the power output increase which occurs in the **Secondary Response** timescale in response to a step change in **System Frequency**.

Unresolved Issues	Any relevant Grid Code provisions or **Bilateral Agreement** requirements identified by **The Company** with which the relevant **User** has not demonstrated compliance to **The Company's** reasonable satisfaction at the date of issue of the **Preliminary Operational Notification** and/or **Interim Operational Notification** and/or **Limited Operational Notification** and which are detailed in such **Preliminary Operational Notification** and/or **Interim Operational Notification** and/or **Limited Operational Notification**.
Urgent Modification	A **Grid Code Modification Proposal** treated or to be treated as an **Urgent Modification** in accordance with GR.23.
User	A term utilised in various sections of the Grid Code to refer to the persons using the **National Electricity Transmission System**, as more particularly identified in each section of the Grid Code concerned. In the **Preface** and the **General Conditions** the term means any person to whom the Grid Code applies. The term **User** includes an **EU Code User** and a **GB Code User**.
User Data File Structure	The file structure given at **DRC 18** which will be specified by **The Company** which a **Generator** or **DC Converter Station** owner or **HVDC System Owner** must use for the purposes of the **CP** or the **ECP** to submit **DRC** data Schedules and information demonstrating compliance with the Grid Code and, where applicable, with the **CUSC Contract(s)**, unless otherwise agreed by **The Company**.
User Development	In the **PC** means either **User's Plant** and/or **Apparatus** to be connected to the **National Electricity Transmission System**, or a **Modification** relating to a **User's Plant** and/or **Apparatus** already connected to the **National Electricity Transmission System**, or a proposed new connection or **Modification** to the connection within the **User System**.
User Self Certification of Compliance	A certificate, in the form attached at CP.A.2.(1) or ECP.A.2.(1) completed by a **Generator** or **DC Converter Station** owner or **HVDC System Owner** to which the **Compliance Statement** is attached which confirms that such **Plant** and **Apparatus** complies with the relevant Grid Code provisions and where appropriate, with the **CUSC Contract**(s), as identified in the **Compliance Statement** and, if appropriate, identifies any **Unresolved Issues** and/or any exceptions to such compliance and details the derogation(s) granted in respect of such exceptions.
User Site	A site owned (or occupied pursuant to a lease, licence or other agreement) by a **User** in which there is a **Connection Point**. For the avoidance of doubt, a site owned by a **Relevant Transmission Licensee** but occupied by a **User** as aforesaid, is a **User Site**.

User System	Any system owned or operated by a **User** comprising:- (a) **Power Generating Modules** or **Generating Units**; and/or (b) Systems consisting (wholly or mainly) of electric lines used for the distribution of electricity from **Grid Supply Points** or **Generating Units** or **Power Generating Modules** or other entry points to the point of delivery to **Customers**, or other **Users**; and **Plant** and/or **Apparatus** (including prior to the **OTSUA Transfer Time**, any **OTSUA**) connecting:- (c) The system as described above; or (d) **Non-Embedded Customers** equipment; to the **National Electricity Transmission System** or to the relevant other **User System**, as the case may be. The **User System** includes any **Remote Transmission Assets** operated by such **User** or other person and any **Plant** and/or **Apparatus** and meters owned or operated by the **User** or other person in connection with the distribution of electricity but does not include any part of the **National Electricity Transmission System**.
User System Entry Point	A point at which a **Power Generating Module**, **Generating Unit**, a **CCGT Module** or a **CCGT Unit** or a **Power Park Module**, or an **Electricity Storage Module** or a **DC Converter** or an **HVDC Converter**, as the case may be, which is **Embedded** connects to the **User System**.
Water Time Constant	Bears the meaning ascribed to the term "Water inertia time" in **IEC**308.
Website	The site established by **The Company** on the World-Wide Web for the exchange of information among **Users** and other interested persons in accordance with such restrictions on access as may be determined from time to time by **The Company**.
Weekly ACS Conditions	Means that particular combination of weather elements that gives rise to a level of peak **Demand** within a week, taken to commence on a Monday and end on a Sunday, which has a particular chance of being exceeded as a result of weather variation alone. This particular chance is determined such that the combined probabilities of **Demand** in all weeks of the year exceeding the annual peak **Demand** under **Annual ACS Conditions** is 50%, and in the week of maximum risk the weekly peak **Demand** under **Weekly ACS Conditions** is equal to the annual peak **Demand** under **Annual ACS Conditions**.
WG Consultation Alternative Request	Any request from an **Authorised Electricity Operator**; the **Citizens Advice** or the **Citizens Advice Scotland**, **The Company** or a **Materially Affected Party** for a **Workgroup Alternative Grid Code Modification** to be developed by the **Workgroup** expressed as such and which contains the information referred to at GR.20.16. For the avoidance of doubt, any **WG Consultation Alternative Request** does not constitute either a **Grid Code Modification Proposal** or a **Workgroup Alternative Grid Code Modification**.
Workgroup	A **Workgroup** established by the **Grid Code Review Panel** pursuant to GR.20.1;
Workgroup Consultation	As defined in GR.20.13, and any further consultation which may be directed by the **Grid Code Review Panel** pursuant to GR.20.20;

Workgroup Alternative Grid Code Modification	An alternative modification to the **Grid Code Modification Proposal** developed by the **Workgroup** under the **Workgroup** terms of reference (either as a result of a **Workgroup Consultation** or otherwise) and which is believed by a majority of the members of the **Workgroup** or by the chairman of the **Workgroup** to better facilitate the **Grid Code Objectives** than the **Grid Code Modification Proposal** or the current version of the **Grid Code**;
Zonal System Security Requirements	That generation required, within the boundary circuits defining the **System Zone**, which when added to the secured transfer capability of the boundary circuits exactly matches the **Demand** within the **System Zone**.

A number of the terms listed above are defined in other documents, such as the **Balancing and Settlement Code** and the **Transmission Licence**. Appendix 1 sets out the current definitions from the other documents of those terms so used in the Grid Code and defined in other documents for ease of reference, but does not form part of the Grid Code.

GD.2 Construction of References

GD.2.1 In the Grid Code:

(i) a table of contents, a Preface, a Revision section, headings, and the Appendix to this **Glossary and Definitions** are inserted for convenience only and shall be ignored in construing the Grid Code;

(ii) unless the context otherwise requires, all references to a particular paragraph, sub-paragraph, Appendix or Schedule shall be a reference to that paragraph, sub-paragraph Appendix or Schedule in or to that part of the Grid Code in which the reference is made;

(iii) unless the context otherwise requires, the singular shall include the plural and vice versa, references to any gender shall include all other genders and references to persons shall include any individual, body corporate, corporation, joint venture, trust, unincorporated association, organisation, firm or partnership and any other entity, in each case whether or not having a separate legal personality;

(iv) references to the words "include" or "including" are to be construed without limitation to the generality of the preceding words;

(v) unless there is something in the subject matter or the context which is inconsistent therewith, any reference to an Act of Parliament or any Section of or Schedule to, or other provision of an Act of Parliament shall be construed at the particular time, as including a reference to any modification, extension or re-enactment thereof then in force and to all instruments, orders and regulations then in force and made under or deriving validity from the relevant Act of Parliament;

(vi) where the **Glossary and Definitions** refers to any word or term which is more particularly defined in a part of the Grid Code, the definition in that part of the Grid Code will prevail (unless otherwise stated) over the definition in the **Glossary & Definitions** in the event of any inconsistency;

(vii) a cross-reference to another document or part of the Grid Code shall not of itself impose any additional or further or co-existent obligation or confer any additional or further or co-existent right in the part of the text where such cross-reference is contained;

(viii) nothing in the Grid Code is intended to or shall derogate from **The Company's** statutory or licence obligations;

(ix) a "holding company" means, in relation to any person, a holding company of such person within the meaning of section 736, 736A and 736B of the Companies Act 1985 as substituted by section 144 of the Companies Act 1989 and, if that latter section is not in force at the **Transfer Date**, as if such latter section were in force at such date;

(x) a "subsidiary" means, in relation to any person, a subsidiary of such person within the meaning of section 736, 736A and 736B of the Companies Act 1985 as substituted by section 144 of the Companies Act 1989 and, if that latter section is not in force at the **Transfer Date**, as if such latter section were in force at such date;

(xi) references to time are to London time; and

(xii) (a) Save where (b) below applies, where there is a reference to an item of data being expressed in a whole number of MW, fractions of a MW below 0.5 shall be rounded down to the nearest whole MW and fractions of a MW of 0.5 and above shall be rounded up to the nearest whole MW;

(b) In the case of the definition of **Registered Capacity** or **Maximum Capacity**, fractions of a MW below 0.05 shall be rounded down to one decimal place and fractions of a MW of 0.05 and above shall be rounded up to one decimal place.

(xiii) For the purposes of the Grid Code, physical quantities such as current or voltage are not defined terms as their meaning will vary depending upon the context of the obligation. For example, voltage could mean positive phase sequence root mean square voltage, instantaneous voltage, phase to phase voltage, phase to earth voltage. The same issue equally applies to current, and therefore the terms current and voltage should remain undefined with the meaning depending upon the context of the application. **European Regulation (EU) 2016/631** defines requirements of current and voltage but they have not been adopted as part of EU implementation for the reasons outlined above.

< END OF GLOSSARY & DEFINITIONS>

OPERATING CODE NO. 2
(OC2)

OPERATIONAL PLANNING AND DATA PROVISION

CONTENTS

(This contents page does not form part of the Grid Code)

OC2.1 INTRODUCTION

OC2.1.1 **Operating Code No. 2** ("**OC2**") is concerned with:

(a) the co-ordination of the release of **Power Generating Modules** (including **DC Connected Power Park Modules**), **Synchronous Generating Units** and **Power Park Modules**, **External Interconnections**, the **National Electricity Transmission System** and **Network Operators' Systems** for construction, repair and maintenance;

(b) provision by **The Company** of the **Surplus** for the **National Electricity Transmission System**;

(c) the provision by **Generators** of **Generation Planning Parameters** for **Gensets**, including **Synchronous Power Generating Module Planning Matrices**, **CCGT Module Planning Matrices** and **Power Park Module Planning Matrices**, to **The Company** for planning purposes only; and

(d) the agreement for release of **Existing Gas Cooled Reactor Plant** for outages in certain circumstances.

OC2.1.2 (a) **Operational Planning** involves planning, through various timescales, the matching of generation output with forecast **National Electricity Transmission System Demand** together with a reserve of generation to provide a margin, taking into account outages of certain **Power Generating Modules** (including **DC Connected Power Park Modules**), **Generating Units**, **Power Park Modules**, **External Interconnections**, **HVDC Systems** and **DC Converters**, and of parts of the **National Electricity Transmission System** and of parts of **Network Operators' Systems** which is carried out to achieve, so far as possible, the standards of security set out in **The Company's Transmission Licence**, each **Relevant Transmission Licensee's Transmission Licence** or **Electricity Distribution Licence** as the case may be.

(b) In general terms, there is an "envelope of opportunity" for the release of **Power Generating Modules** (including **DC Connected Power Park Modules**), **Synchronous Generating Units**, **Power Park Modules** and **External Interconnections**, and for the release of parts of the **National Electricity Transmission System** and parts of the **Network Operator's User Systems** for outages. The envelope is defined by the difference between the total generation output expected from **Large Power Stations**, **Medium Power Stations** and **Demand**, the operational planning margin and taking into account **External Interconnections**.

OC2.1.3 In this **OC2**, for the purpose of **Generator** and **Interconnector Owner** outage co-ordination, Year 0 means the current calendar year at any time, Year 1 means the next calendar year at any time, Year 2 means the calendar year after Year 1, etc. For the purpose of **Transmission** outage planning, Year 0 means the current **Financial Year** at any time, Year 1 means the next **Financial Year** at any time, Year 2 means the **Financial Year** after Year 1, etc. References to 'weeks' in **OC2** are to calendar weeks as defined in ISO 8601.

OC2.1.4 References in **OC2** to a **Generator's** and **Interconnector Owner's** "best estimate" shall be that **Generator's** or **Interconnector Owner's** best estimate acting as a reasonable and prudent **Generator** or **Interconnector Owner** in all the circumstances.

OC2.1.5 References to **The Company** planning the **National Electricity Transmission System** outage programme on the basis of the **Final Generation Outage Programme**, are to **The Company** planning against the **Final Generation Outage Programme** current at the time it so plans.

OC2.1.6 Where in **OC2**, data is required to be submitted or information is to be given on a particular weekday, that data does not need to be submitted and that information does not need to be given on that day if it is not a **Business Day** or it falls within a holiday period (the occurrence and length of which shall be determined by **The Company**, in its reasonable discretion, and notified to **Users**). Instead, that data shall be submitted and/or that information shall be given on such other **Business Day** as **The Company** shall, in its reasonable discretion, determine. However, **The Company** may determine that that data and/or information need not be submitted or given at all, in which case it shall notify each **User** as appropriate.

OC2.1.7 In Scotland, it may be possible with the agreement of **The Company** to reduce the administrative burden for **Users** in producing planning information where either the output or demand is small.

OC2.2 OBJECTIVE

OC2.2.1 (a) The objective of **OC2** is to seek to enable **The Company** to harmonise outages of **Power Generating Modules** (including **DC Connected Power Park Modules**), **Generating Units**, **Power Park Modules** and **External Interconnections** in order that such outages are co-ordinated (taking account of **Embedded Medium Power Stations**) between **Generators** and **Network Operators**, and that such outages are co-ordinated taking into account **National Electricity Transmission System** outages and other **System** outages, so far as possible to minimise the number and effect of constraints on the **National Electricity Transmission System** or any other **System**.

(b) In the case of **Network Operator' User Systems** directly connected to the **National Electricity Transmission System**, this means in particular that there will also need to be harmonisation of outages of **Embedded Power Generating Modules**, **Embedded Synchronous Generating Units** and **Embedded Power Park Modules**, and **National Electricity Transmission System** outages, with **Network Operators** in respect of their outages on those **Systems**.

OC2.2.2 The objective of **OC2** is also to enable the provision by **The Company** of the **Surplus** for the **National Electricity Transmission System**.

OC2.2.3 A further objective of **OC2** is to provide for the agreement for outages for **Existing Gas Cooled Reactor Plant** in certain circumstances and to enable a process to be followed in order to provide for that.

OC2.3 SCOPE

OC2.3.1 **OC2** applies to **The Company** and to **Users** which in **OC2** means:

(a) **Generators**, only in respect of their **Large Power Stations** or their **Power Stations** which are directly connected to **National Electricity Transmission System** (and the term **Generator** in this **OC2** shall be construed accordingly);

(b) **Network Operators**; and

(c) **Non-Embedded Customers**; and

(d) **HVDC System Owners** and **DC Converter Station** owners; and

(e) **Interconnector Owners** in respect of their **External Interconnections**.

OC2.3.2 **The Company** may provide to the **Relevant Transmission Licensees** any data which has been submitted to **The Company** by any **Users** in respect of **Relevant Units** pursuant to the following paragraphs of the **OC2**.

OC2.4.1.2.1

OC2.4.1.3.2 (a)

OC2.4.1.3.2 (b)

OC2.4.1.3.3

OC2.4.2.1 (a)

OC2.3.3 For the purpose of **OC2** only, the term **Output Usable** shall include the terms **Interconnector Export Capacity** and **Interconnector Import Capacity** where the term **Output Usable** is being applied to an **External Interconnection**.

OC2.4 PROCEDURE

OC2.4.1 Co-ordination of Outages

OC2.4.1.1 Under **OC2** the interaction between **The Company** and **Users** will be as follows:

(a)	Each **Generator**, and each **Interconnector Owner** and **The Company**	In respect of outages of **Power Generating Modules** (including **DC Connected Power Park Modules**), **Synchronous Generating Units**, **Power Park Modules** and **External Interconnection Circuits** and in respect of outages of other **Plant** and/or **Apparatus** directly connected to the **National Electricity Transmission System**;
(b)	**The Company** and each **Generator** and each **Inteconnector Owner**	in respect of **National Electricity Transmission System** outages relevant to each **Generator** (other than in respect of **Embedded Small Power Stations** or **Embedded Medium Power Stations**) and **Interconnector Owner**;
(c)	**The Company** and each **Network Operator**	in respect of outages of all **Embedded Large Power Stations** and in respect of outages of other **Plant** and/or **Apparatus** relating to such **Embedded Large Power Stations**;
(d)	**The Company** and each **Network Operator** and each **Non-Embedded Customer**	in respect of **National Electricity Transmission System** outages relevant to the particular **Network Operator** or **Non-Embedded Customers**;
(e)	Each **Network Operator** and each **Non-Embedded Customer** and **The Company**	in respect of **User System** outages relevant to **The Company**; and in respect of **Network Operators** only, outages of the **Network Operator's User System** that may impact upon an **Offshore Transmission System** connected to that **Network Operator's User System**.

OC2.4.1.2 Data Provison of **Output Usable** of **Power Generating Modules**, **Generating Units**, **External Interconnection Circuits** and **Power Park Modules** and the Publication of National **Surplus**.

OC2.4.1.2.1 In the event that:

a) a **Generator** referred to in OC2.3.1(a) experiences any unplanned change to the availability of a **Generating Unit** and/or **Power-Generating Module** and/or **Power Park Module** or makes a future plan which would impact the availability of a **Generating Unit** and/or **Power-Generating Module** and/or **Power Park Module** resulting in a change of level in the **Output Usable** of that **Generating Unit** and/or **Power-Generating Module** and/or **Power Park Module** below or above its previously notified availability, which is expected to last one **Settlement Period** or longer and up to three years ahead; or

b) an **Interconnector Owner** referred to in OC2.3.1(e) experiences any unplanned change to the availability of an **External Interconnection Circuit** or makes a future plan which would impact the availability of an **External Interconnection Circuit** resulting in any change in the **Output Usable** of that **External Interconnection Circuit** below or above its previously notified availability, which is expected to last one **Settlement Period** or longer and up to three years ahead;

The **Generator** or **Interconnector Owner** shall provide **The Company** with the best estimate of the revised available **Output Usable** profile using one of **The Company's** recommended platforms.

For **Generators** subject to EU Transparency Regulations the **Generator** shall provide the data within 1 hour of the unplanned change in availability occurring, and for a planned change to the availability, the **Generator** shall provide the data within 1 hour of planning the availability change in line with EU Transparency Regulations. For **Generators** not subject to EU Transparency Regulations the **Generator** shall provide the data within 24 hours of the unplanned change in availabiity occurring, and for a planned change to the availability, the **Generator** shall provide the data within 24 hours of planning the availability change**.**

For an unplanned change in availability, the **Interconnector Owner** shall provide the data within 1 hour of the unplanned change in availability occurring, and for a planned change to the availability, the **Interconnector Owner** shall provide the data within 1 hour of planning the availability change in line with EU Transparency Regulations.

If the **Generator** referred to in OC2.3.1(a) provides information relating to multi-shaft **Generating Units** then the detail of the individual shaft availability levels, that have been summed to produce the **Output Usable** should also be defined within 24 hours.

In the case of an **External Interconnection Circuit**, the details of the individual pole-capacity levels that have been summed to produce the **Output Usable** should also be defined within 24 hours.

The Company may, as appropriate, contact each **Generator** and each **Interconnector Owner** who has supplied information to seek clarification on their **Output Usable** submissions.

OC2.4.1.2.2 At a regular time interval, at least once per day (by 1600 hours) and up to every hour:

The Company will:

(i) having taken into account the information notified to it by **Generators** and **Interconnector Owners** via the process defined in OC2.4.1.2.1 and taking into account:

(1) **Demand** forecasts and details of proposed use of **Demand Control** received under **OC1**, and an **Operational Planning Margin** requirement set by **The Company** (the "OPMR"),

(2) **National Electricity Transmission System** constraints and outages,

(3) **Network Operator System** constraints and outages, known to **The Company**, and

(4) the **Output Usable** required, in its view, to meet daily total MW requirements,

Provide each **Generator** and each **Interconnector Owner** (where required by **The Company**) in writing with any suggested amendments to the provisional **Output Usable** supplied by the **Generator** and **Interconnector Owner** which **The Company** believes necessary, and will advise **Generators** with **Large Power Stations** of the **Surpluses** for the **National Electricity Transmission System** and potential export limitations, which would occur without such amendments;

(ii) calculate and submit to **BMRA**:

1. total generating **Output Usable** from **Generating Units** assumed to be available to the **Total System** (National **Output Useable**);

2. generating **Output Usable** by fuel type from **Generating Units** assumed to be available to the **Total System** (**Output Useable** by fuel type);

3. generating **Output Usable** by individual **Generating Units** assumed to be available to the **Total System** (**Output Useable** by **Generating Unit**);

4. total **Generating Plant Demand Margin** assumed to be available to the **Total System** (National Margin);

5. total **Generating Surplus** assumed to be available to the **Total System** (National Surplus);

with daily resolution, for at least the peak **Demand** of each day for 2 day-ahead to 14 day-ahead time scope, and

with weekly resolution, for at least peak **Demand** of each week for 2 week-ahead up to 3 year-ahead time scope.

The calculation under (ii) will effectively define the envelope of opportunity for outages of **Power Generating Modules** (including **DC Connected Power Park Modules**), **Synchronous Generating Units** and **Power Park Modules** covering both **Embedded** and directly connected **Large Power Stations.**

.

The Company may, as appropriate, contact each **Generator** and each **Interconnector Owner** who has supplied information to seek clarification on outages and suggest amendments.

(iii) Where a **Generator** or **Interconnector Owner** or a **Network Operator** is unhappy with the suggested amendments to its provisional outage programme (in the case of a **Generator** or **Interconnector Owner**) or such potential outages (in the case of a **Network Operator**) it may contact **The Company** to explain its concerns and **The Company** and that **Generator, Interconnector Owner** or **Network Operator** will then discuss the problem and seek to resolve it.

(iv) The possible resolution of the problem may require **The Company** or a **User** to contact other **Generators,** Interconnector Owner or **Network Operators**, and joint meetings of all parties may, if any **User** feels it would be helpful, be convened by **The Company**. The need for further discussions, be they on the telephone or at meetings, can only be determined at the time.

Each **Generator** will provide **The Company** with updated **Output Usable** as per OC2.4.1 resulting from the above for **Generating Unit, Power Generating Module** and **Power Part Module** outage programme covering both **Embedded** and non-**Embedded Large Power Stations**.

The Company will then consider the updated **Output Usable** and takes this into account in the next calculation and submission to **BMRA**.

OC2.4.1.2.3 **The Company** retains the right to contact **Generators** with **Large Power Stations**, **Interconnector Owners** and **Network Operators** in reference to planned outages of their assets in timescales beyond the European Requirements (3 years) up to the 5 year ahead period to assist in the operational planning of **National Electricity Transmisson System** outages.

OC2.4.1.3 Planning of National Electricity Transmission System Outages

OC2.4.1.3.1 Operational Planning Phase - Planning for Financial Years 2 to 5 inclusive ahead

The Company shall plan **National Electricity Transmission System** outages required in Years 2 to 5 inclusive required as a result of construction or refurbishment works. This contrasts with the planning of **National Electricity Transmission System** outages required in Years 0 and 1 ahead, when **The Company** also takes into account **National Electricity Transmission System** outages required as a result of maintenance.

Users should bear in mind that **The Company** will be planning the **National Electricity Transmission System** outage programme on the basis of the previous year's **Final Generation Outage Programme** and if in the event a **Generator's**, an **Interconnector Owner's** or **Network Operator's** outages differ from those contained in the **Final Generation Outage Programme**, or in the case of **Network Operators**, those known to **The Company**, in any way conflict with the **National Electricity Transmission System** outage programme, **The Company** need not alter the **National Electricity Transmission System** outage programme.

OC2.4.1.3.2 In each calendar year:

(a) By the end of week 8

Each **Network Operator** will notify **The Company** in writing of details of proposed outages in Years 2-5 ahead in its **User System** which may affect the performance of the **Total System** (which includes but is not limited to outages of **User System Apparatus** at **Grid Supply Points** and outages which constrain the output of **Power Generating Modules** (including **DC Connected Power Park Modules**) and/or **Synchronous Generating Units** and/or **Power Park Modules Embedded** within that **User System**).

Each **Network Operator** will notify **The Company** in writing of details of proposed outages in Years 2-5 ahead in its **User System** which may affect the declared values of **Maximum Export Capacity** and/or **Maximum Import Capacity** for each **Interface Point** within its **User System** together with the **Network Operator's** revised best estimate of the **Maximum Export Capacity** and/or **Maximum Import Capacity** during such outages. **Network Operators** will also notify **The Company** of any automatic and/or manual post fault actions that it intends to utilise or plans to utilise during such outages.

(b) By the end of week 13

Each **Generator** will inform **The Company** in writing of proposed outages in Years 2 - 5 ahead of **Generator** owned **Apparatus** (eg. busbar selectors) other than **Power Generating Modules** (including **DC Connected Power Park Modules**) and/or **Synchronous Generating Units**, and/or **Power Park Modules**, at each **Grid Entry Point**.

The Company will provide to each **Network Operator** and to each **Generator** and each **Interconnector Owner**, a copy of the information given to **The Company** under paragraph (a) above (other than the information given by that **Network Operator**). In relation to a **Network Operator**, the data must only be used by that **User** in planning and operating that **Network Operator's User System** and must not be used for any other purpose or passed on to, or used by, any other business of that **User** or to, or by, any person within any other such business or elsewhere.

(c) By the end of week 28

The Company will provide each **Network Operator** in writing with details of proposed outages in Years 2-5 ahead which may, in **The Company's** reasonable judgement, affect the performance of that **Network Operator's User System**.

(d) By the end of week 30

Where **The Company** or a **Network Operator** is unhappy with the proposed outages notified to it under (a), (b) or (c) above, as the case may be, equivalent provisions to those set out in OC2.4.1.2.1 (d) will apply.

(e) By the end of week 34

The Company will draw up a draft **National Electricity Transmission System** outage plan covering the period Years 2 to 5 ahead and **The Company** will notify each **Generator**, **Interconnector Owner** and **Network Operator** in writing of those aspects of the plan which may operationally affect such **Generator** (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**), **Interconnector Owner** or **Network Operator**. **The Company** will also indicate where a need may exist to issue other operational instructions or notifications (including but not limited to the requirement for the arming of an **Operational Intertripping** scheme) or **Emergency Instructions** to **Users** in accordance with **BC2** to allow the security of the **National Electricity Transmission System** to be maintained within the **Licence Standards**.

OC2.4.1.3.3 Operational Planning Phase - Planning for Financial Year 1 ahead

Each calendar year, **The Company** shall update the draft **National Electricity Transmission System** outage plan prepared under OC2.4.1.3.2 above and shall in addition take into account outages required as a result of maintenance work.

In each calendar year:

(a) By the end of week 13

Generators and **Non-Embedded Customers** will inform **The Company** in writing of proposed outages for Year 1 of **Generator** owned **Apparatus** at each **Grid Entry Point** (e.g. busbar selectors) other than **Power Generating Modules** (including **DC Connected Power Park Modules**), **Synchronous Generating Units** and/or **Power Park Modules** or **Non-Embedded Customer** owned **Apparatus**, as the case may be, at each **Grid Supply Point**.

(b) By the end of week 28

The Company will provide each **Network Operator** and each **Non-Embedded Customer** in writing with details of proposed outages in Year 1 ahead which may, in **The Company's** reasonable judgement, affect the performance of its **User System** or the **Non-Embedded Customer Apparatus** at the **Grid Supply Point**.

(c) By the end of week 32

Each **Network Operator** will notify **The Company** in writing with details of proposed outages in Year 1 in its **User System** which may affect the performance of the **Total System** (which includes but is not limited to outages of **User System Apparatus** at **Grid Supply Points** and outages which constrain the output of **Power Generating Modules** (including **DC Connected Power Park Modules**), **Synchronous Generating Units** and/or **Power Park Modules Embedded** within that **User System**).

Each **Network Operator** will notify **The Company** in writing of details of proposed outages in Year 1 in its **User System** which may affect the declared values of **Maximum Export Capacity** and/or **Maximum Import Capacity** for each **Interface Point** within its **User System** together with the **Network Operator's** revised best estimate of the **Maximum Export Capacity** and/or **Maximum Import Capacity** during such outages. **Network Operators** will also notify **The Company** of any automatic and/or manual post fault actions that it intends to utilise or plans to utilise during such outages.

Each **Network Operator** will also notify **The Company** in writing of any revisions to **Interface Point Target Voltage/Power Factor** data submitted pursuant to PC.A.2.5.4.2.

(d) Between the end of week 32 and the end of week 34

The Company will draw up a revised **National Electricity Transmission System** outage plan (which for the avoidance of doubt includes **Transmission Apparatus** at the **Connection Points**).

(e) By the end of week 34

The Company will notify each **Generator**, **Interconnector Owner**, and **Network Operator**, in writing, of those aspects of the **National Electricity Transmission System** outage programme which may, in **The Company's** reasonable opinion, operationally affect that **Generator** (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**), **Interconnector Owner**, or **Network Operator** including in particular proposed start dates and end dates of relevant **National Electricity Transmission System** outages.

The Company will provide to each **Network Operator** and to each **Generator** and each **Interconnector Owner** a copy of the information given to **The Company** under paragraph (c) above (other than the information given by that **Network Operator**). In relation to a **Network Operator**, the data must only be used by that **User** in planning and operating that **Network Operator's User System** and must not be used for any other purpose or passed on to, or used by, any other business of that **User** or to, or by, any person within any other such business or elsewhere.

(f) By the end of week 36

Where a **Generator**, **Interconnector Owner** or **Network Operator** is unhappy with the proposed aspects notified to it under (e) above, equivalent provisions to those set out in OC2.4.1.2.1 (d) will apply.

(g) Between the end of week 34 and 49

The Company will draw up a final **National Electricity Transmission System** outage plan covering Year 1.

(h) By the end of week 49

(i) **The Company** will complete the final **National Electricity Transmission System** outage plan for Year 1. The plan for Year 1 becomes the final plan for Year 0 when by expiry of time Year 1 becomes Year 0.

(ii) **The Company** will notify each **Generator**, each **Interconnector Owner** and each **Network Operator** in writing of those aspects of the plan which may operationally affect such **Generator** (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**), **Interconnector Owner** or **Network Operator** including in particular proposed start dates and end dates of relevant **National Electricity Transmission System** outages. **The Company** will also indicate where a need may exist to issue other operational instructions or notifications (including but not limited to the requirement for the arming of an **Operational Intertripping** scheme) or **Emergency Instructions** to **Users** in accordance with **BC2** to allow the security of the **National Electricity Transmission System** to be maintained within the **Licence Standards**. **The Company** will also inform each relevant **Non-Embedded Customer** of the aspects of the plan which may affect it.

(iii) In addition, in relation to the final **National Electricity Transmission System** outage plan for Year 1, **The Company** will provide to each **Generator** and each **Interconnector Owner** a copy of the final **National Electricity Transmission System** outage plan for that year. OC2.4.1.3.4 contains provisions whereby updates of the final **National Electricity Transmission System** outage plan are provided. The plan and the updates will be provided in writing. It should be noted that the final **National Electricity Transmission System** outage plan for Year 1 and the updates will not give a complete understanding of how the **National Electricity Transmission System** will operate in real time, where the **National Electricity Transmission System** operation may be affected by other factors which may not be known at the time of the plan and the updates. Therefore, **Users** should place no reliance on the plan or the updates showing a set of conditions which will actually arise in real time.

(i) Information Release Or Exchange

This paragraph (i) contains alternative requirements on **The Company**, paragraph (z) being an alternative to a combination of paragraphs (x) and (y). Paragraph (z) will only apply in relation to a particular **User** if **The Company** and that **User** agree that it should apply, in which case paragraphs (x) and (y) will not apply. In the absence of any relevant agreement between **The Company** and the **User**, **The Company** will only be required to comply with paragraphs (x) and (y).

Information Release To Each Network Operator And Non-Embedded Customer

Between the end of Week 34 and 49 **The Company** will upon written request:

(x) for radial systems, provide each **Network Operator** and **Non Embedded Customer** with data to allow the calculation by the **Network Operator**, and each **Non Embedded Customer**, of symmetrical and asymmetrical fault levels; and

(y) for interconnected **Systems**, provide to each **Network Operator** an equivalent network, sufficient to allow the identification of symmetrical and asymmetrical fault levels, and power flows across interconnecting **User Systems** directly connected to the **National Electricity Transmission System**; or

System Data Exchange

(z) as part of a process to facilitate understanding of the operation of the **Total System**,

(1) **The Company** will make available to each **Network Operator**, the **National Electricity Transmission System Study Network Data Files** covering Year 1 which are of relevance to that **User's System**;

(2) where **The Company** and a **User** have agreed to the use of data links between them, the making available will be by way of allowing the **User** access to take a copy of the **National Electricity Transmission System Study Network Data Files** once during that period. The **User** may, having taken that copy, refer to the copy as often as it wishes. Such access will be in a manner agreed by **The Company** and may be subject to separate agreements governing the manner of access. In the absence of agreement, the copy of the **National Electricity Transmission System Study Network Data Files** will be given to the **User** on a disc, or in hard copy, as determined by **The Company**;

(3) the data contained in the **National Electricity Transmission System Study Network Data Files** represents **The Company's** view of operating conditions although the actual conditions may be different;

(4) **The Company** will notify each **Network Operator**, as soon as reasonably practicable after it has updated the **National Electricity Transmission System Study Network Data Files** covering Year 1 that it has done so, when this update falls before the next annual update under this OC2.4.1.3.3(i). **The Company** will then make available to each **Network Operator** who has received an earlier version (and in respect of whom the agreement still exists), the updated **National Electricity Transmission System Study Network Files** covering the balance of Years 1 and 2 which remain given the passage of time, and which are of relevance to that **User's System**. The provisions of paragraphs (2) and (3) above shall apply to the making available of these updates;

(5) the data from the **National Electricity Transmission System Study Network Data Files** received by each **Network Operator** must only be used by that **User** in planning and operating that **Network Operator's User System** and must not be used for any other purpose or passed on to, or used by, any other business of that **User** or to, or by, any person within any other such business or elsewhere.

OC2.4.1.3.4 Operational Planning Phase - Planning In Financial Year 0 Down To The Programming Phase (And In The Case Of Load Transfer Capability, Also During The Programming Phase)

(a) The **National Electricity Transmission System** outage plan for Year 1 issued under OC2.4.1.3.3 shall become the plan for Year 0 when by expiry of time Year 1 becomes Year 0.

(b) Each **Generator** or **Interconnector Owner** or **Network Operator** or **Non-Embedded Customer** may at any time during Year 0, request **The Company** in writing for changes to the outages requested by them under OC2.4.1.3.3. In relation to that part of Year 0, excluding the period 1-7 weeks from the date of request, **The Company** shall determine whether the changes are possible and shall notify the **Generator**, **Interconnector Owner**, **Network Operator** or **Non-Embedded Customer** in question whether this is the case as soon as possible, and in any event within 14 days of the date of receipt by **The Company** of the written request in question.

Where **The Company** determines that any change so requested is possible and notifies the relevant **User** accordingly, **The Company** will provide to each **Network Operator**, each **Interconnector Owner**, and each **Generator** a copy of the request to which **The Company** has agreed which relates to outages on **Systems** of **Network Operators** (other than any request made by that **Network Operator**). The information must only be used by that **Network Operator** in planning and operating that **Network Operator's User System** and must not be used for any other purpose or passed on to, or used by, any other business of that **User** or to, or by, any person within any other such business or elsewhere.

(c) During Year 0 (including the **Programming Phase**) each **Network Operator** shall at **The Company's** request, make available to **The Company**, such details of automatic and manual load transfer capability of:

(i) 12MW or more (averaged over any half hour) for England and Wales

(ii) 10MW or more (averaged over any half hour) for Scotland

between Grid Supply Points.

During Year 0 (including the **Programming Phase**) each **Network Operator** shall notify **The Company** of any revisions to the information provided pursuant to OC2.4.1.3.3 (c) for **Interface Points** as soon as reasonably practicable after the **Network Operator** becomes aware of the need to make such revisions.

(d) When necessary during Year 0, **The Company** will notify each **Generator**, each **Interconnector Owner** and **Network Operator** and each **Non-Embedded Customer**, in writing of those aspects of the **National Electricity Transmission System** outage programme in the period from the 8th week ahead to the 52nd week ahead, which may, in **The Company 's** reasonable opinion, operationally affect that **Generator** (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**) **Interconnector Owner** or **Network Operator** or **Non-Embedded Customer** including in particular proposed start dates and end dates of relevant **National Electricity Transmission System** outages.

The Company will also notify changes to information supplied by **The Company** pursuant to OC2.4.1.3.3(i)(x) and (y) except where in relation to a **User** information was supplied pursuant to OC2.4.1.3.3(i)(z). In that case:-

(i) **The Company** will, by way of update of the information supplied by it pursuant to OC2.4.1.3.3(i)(z), make available at the first time in Year 0 that it updates the **National Electricity Transmission System Study Network Data Files** in respect of Year 0 (such update being an update on what was shown in respect of Year 1 which has then become Year 0) to each **Network Operator** who has received an earlier version under OC2.4.1.3.3(i)(z) (and in respect of whom the agreement still exists), the **National Electricity Transmission System Study Network Data Files** covering Year 0 which are of relevance to that **User's System**.

(ii) **The Company** will notify each relevant **Network Operator**, as soon as reasonably practicable after it has updated the **National Electricity Transmission System Study Network Data Files** covering Year 0, that it has done so. **The Company** will then make available to each such **Network Operator**, the updated **National Electricity Transmission System Study Network Data Files** covering the balance of Year 0 which remains given the passage of time, and which are of relevance to that **User's System**.

(iii) The provisions of OC2.4.1.3.3(i)(z)(2), (3) and (5) shall apply to the provision of data under this part of OC2.4.1.3.4(d) as if set out in full.

The Company will also indicate where a need may exist to issue other operational instructions or notifications (including but not limited to the requirement for the arming of an **Operational Intertripping** scheme) or **Emergency Instructions** to **Users** in accordance with **BC2** to allow the security of the **National Electricity Transmission System** to be maintained within the **Licence Standards**.

(e) In addition, by the end of each month during Year 0, **The Company** will provide to each **Generator** and each **Interconnector Owner** a notice containing any revisions to the final **National Electricity Transmission System** outage plan for Year 1, provided to the **Generator** or the **Interconnector Owner** under OC2.4.1.3.3 or previously under this provision, whichever is the more recent.

OC2.4.1.3.5 Programming Phase

(a) By 1600 hours each Thursday

(i) **The Company** shall continue to update a preliminary **National Electricity Transmission System** outage programme for the eighth week ahead, a provisional **National Electricity Transmission System** outage programme for the next week ahead and a final day ahead **National Electricity Transmission System** outage programme for the following day.

(ii) **The Company** will notify each **Generator**, **Interconnector Owner** and **Network Operator** and each **Non-Embedded Customer**, in writing of those aspects of the preliminary **National Electricity Transmission System** outage programme which may operationally affect each **Generator** (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**) or **Interconnector Owner** or **Network Operator** and each **Non-Embedded Customer** including in particular proposed start dates and end dates of relevant **National Electricity Transmission System** outages.

The Company will also notify changes to information supplied by **The Company** pursuant to OC2.4.1.3.3(i)(x) and (y) except where in relation to a **User** information was supplied pursuant to OC2.4.1.3.3(i)(z). In that case:

(1) **The Company** will, by way of update of the information supplied by it pursuant to OC2.4.1.3.3(i)(z), make available the **National Electricity Transmission System Study Network Data Files** for the next week ahead and

(2) **The Company** will notify each relevant **Network Operator**, as soon as reasonably practicable after it has updated the **National Electricity Transmission System Study Network Data Files** covering the next week ahead that it has done so, and

(3) The provisions of OC2.4.1.3.3(i)(z)(2), (3) and (5) shall apply to the provision of data under this part of OC2.4.1.3.5(a)(ii) as if set out in full.

The Company may make available, the **National Electricity Transmission System Study Network Data Files** for the next week ahead where **The Company** and a particular **User** agree, and in such case the provisions of OC2.4.1.1.3.3(i)(x) and (y) and the provisions of OC2.4.1.3.4(d) and OC2.4.1.3.5(a) which relate to OC2.4.1.1.3.3(i)(x) and (y) shall not apply. In such case, the provisions of this OC2.4.1.3.5(a)(ii)2 and 3 shall apply to the provision of the data under this part of OC2.4.1.3.5(a)(ii) as if set out in full.

The Company will also indicate where a need may exist to arm an **Operational Intertripping** scheme, emergency switching, emergency **Demand** management or other measures including the issuing of other operational instructions or notifications or **Emergency Instructions** to **Users** in accordance with **BC2** to allow the security of the **National Electricity Transmission System** to be maintained within the **Licence Standards**.

(b) By 1000 hours each Friday

Generators, **Interconnector Owners** and **Network Operators** will discuss with **The Company** and confirm in writing to **The Company**, acceptance or otherwise of the requirements detailed under OC2.4.1.3.5.

Network Operators shall confirm for the following week:

(i) the details of any outages of its **User System** that will restrict the **Maximum Export Capacity** and/or **Maximum Import Capacity** at any **Interface Points** within its **User System** for the following week; and

(ii) any changes to the previously declared values of the **Interface Point Target Voltage/Power Factor**.

(c) By 1600 hours each Friday

(i) **The Company** shall finalise the preliminary **National Electricity Transmission System** outage programme up to the seventh week ahead. **The Company** will endeavour to give as much notice as possible to a **Generator** with nuclear **Large Power Stations** which may be operationally affected by an outage which is to be included in such programme.

(ii) **The Company** shall finalise the provisional **National Electricity Transmission System** outage programme for the next week ahead.

(iii) **The Company** shall finalise the **National Electricity Transmission System** outage programme for the weekend through to the next normal working day.

(iv) In each case, **The Company** will indicate the factors set out in (a)(ii) above (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**) to the relevant **Generators** and **Network Operators** and **Non-Embedded Customers**.

(v) Where a **Generator** with nuclear **Large Power Stations** which may be operationally affected by the preliminary **National Electricity Transmission System** outage programme referred to in (i) above (acting as a reasonable operator) is concerned on grounds relating to safety about the effect which an outage within such outage programme might have on one or more of its nuclear **Large Power Stations**, it may contact **The Company** to explain its concerns and discuss whether there is an alternative way of taking that outage (having regard to technical feasibility). If there is such an alternative way, but **The Company** refuses to adopt that alternative way in taking that outage, that **Generator** may involve the **Disputes Resolution Procedure** to decide on the way the outage should be taken. If there is no such alternative way, then **The Company** may take the outage despite that **Generator's** concerns.

(d) By 1600 hours each Monday, Tuesday, Wednesday and Thursday

(i) **The Company** shall prepare a final **National Electricity Transmission System** outage programme for the following day.

(ii) **The Company** shall notify each **Generator** and **Network Operator** and **Non-Embedded Customer** in writing of the factors set out in (a)(ii) above (other than those aspects which may operationally affect **Embedded Small Power Stations** or **Embedded Medium Power Stations**).

OC2.4.2 DATA REQUIREMENTS

OC2.4.2.1 When a **Statement** of **Readiness** under the **Bilateral Agreement** and/or **Construction Agreement** is submitted, and thereafter in calendar week 24 in each calendar year,

(a) each **Generator** shall (subject to OC2.4.2.1(k)) in respect of each of its:-

(i) **Gensets** (in the case of the **Generation Planning Parameters**); and

(ii) **CCGT Units** within each of its **CCGT Modules** at a **Large Power Station** (in the case of the **Generator Performance Chart**)

(iii) **Generating Units** within each of its **Synchronous Power Generating Modules** at a **Large Power Station** (in the case of the **Power-Generating Module Performance Chart** and **Synchronous Generating Unit Performance Chart**)

submit to **The Company** in writing the **Generation Planning Parameters** and the **Generator Performance Charts** as required.

(b) Each shall meet the requirements of CC.6.3.2 or ECC.6.3.2 (as applicable) and shall reasonably reflect the true operating characteristics of the **Genset**.

(c) They shall be applied (unless revised under this **OC2** or (in the case of the **Generator Performance Chart** only) **BC1** in relation to **Other Relevant Data**) from the **Completion Date**, in the case of the ones submitted with the **Statement of Readiness**, and in the case of the ones submitted in calendar week 24, from the beginning of week 25 onwards.

(d) They shall be in the format indicated in Appendix 1 for these charts and as set out in Appendix 2 for the **Generation Planning Parameters**.

(e) Any changes to the **Generator Performance Chart** or **Generation Planning Parameters** should be notified to **The Company** promptly.

(f) **Generators** should note that amendments to the composition of the **Power Generating Module**, **CCGT Module** or **Power Park Module** at **Large Power Stations** may only be made in accordance with the principles set out in PC.A.3.2.3 or PC.A.3.2.4 respectively. If in accordance with PC.A.3.2.3 or PC.A.3.2.4 an amendment is made, any consequential changes to the **Generation Planning Parameters** should be notified to **The Company** promptly.

(g) **The Generator Performance Chart** must be as described below and demonstrate the limitation on reactive capability of the **System** voltage at 3% above nominal. It must also include any limitations on output due to the prime mover (both maximum and minimum), **Generating Unit** step up transformer or **User System**.

(i) For a **Synchronous Generating Unit** on a **Generating Unit** specific basis at the **Generating Unit** stator terminals. It must include details of the **Generating Unit** transformer parameters.

(ii) For a **Non-Synchronous Generating Unit** (excluding a **Power Park Unit**) on a **Generating Unit** specific basis at the **Grid Entry Point** (or **User System Entry Point** if **Embedded**).

(iii) For a **Power Park Module**, on a **Power Park Module** specific basis at the **Grid Entry Point** (or **User System Entry Point** if **Embedded**).

(iv) For a **DC Converter** on a **DC Converter** specific basis at the **Grid Entry Point** (or **User System Entry Point** if **Embedded**).

(v) For a **Synchronous Generating Unit** within a **Synchronous Power Generating Module**, both the **Power-Generating Module Performance Chart** and **Synchronous Generating Unit Performance Chart** should be provided.

(h) For each **CCGT Unit**, and any other **Generating Unit** or **Power Park Module** or **Power Generating Module** whose performance varies significantly with ambient temperature, the **Generator Performance Chart** (including the **Power-Generating Module Performance Chart** and **Synchronous Generating Unit Performance Chart** in the case of **Synchronous Power Generating Modules**) shall show curves for at least two values of ambient temperature so that **The Company** can assess the variation in performance over all likely ambient temperatures by a process of linear interpolation or extrapolation. One of these curves shall be for the ambient temperature at which the **Generating Unit**'s output, or **CCGT Module** or **Power-Generating Module** at a **Large Power Station** output or **Power Park Module's** output, as appropriate, equals its **Registered Capacity**.

(i) The **Generation Planning Parameters** supplied under OC2.4.2.1 shall be used by **The Company** for operational planning purposes only and not in connection with the operation of the **Balancing Mechanism** (subject as otherwise permitted in the **BC**).

(j) Each **Generator** shall in respect of each of its **Synchronous Power Generating Modules** or **CCGT Modules** (including those which are part of a **Synchronous Power Generating Module**) at **Large Power Stations** submit to **The Company** in writing a **CCGT Module Planning Matrix** and/or a **Synchronous Power-Generating Module Planning Matrix**. It shall be prepared on a best estimate basis relating to how it is anticipated the **Synchronous Power-Generating Module** or **CCGT Module** will be running and which shall reasonably reflect the true operating characteristics of the **Power-Generating Module** or **CCGT Module**. It will be applied (unless revised under this OC2) from the **Completion Date**, in the case of the one submitted with the **Statement of Readiness**, and in the case of the one submitted in calendar week 24, from the beginning of week 31 onwards. It must show the combination of **CCGT Units** or **Synchronous Power Generating Units** which would be running in relation to any given MW output, in the format indicated in Appendix 3.

Any changes must be notified to **The Company** promptly. **Generators** should note that amendments to the composition of the **CCGT Module** or **Synchronous Power-Generating Module** at **Large Power Stations** may only be made in accordance with the principles set out in PC.A.3.2.3. If in accordance with PC.A.3.2.3 an amendment is made, an updated **CCGT Module Planning Matrix** or **Synchronous Power-Generating Module Planning Matrix** must be immediately submitted to **The Company** in accordance with this OC2.4.2.1(b).

The **CCGT Module Planning Matrix** or **Synchronous Power-Generating Module Planning Matrix** will be used by **The Company** for operational planning purposes only and not in connection with the operation of the **Balancing Mechanism**.

(k) Each **Generator** shall in respect of each of its **Cascade Hydro Schemes** also submit the **Generation Planning Parameters** detailed at OC2.A.2.6 to OC2.A.2.10 for each **Cascade Hydro Scheme**. Such parameters need not also be submitted for the individual **Gensets** within such **Cascade Hydro Scheme**.

(l) Each **Generator** shall in respect of each of its **Power Park Modules** at **Large Power Stations** submit to **The Company** in writing a **Power Park Module Planning Matrix**. It shall be prepared on a best estimate basis relating to how it is anticipated the **Power Park Module** will be running and which shall reasonably reflect the operating characteristics of the **Power Park Module** and the **BM Unit** of which it forms part. It will be applied (unless revised under this **OC2**) from the **Completion Date**, in the case of the one submitted with the **Statement of Readiness**, and in the case of the one submitted in calendar week 24, from the beginning of week 31 onwards. It must show the number of each type of **Power Park Unit** in the **Power Park Module** typically expected to be available to generate and the **BM Unit** of which it forms part, in the format indicated in Appendix 4. The **Power Park Module Planning Matrix** shall be accompanied by a graph showing the variation in MW output with **Intermittent Power Source** (e.g. MW vs wind speed) for the **Power Park Module**. The graph shall indicate the typical value of the **Intermittent Power Source** for the **Power Park Module**.

Any changes must be notified to **The Company** promptly. **Generators** should note that amendments to the composition of the **Power Park Module** at **Large Power Stations** may only be made in accordance with the principles set out in PC.A.3.2.4. If in accordance with PC.A.3.2.4 an amendment is made, an updated **Power Park Module Planning Matrix** must be immediately submitted to **The Company** in accordance with this OC2.4.2.1(a).

The **Power Park Module Planning Matrix** will be used by **The Company** for operational planning purposes only and not in connection with the operation of the **Balancing Mechanism**.

(m) For each **Synchronous Generating Unit** (including **Synchronous Generating Units** within a **Power Generating Module**) where the **Generator** intends to adjust the **Generating Unit** terminal voltage in response to a MVAr output Instruction or a Target Voltage Level instruction in accordance with BC2.A.2.6 the **Generator Performance Chart** including the **Synchronous Generating Unit Performance Chart** shall show curves corresponding to the **Generating Unit** terminal voltage being controlled to its rated value and to its maximum value.

OC2.4.2.2 Each **Network Operator** shall by 1000 hrs on the day falling seven days before each **Operational Day** inform **The Company** in writing of any changes to the circuit details called for in PC.A.2.2.1 which it is anticipated will apply on that **Operational Day** (under **BC1** revisions can be made to this data).

OC2.4.2.3 Under European Commission Regulation No. 543/2013, **Users** are required to submit certain data for publication on the Central European Transparency Platform managed by the European Network of Transmission System Operators for Electricity (ENTSO-E). **The Company** is required to facilitate the collection, verification and processing of data from **Users** for onward transmission to the Central European Transparency Platform.

Each **Generator** and each **Non-Embedded Customer** connected to or using the **National Electricity Transmission System** shall provide **The Company** with such information as required by and set out in **DRC** Schedule 6 (Users' Outage Data **EU Transparency Availability Data**) in the timescales detailed therein.

OC2.4.3 NEGATIVE RESERVE ACTIVE POWER MARGINS

OC2.4.3.1 At a regular time interval, at least once each day (by 1600 hours) and up to every hour **The Company** will, taking into account the **Generation Outage Programme** and forecast of **Output Usable** supplied by each **Generator** and by each **Interconnector Owner** defined in OC2.4.1.2.1 and forecast **Demand** for the minimum **Demand** period, calculate and publish:-

(1) the level of the **System NRAPM** each day within the period 2 to 14 days ahead (inclusive) and for each week the level of risk of **System NRAPM** within the 2-52 week ahead period; and

(2) the level of the **Localised NRAPM** (currently for the main constraint between England and Scotland only) for each day within the period 2 to 14 days ahead (inclusive) having taken into account the appropriate limit on transfers to and from the **System Constraint Group** and for each week the level of risk of **Localised NRAPM** within the 2-52 week ahead period.

Outages Adjustments

(a) Under the necessary circumstances **The Company** will then contact **Generators** in respect of their **Large Power Stations** and **Interconnector Owners** to discuss outages as set out in the following paragraphs of this OC2.4.3.1.

(b) **The Company** will contact all **Generators** and **Interconnector Owners** in the case of low **System NRAPM** and will contact **Generators** in relation to relevant **Large Power Stations** and **Interconnector Owners** in the case of low **Localised NRAPM**. **The Company** will raise with each **Generator** and **Interconnector Owner** the problems it is anticipating due to the low **System NRAPM** or **Localised NRAPM** and will discuss:

(1) whether any change is possible to the estimate of **Genset** inflexibility; and

(2) whether **Genset** or **External Interconnection** outages can be taken to coincide with the periods of low **System NRAPM** or **Localised NRAPM** (as the case may be).

In relation to **Generators** with nuclear **Large Power Stations** the discussions on outages can include the issue of whether outages can be taken for re-fuelling purposes to coincide with the relevant low **System NRAPM** and/or **Localised NRAPM** periods.

(c) If agreement is reached with a **Generator** or an **Interconnector Owner**, then such **Generator** or **Interconnector Owner** will take such outage, as agreed with **The Company**, and the **Generator** or an **Interconnector Owner** will issue updates to its **Output Usable** via the data provision process defined in OC2.4.1.2.1 and **The Company** will process the updated data which will then be included in the next published update of the **System NRAPM** and/or **Localised NRAPM.**

(d) If on the day prior to an **Operational Day**, it is apparent from the **BM Unit Data** submitted by **Users** under **BC1** that **System NRAPM** and/or **Localised NRAPM** (as the case may be) is, in **The Company's** reasonable opinion, too low, then in accordance with the procedures and requirements set out in BC1.5.5 **The Company** may contact **Users** to discuss whether changes to **Physical Notifications** are possible, and if they are, will reflect those in the operational plans for the next following **Operational Day** or will, in accordance with BC2.9.4 instruct **Generators** to **De-Synchronise** a specified **Genset** for such period. In determining which **Genset** to so instruct, **BC2** provides that **The Company** will not (other than as referred to below) consider in such determination (and accordingly shall not instruct to **De-Synchronise**) any **Genset** within an **Existing Gas Cooled Reactor Plant**. **BC2** further provides that:-

(i) **The Company** is permitted to instruct to **De-Synchronise** any **Gensets** within an **Existing AGR Plant** if those **Gensets** within an **Existing AGR Plant** have failed to offer to be flexible for the relevant instance at the request of **The Company** provided the request is within the **Existing AGR Plant Flexibility Limit**.

(ii) **The Company** will only instruct to **De-Synchronise** any **Gensets** within an **Existing Magnox Reactor Plant** or within an **Existing AGR Plant** (other than under (i) above) if the level of **System NRAPM** (taken together with **System** constraints) and/or **Localised NRAPM** is such that it is not possible to avoid **De-Synchronising** such **Generating Unit** or **Power Generating Module**, and provided the power flow across each **External Interconnection** is either at zero or results in an export of power from the **Total System**. This proviso applies in all cases in the case of **System NRAPM** and in the case of **Localised NRAPM**, only when the power flow would have a relevant effect.

OC2.4.4 FREQUENCY SENSITIVE OPERATION

By 1600 hours each Wednesday

OC2.4.4.1 Using such information as **The Company** shall consider relevant including, if appropriate, forecast **Demand**, any estimates provided by **Generators** of **Genset** inflexibility and anticipated plant mix relating to operation in **Frequency Sensitive Mode**, **The Company** shall determine for the period 2 to 7 weeks ahead (inclusive) whether it is possible that there will be insufficient **Gensets** (other than those **Gensets** within **Existing Gas Cooled Reactor Plant** which are permitted to operate in **Limited Frequency Sensitive Mode** at all times under BC3.5.3) to operate in **Frequency Sensitive Mode** for all or any part of that period.

OC2.4.4.2 BC3.5.3 explains that **The Company** permits **Existing Gas Cooled Reactor Plant** other than **Frequency Sensitive AGR Units** to operate in a **Limited Frequency Sensitive Mode** at all times.

OC2.4.4.3 If **The Company** foresees that there will be an insufficiency in **Gensets** operating in a **Frequency Sensitive Mode**, it will contact **Generators** in order to seek to agree (as soon as reasonably practicable) that all or some of the **Gensets** (the MW amount being determined by **The Company** but the **Gensets** involved being determined by the **Generator**) will take outages to coincide with such period as **The Company** shall specify to enable replacement by other **Gensets** which can operate in a **Frequency Sensitive Mode**. If agreement is reached (which unlike the remainder of **OC2** will constitute a binding agreement) then such **Generator** will take such outage as agreed with **The Company**. If agreement is not reached, then the provisions of BC2.9.5 may apply.

OC2.4.5 If in **The Company 's** reasonable opinion it is necessary for both the procedure set out in OC2.4.3 (relating to **System NRAPM** and **Localised NRAPM**) and in OC2.4.4 (relating to operation in **Frequency Sensitive Mode**) to be followed in any given situation, the procedure set out in OC2.4.3 will be followed first, and then the procedure set out in OC2.4.4. For the avoidance of doubt, nothing in this paragraph shall prevent either procedure from being followed separately and independently of the other.

OC2.4.6 OPERATING MARGIN DATA REQUIREMENTS

OC2.4.6.1 Modifications to relay settings

'Relay settings' in this OC2.4.6.1 refers to the settings of **Low Frequency Relays** in respect of **Gensets** that are available for start from standby by **Low Frequency Relay** initiation with **Fast Start Capability** agreed pursuant to the **Bilateral Agreement**.

By 1600 hours each Wednesday

A change in relay settings will be sent by **The Company** no later than 1600 hours on a Wednesday to apply from 1000 hours on the Monday following. The settings allocated to particular **Large Power Stations** may be interchanged between 49.70Hz and 49.60Hz (or such other **System Frequencies** as **The Company** may have specified) provided the overall capacity at each setting and **System** requirements can, in **The Company 's** view, be met.

Between 1600 hours each Wednesday and 1200 hours each Friday

If a **Generator** wishes to discuss or interchange settings it should contact **The Company** by 1200 hours on the Friday prior to the Monday on which it would like to institute the changes to seek **The Company 's** agreement. If **The Company** agrees, **The Company** will then send confirmation of the agreed new settings.

By 1500 hours each Friday

If any alterations to relay settings have been agreed, then the updated version of the current relay settings will be sent to affected **Users** by 1500 hours on the Friday prior to the Monday on which the changes will take effect. Once accepted, each **Generator** (if that **Large Power Station** is not subject to forced outage or **Planned Outage**) will abide by the terms of its latest relay settings.

In addition, **The Company** will take account of any **Large Power Station** unavailability (as notified under OC2.4.1.2 submissions) in its total **Operating Reserve** policy.

The Company may from time to time, for confirmation purposes only, issue the latest version of the current relay settings to each affected **Generator**

OC2.4.6.2 Operational Planning Margin Requirements (OPMR)

At a regular time interval, at least once each day (by 1600 hours) and up to every hour

The Company will provide an indication of the level of **Operating Reserve** to be utilised by **The Company** in connection with the operation of the **Balancing Mechanism** covering a 2-14 day ahead period (with a daily peak demand resolution) and the 2-52 week resolution (with a weekly resolution focusing on the peak demand of the week). This level shall be purely indicative.

This **Operational Planning Margin** requirements indication will also note the possible level of **High Frequency Response** to be utilised by **The Company** in connection with the operation of the **Balancing Mechanism** in the week beginning with the **Operational Day** commencing during the subsequent Monday, which level shall be purely indicative.

OC2.4.7 In the event that:

a) a **Non-Embedded Customer** experiences the planned unavailability of its **Apparatus** resulting in the reduction of Demand of 100MW or more, or a change to the planned unavailability of its **Apparatus** resulting in a change in Demand of 100MW or more, for one Settlement Period or longer; or

b) a **Non-Embedded Customer** experiences a change in the actual availability of its **Apparatus** resulting in a change in Demand of 100MW or greater; or

c) a **Generator** experiences a planned unavailability of a **Generating Unit** and/or **Power-Generating Module** resulting in a change of 100MW or more in the **Output Usable** of that **Generating Unit** and/or **Power-Generating Module** below its previously notified availability, which is expected to last one **Settlement Period o**r longer and up to three years ahead; or

d) a **Generator** experiences a change of 100MW or more in the Maximum Export Limit of a **Generating Unit** which is expected to last one **Settlement Period** or longer; or

e) a **Generator** experiences a planned unavailability resulting in a change of 100MW or more in its aggregated **Output Usable** below its previously notified availability for a **Power Station** with a **Registered Capacity** of 200MW or more and which is expected to last one **Settlement Period** or longer and up to three years ahead, save where data has been provided pursuant to OC.2.4.7(c) above; or

f) a **Generator** experiences a change of 100MW or more in the aggregated Maximum Export Limit of a **Power Station** with a **Registered Capacity** of 200MW or more, which is expected to last one **Settlement Period** or longer, save where data has been provided pursuant to OC.2.4.7(d) above;

such **Non-Embedded Customer** or **Generator** shall provide **The Company** with the **EU Transparency Availability Data** in accordance with **DRC** Schedule 6 (Users' Outage Data) using **MODIS** and, with reference to points OC2.4.7(a) to (f), EU Transparency Regulation articles 7.1(a), 7.1(b), 15.1(a), 15.1(b), 15.1(c) and 15.1(d) respectively.

APPENDIX 1 - PERFORMANCE CHART EXAMPLES

GENERATOR PERFORMANCE CHART

KEY
A) Practical Stability Limit
B) Rated Excitation Limit
C) Restricted Excitation Limit
D) Generator or Transformer MVA Limit
E) Tap Limit (High Turns Ratio) - tap 1
F) Tap Limit (Low Turns Ratio)
G) Operating Envelope
H) High Temperature Output

GENERATOR			
MW	500.0	kV	22.0
MVA	588.0	Xd	2.10
PF	0.85	SCR	0.52
COOLING	H2 & H2O	Rotor Current	3900

TRANSFORMER			
MVA			600
Xt (Nominal)			0.160
Xt (Low Turns Ratio)			0.155
Xt (High Turns Ratio)			0.170
Tap Range	-15.0%	to	15.0%

UNIT TRANSFORMER	
MW Load	15.0
MVAr Load	12.5

SYSTEM VOLTAGE
400 kV Nominal
420 kV High

	MW	Lead (MVAr)	Lag (MVAr)
Rated MW (LV)	500	-164	309
Full Output (LV)	529	-161	257
Min Output (LV)	250	-197	425
Rated MW (HV)	485	-248	211
Min Gen (HV)	235	-236	352

	Temp°C	LV Output (MW)
Low Temperature	0	529
Site Conditions	10	500
High Temperature	30	420



Comments

Drawn by:		

Power Station	Unit
Windmill Hill	2
LV CHART	Revision: Draft
Date	11/01/2018

Synchronous Generating Unit Performance Chart within a Synchronous Power Generating Module

KEY
A) Practical Stability Limit
B) Rated Excitation Limit
C) Restricted Excitation Limit
D) Generator or Transformer MVA Limit
E) Tap Limit (High Turns Ratio) - tap 1
F) Tap Limit (Low Turns Ratio)
G) Operating Envelope
H) High Temperature Output
I) HV 0.92pf lead
J) HV 0.92pf lag

GENERATOR			
MW	460	kV	21.0
MVA	520	Xd	2.03
ROTOR CURRENT	4551	SCR	0.5185
COOLING	H2		

TRANSFORMER			
MVA			515
Xt (Nominal)			0.15
Xt (Low Turns Ratio)			0.14
Xt (High Turns Ratio)			0.16
Tap Range	-15.0%	to	15.0%

UNIT TRANSFORMER	
MW Load	7.5
MVAr Load	5.0

SYSTEM VOLTAGE
400 kV Nominal
420 kV High

	MW	Lead MVAr	Lag MVAr
Max Capacity (LV)	460	-151	242
Min Regulating Level (LV)	200	-185	365

	Temp°C	Output (MW)
High Temperature	30	400



Comments
Tap limit should take into account operation at 1.05pu Terminal Voltage AS PER ECC 6.3.8.3 as required

Drawn by		

Power Station	Unit
Windmill Hill	U1
Revision:	Draft
Date	11/01/2018

GENERATOR PERFORMANCE CHART

KEY
A) Practical Stability Limit
B) Rated Excitation Limit
C) Restricted Excitation Limit
D) Generator or Transformer MVA Limit
E) Tap Limit (High Turns Ratio) - tap 1
F) Tap Limit (Low Turns Ratio)
G) Operating Envelope
H) High Temperature Output

GENERATOR			
MW	500.0	kV	22.0
MVA	588.0	Xd	2.10
PF	0.85	SCR	0.52
COOLING	H2 & H2O	Rotor Current	3900
TRANSFORMER			
MVA			600
Xt (Nominal)			0.160
Xt (Low Turns Ratio)			0.155
Xt (High Turns Ratio)			0.170
Tap Range	-15.0%	to	15.0%
UNIT TRANSFORMER			
MW Load			15.0
MVAr Load			12.5
SYSTEM VOLTAGE			
400 kV Nominal			
420 kV High			

	MW	Lead (MVAr)	Lag (MVAr)
Rated MW (LV)	500	-164	309
Full Output (LV)	529	-161	257
Min Output (LV)	250	-197	425
Rated MW (HV)	485	-248	211
Min Gen (HV)	235	-236	352

	Temp°C	LV Output (MW)
Low Temperature	0	529
Site Conditions	10	500
High Temperature	30	420



Comments	
Drawn by:	

Power Station	Unit
Windmill Hill	2
LV CHART	Revision: Draft
Date	11/01/2018

Synchronous Generating Unit Performance Chart within a Synchronous Power Generating Module

KEY
A) Practical Stability Limit
B) Rated Excitation Limit
C) Restricted Excitation Limit
D) Generator or Transformer MVA Limit
E) Tap Limit (High Turns Ratio) - tap 1
F) Tap Limit (Low Turns Ratio)
G) Operating Envelope
H) High Temperature Output
I) HV 0.92pf lead
J) HV 0.92pf lag

(E)

GENERATOR			
MW	460	kV	21.0
MVA	520	Xd	2.03
ROTOR CURRENT	4551	SCR	0.5185
COOLING	H2		
TRANSFORMER			
MVA			515
Xt (Nominal)			0.15
Xt (Low Turns Ratio)			0.14
Xt (High Turns Ratio)			0.16
Tap Range	-15.0%	to	15.0%
UNIT TRANSFORMER			
MW Load			7.5
MVAr Load			5.0
SYSTEM VOLTAGE			
400 kV Nominal			
420 kV High			

	MW	Lead MVAr	Lag MVAr
Max Capacity (LV)	460	-151	242
Min Regulating Level (LV)	200	-185	365

	Temp°C	Output (MW)
High Temperature	30	400



Comments	
	Tap limit should take into account operation at 1.05pu Terminal Voltage AS PER ECC 6.3.8.3 as required
Drawn by	

Power Station	Unit
Windmill Hill	U1
	Revision: Draft
Date	11/01/2018

POWER PARK MODULE PERFORMANCE CHART AT THE CONNECTION POINT OR USER'S SYSTEM ENTRY POINT



LEADING LAGGING

Point A is equivalent (in MVAr) to:	0.95 leading **Power Factor** at **Rated MW** output
Point B is equivalent (in MVAr) to:	0.95 lagging **Power Factor** at **Rated MW** output
Point C is equivalent (in MVAr) to:	-5% of **Rated MW** output
Point D is equivalent (in MVAr) to:	+5% of **Rated MW** output
Point E is equivalent (in MVAr) to:	-12% of **Rated MW** output
Line F is equivalent (in MVAr) to:	Leading **Power Factor Reactive Despatch Network Restriction**
Line G is equivalent (in MVAr) to:	Lagging **Power Factor Reactive Despatch Network Restriction**

☐ Where a **Reactive Despatch Network Restriction** is in place which requires following of local voltage conditions, alternatively to Line F and G, please check this box.

APPENDIX 2 - GENERATION PLANNING PARAMETERS

OC2.A.2 Generation Planning Parameters

The following parameters are required in respect of each **Genset**.

OC2.A.2.1 Regime Unavailability

Where applicable the following information must be recorded for each **Genset**.

- Earliest synchronising time:

  Monday

  Tuesday to Friday

  Saturday to Sunday

- Latest de-synchronising time:

  Monday to Thursday

  Friday

  Saturday to Sunday

OC2.A.2.2 Synchronising Intervals

(a) The synchronising interval between **Gensets** in a **Synchronising Group** assuming all **Gensets** have been **Shutdown** for 48 hours;

(b) The **Synchronising Group** within the **Power Station** to which each **Genset** should be allocated.

OC2.A.2.3 De-Synchronising Interval

A fixed value **De-Synchronising** interval between **Gensets** within a **Synchronising Group**.

OC2.A.2.4 Synchronising Generation

The amount of MW produced at the moment of **Synchronising** assuming the **Genset** has been **Shutdown** for 48 hours.

OC2.A.2.5 Minimum Non-zero time (MNZT)

The minimum period on-load between **Synchronising** and **De-Synchronising** assuming the **Genset** has been **Shutdown** for 48 hours.

OC2.A.2.6 Run-Up rates

A run-up characteristic consisting of up to three stages from **Synchronising Generation** to **Output Usable** with up to two intervening break points assuming the **Genset** has been **Shutdown** for 48 hours.

OC2.A.2.7 Run-down rates

A run down characteristic consisting of up to three stages from **Output Usable** to **De-Synchronising** with breakpoints at up to two intermediate load levels.

OC2.A.2.8 Notice to Deviate from Zero (NDZ)

The period of time normally required to **Synchronise** a **Genset** following instruction from **The Company** assuming the **Genset** has been **Shutdown** for 48 hours.

OC2.A.2.9 Minimum Zero time (MZT)

The minimum interval between **De-Synchronising** and **Synchronising** a **Genset**.

OC2.A.2.10 Not used.

OC2.A.2.11 Gas Turbine Units loading parameters

- Loading rate for fast starting
- Loading rate for slow starting

APPENDIX 3 - CCGT MODULE PLANNING MATRIX

CCGT Module Planning Matrix Example Form

CCGT MODULE	CCGT GENERATING UNITS AVAILABLE								
	1st GT	2nd GT	3rd GT	4th GT	5th GT	6th GT	1st ST	2nd ST	3rd ST
OUTPUT USABLE	OUTPUT USABLE								
MW	150	150	150				100		
0MW to 150MW	/								
151MW to 250MW	/						/		
251MW to 300MW	/	/							
301MW to 400MW	/	/					/		
401MW to 450MW	/	/	/						
451MW to 550MW	/	/	/				/		

APPENDIX 4 - POWER PARK MODULE PLANNING MATRIX

Power Park Module Planning Matrix Example Form

BM Unit Name				
Power Park Module [unique identifier]				
POWER PARK UNIT AVAILABILITY	**POWER PARK UNITS**			
	Type A	Type B	Type C	Type D
Description (Make/Model)				
Number of units				
Power Park Module [unique identifier]				
POWER PARK UNIT AVAILABILITY	**POWER PARK UNITS**			
	Type A	Type B	Type C	Type D
Description (Make/Model)				
Number of units				

The **Power Park Module Planning Matrix** may have as many columns as are required to provide information on the different make and model for each type of **Power Park Unit** in a **Power Park Module** and as many rows as are required to provide information on the **Power Park Modules** within each **BM Unit**. The description is required to assist identification of the **Power Park Units** within the **Power Park Module** and correlation with data provided under the **Planning Code**.

APPENDIX 5 – SYNCHRONOUS POWER GENERATNG MODULE PLANNING MATRIX

Synchronous Power Generating Module Planning Matrix Example Form

SYNCHRONOUS POWER GENERATING MODULE	SYNCHRONOUS POWER GENERATING UNITS AVAILABLE								
	1st GT	2nd GT	3rd GT	4th GT	5th GT	6th GT	1st ST	2nd ST	3rd ST
	OUTPUT USABLE								
OUTPUT USABLE MW	150	150	150				100		
0MW to 150MW	/								
151MW to 250MW	/						/		
251MW to 300MW	/	/							
301MW to 400MW	/	/					/		
401MW to 450MW	/	/	/						
451MW to 550MW	/	/	/				/		

< END OF OPERATING CODE NO. 2 >

DATA REGISTRATION CODE
(DRC)

CONTENTS

(This contents page does not form part of the Grid Code)

DRC.1 INTRODUCTION

DRC.1.1 The **Data Registration Code** ("**DRC**") presents a unified listing of all data required by **The Company** from **Users** and by **Users** from **The Company**, from time to time under the **Grid Code**. The data which is specified in each section of the **Grid Code** is collated here in the **DRC**. Where there is any inconsistency in the data requirements under any particular section of the **Grid Code** and the **Data Registration Code** the provisions of the particular section of the **Grid Code** shall prevail.

DRC.1.2 The **DRC** identifies the section of the **Grid Code** under which each item of data is required.

DRC.1.3 The Code under which any item of data is required specifies procedures and timings for the supply of that data, for routine updating and for recording temporary or permanent changes to that data. All timetables for the provision of data are repeated in the **DRC**.

DRC.1.4 Various sections of the **Grid Code** also specify information which **Users** will receive from **The Company**. This information is summarised in a single schedule in the **DRC** (Schedule 9).

DRC.1.5 The categorisation of data into **DPD I** and **DPD II** is indicated in the **DRC** below.

DRC.2 OBJECTIVE

The objective of the **DRC** is to:

DRC.2.1 List and collate all the data to be provided by each category of **User** to **The Company** under the **Grid Code**.

DRC.2.2 List all the data to be provided by **The Company** to each category of **User** under the **Grid Code**.

DRC.3 SCOPE

DRC.3.1 The **DRC** applies to **The Company** and to **Users**, which in this **DRC** means:-

(a) **Generators** (including those undertaking **OTSDUW** and/or those who own and/or operate **DC Connected Power Park Modules**);

(b) **Network Operators**;

(c) **DC Converter Station** owners and **HVDC System Owners**;

(d) **Suppliers**;

(e) **Non-Embedded Customers**;

(f) **Externally Interconnected System Operators**;

(g) **Interconnector Users**;

(h) **BM Participants**; and

(i) **Pumped Storage Generators** and **Generators** in respect of Electricity **Storage Modules**.

DRC.3.2 For the avoidance of doubt, the **DRC** applies to both **GB Code Users** and **EU Code Users**.

DRC.4 DATA CATEGORIES AND STAGES IN REGISTRATION

DRC.4.1.1 Within the **DRC** each data item is allocated to one of the following three categories:

(a) **Standard Planning Data** (**SPD**)

(b) **Detailed Planning Data** (**DPD**)

(c) **Operational Data**

DRC.4.2 Standard Planning Data (SPD)

DRC.4.2.1 The **Standard Planning Data** listed and collated in this **DRC** is that data listed in Part 1 of the Appendix to the **PC**.

DRC.4.2.2 **Standard Planning Data** will be provided to **The Company** in accordance with PC.4.4 and PC.A.1.2.

DRC.4.3 Detailed Planning Data (DPD)

DRC.4.3.1 The **Detailed Planning Data** listed and collated in this **DRC** is categorised as **DPD I** and **DPD II** and is that data listed in Part 2 of the Appendix to the **PC**.

DRC.4.3.2 **Detailed Planning Data** will be provided to **The Company** in accordance with PC.4.4, PC.4.5 and PC.A.1.2.

DRC.4.4 Operational Data

DRC.4.4.1 **Operational Data** is data which is required by the **Operating Codes** and the **Balancing Codes**. Within the **DRC**, **Operational Data** is sub-categorised according to the Code under which it is required, namely **OC1**, **OC2**, **BC1** or **BC2**.

DRC.4.4.2 **Operational Data** is to be supplied in accordance with timetables set down in the relevant **Operating Codes** and **Balancing Codes** and repeated in tabular form in the schedules to the **DRC**.

DRC.5 PROCEDURES AND RESPONSIBILITIES

DRC.5.1 Responsibility For Submission And Updating Of Data

In accordance with the provisions of the various sections of the **Grid Code**, each **User** must submit data as summarised in DRC.6 and listed and collated in the attached schedules.

DRC.5.2 Methods Of Submitting Data

DRC.5.2.1 Wherever possible, the data schedules to the **DRC** are structured to serve as standard formats for data submission and such format must be used for the written submission of data to **The Company**.

DRC.5.2.2 Data must be submitted to the **Transmission Control Centre** notified by **The Company**, or to such other department or address as **The Company** may from time to time advise. The name of the person at the **User Site** who is submitting each schedule of data must be included.

DRC.5.2.3 Where a computer data link exists between a **User** and **The Company**, data may be submitted via this link. **The Company** will, in this situation, provide computer files for completion by the **User** containing all the data in the corresponding **DRC** schedule.

Data submitted can be in an electronic format using a proforma to be supplied by **The Company** or other format to be agreed annually in advance with **The Company**. In all cases the data must be complete and relate to, and relate only to, what is required by the relevant section of the **Grid Code**.

DRC.5.2.4 Other modes of data transfer, such as magnetic tape, may be utilised if **The Company** gives its prior written consent.

DRC.5.2.5 **Generators**, **HVDC System Owners** and **DC Converter Station** owners submitting data for a **Power Generating Module**, **Generating Unit**, **DC Converter**, **HVDC System**, **Power Park Module** (including **DC Connected Power Park Modules**) or **CCGT Module** before the issue of a **Final Operational Notification** should submit the **DRC** data schedules and compliance information required under the **CP** electronically using the **User Data File Structure** unless otherwise agreed with **The Company**.

DRC.5.3 Changes To User's Data

DRC.5.3.1 Whenever a **User** becomes aware of a change to an item of data which is registered with **The Company**, the **User** must notify **The Company** in accordance with each section of the Grid Code. The method and timing of the notification to **The Company** is set out in each section of the Grid Code.

DRC.5.4 Data Not Supplied

DRC.5.4.1 **Users** and **The Company** are obliged to supply data as set out in the individual sections of the **Grid Code** and repeated in the **DRC**. If a **User** fails to supply data when required by any section of the **Grid Code**, **The Company** will estimate such data if and when, in **The Company's** view, it is necessary to do so. If **The Company** fails to supply data when required by any section of the **Grid Code**, the **User** to whom that data ought to have been supplied, will estimate such data if and when, in that **User's** view, it is necessary to do so. Such estimates will, in each case, be based upon data supplied previously for the same **Plant** or **Apparatus** or upon corresponding data for similar **Plant** or **Apparatus** or upon such other information as **The Company** or that **User**, as the case may be, deems appropriate.

DRC.5.4.2 **The Company** will advise a **User** in writing of any estimated data it intends to use pursuant to DRC.5.4.1 relating directly to that **User's Plant** or **Apparatus** in the event of data not being supplied.

DRC.5.4.3 A **User** will advise **The Company** in writing of any estimated data it intends to use pursuant to DRC.5.4.1 in the event of data not being supplied.

DRC.5.5 Substituted Data

DRC.5.5.1 In the case of PC.A.4 only, if the data supplied by a **User** does not in **The Company's** reasonable opinion reflect the equivalent data recorded by **The Company**, **The Company** may estimate such data if and when, in the view of **The Company**, it is necessary to do so. Such estimates will, in each case, be based upon data supplied previously for the same **Plant** or **Apparatus** or upon corresponding data for similar **Plant** or **Apparatus** or upon such other information as **The Company** deems appropriate.

DRC.5.5.2 **The Company** will advise a **User** in writing of any estimated data it intends to use pursuant to DRC.5.5.1 relating directly to that **User's Plant** or **Apparatus** where it does not in **The Company's** reasonable opinion reflect the equivalent data recorded by **The Company**. Such estimated data will be used by **The Company** in place of the appropriate data submitted by the **User** pursuant to PC.A.4 and as such shall be deemed to accurately represent the **User's** submission until such time as the **User** provides data to **The Company's** reasonable satisfaction.

DRC.6 DATA TO BE REGISTERED

DRC.6.1 Schedules 1 to 19 attached cover the following data areas.

DRC.6.1.1 Schedule 1 – Power Generating Module, Generating Unit (or CCGT Module), Power Park Module (including DC Connected Power Park Module and Power Park Unit), HVDC System and DC Converter Technical Data.

Comprising **Power Generating Module**, **Generating Unit** (and **CCGT Module**), **Power Park Module** (including **DC Connected Power Park Module** and **Power Park Unit**) and **DC Converter** fixed electrical parameters.

DRC.6.1.2 Schedule 2 - Generation Planning Parameters

Comprising the **Genset** parameters required for **Operational Planning** studies.

DRC.6.1.3 Schedule 3 - Large Power Station Outage Programmes, Output Usable and Inflexibility Information.

Comprising generation and storage outage planning, **Output Usable** and inflexibility information at timescales down to the daily **BM Unit Data** submission.

DRC.6.1.4 Schedule 4 - Large Power Station Droop and Response Data.

Comprising data on governor **Droop** settings and **Primary**, **Secondary** and **High Frequency Response** data for **Large Power Stations**.

DRC.6.1.5 Schedule 5 – User's System Data.

Comprising electrical parameters relating to **Plant** and **Apparatus** connected to the **National Electricity Transmission System**.

DRC.6.1.6 Schedule 6 – Users Outage Information.

Comprising the information required by **The Company** for outages on the **User System**, including outages at **Power Stations** other than outages of **Gensets**

DRC.6.1.7 Schedule 7 - Load Characteristics.

Comprising the estimated parameters of load groups in respect of, for example, harmonic content and response to frequency.

DRC.6.1.8 Schedule 8 - BM Unit Data.

DRC.6.1.9 Schedule 9 - Data Supplied by The Company to Users.

DRC.6.1.10 Schedule 10 - Demand Profiles and Active Energy Data

Comprising information relating to the **Network Operators'** and **Non-Embedded Customers'** total **Demand** and **Active Energy** taken from the **National Electricity Transmission System**

DRC.6.1.11 Schedule 11 - Connection Point Data

Comprising information relating to **Demand**, demand transfer capability and the **Small Power Station**, **Medium Power Station** and **Customer** generation connected to the **Connection Point**

DRC.6.1.12 Schedule 12 - Demand Control Data

Comprising information related to **Demand Control**

DRC.6.1.13 Schedule 13 - Fault Infeed Data

Comprising information relating to the short circuit contribution to the **National Electricity Transmission System** from **Users** other than **Generators**, **HVDC System Owners** and **DC Converter Station** owners.

DRC.6.1.14 Schedule 14 - Fault Infeed Data (Generators Including Unit and Station Transformers)

Comprising information relating to the Short Circuit contribution to the **National Electricity Transmission System** from **Generators**, **HVDC System Owners** and **DC Converter Station** owners.

DRC.6.1.15 Schedule 15 – Mothballed Power Generating Module, Mothballed Generating Unit, Mothballed Power Park Module (including Mothballed DC Connected Power Park Modules), Mothballed HVDC Systems, Mothballed HVDC Converters, Mothballed DC Converters at a DC Converter Station and Alternative Fuel Data

Comprising information relating to estimated return to service times for **Mothballed Power Generating Modules**, **Mothballed Generating Units**, **Mothballed Power Park Modules** (including **Mothballed DC Connected Power Park Modules**), **Mothballed HVDC Systems**, **Mothballed HVDC Converters** and **Mothballed DC Converters at a DC Converter Station** and the capability of gas-fired **Generating Units** to operate using alternative fuels.

DRC.6.1.16 Schedule 16 – Black Start Information

Comprising information relating to **Black Start**.

DRC.6.1.17 Schedule 17 – Access Period Schedule

Comprising **Access Period** information for **Transmission Interface Circuits** within an **Access Group**.

DRC.6.1.18 Schedule 18 – Generators Undertaking OTSDUW Arrangements

Comprising electrical parameters relating to **OTSDUW Plant and Apparatus** between the **Offshore Grid Entry Point** and **Transmission Interface Point**.

DRC.6.1.19 Schedule 19 – User Data File Structure

Comprising information relating to the **User Data File Structure**.

DRC.6.2 The **Schedules** applicable to each class of **User** are as follows:

User	Schedule
Generators with **Large Power Stations**	1, 2, 3, 4, 9, 14, 15, 16, 19
Generators with **Medium Power Stations** (see notes 2, 3, 4)	1, 2 (part), 9, 14, 15, 19
Generators with **Small Power Stations** directly connected to the **National Electricity Transmission System**	1, 6, 14, 15, 19
Generators undertaking **OTSDUW** (see note 5)	18, 19
All **Users** connected directly to the **National Electricity Transmission System**	5, 6, 9
All **Users** connected directly to the **National Electricity Transmission System** other than **Generators**	10,11,13,17
All **Users** connected directly to the **National Electricity Transmission System** with **Demand**	7, 9
A **Pumped Storage Generator**, a **Generator** in respect of one or more **Electricity Storage Modules** and an **Externally Interconnected System Operator** and **Interconnector Users**	12 (as marked)
All **Suppliers**	12
All **Network Operators**	12
All **BM Participants**	8
All **DC Converter Station** owners	1, 4, 9, 14, 15, 19

Notes:

(1) **Network Operators** must provide data relating to **Small Power Stations** and/or **Customer Generating Plant Embedded** in their **Systems** when such data is requested by **The Company** pursuant to PC.A.3.1.4 or PC.A.5.1.4.

(2) The data in schedules 1, 14 and 15 need not be supplied in relation to **Medium Power Stations** connected at a voltage level below the voltage level of the **Subtransmission System** except in connection with a **CUSC Contract** or unless specifically requested by **The Company**.

(3) Each **Network Operator** within whose **System** an **Embedded Medium Power Station** not subject to a **Bilateral Agreement** or **Embedded DC Converter Station** not subject to a **Bilateral Agreement** is situated shall provide the data to **The Company** in respect of each such **Embedded Medium Power Station** or **Embedded DC Converter Station** or **HVDC System**.

(4) In the case of Schedule 2, **Generators**, **HVDC System Owners**, **DC Converter Station** owners or **Network Operators** in the case of **Embedded Medium Power Stations** not subject to a **Bilateral Agreement** or **Embedded DC Converter Stations** not subject to a **Bilateral Agreement**, would only be expected to submit data in relation to **Standard Planning Data** as required by the **Planning Code**.

(5) In the case of **Generators** undertaking **OTSDUW**, the **Generator** will need to supply **User** data in accordance with the requirements of **Large** or **Small Power Stations** (as defined in DRC.6.2) up to the **Offshore Grid Entry Point**. In addition, the **User** will also need to submit **Offshore Transmission System** data in between the **Interface Point** and its **Connection Points** in accordance with the requirements of Schedule 18.

SCHEDULE 1 – POWER GENERATING MODULE, GENERATING UNIT (OR CCGT MODULE), POWER PARK MODULE, DC CONNECTED POWER PARK MODULE, HVDC SYSTEM AND DC CONVERTER TECHNICAL DATA

ABBREVIATIONS:

SPD = **Standard Planning Data**	**DPD** = **Detailed Planning Data**
% on MVA = % on Rated MVA	**RC** = **Registered Capacity** **MC = Maximum Capacity**
% on 100 = % on 100 MVA	**OC1**, **BC1**, etc = Grid Code for which data is required

CUSC Contract =	**User** data which may be submitted to the **Relevant Transmission Licensees** by **The Company**, following the acceptance by a **User** of a **CUSC Contract**.	CUSC App. Form =	**User** data which may be submitted to the **Relevant Transmission Licensees** by **The Company**, following an application by a **User** for a **CUSC Contract**.

Note:

All parameters, where applicable, are to be measured at nominal **System Frequency**

\+ these **SPD** items should only be given in the data supplied with the application for a **CUSC Contract**.

* Asterisk items are not required for **Small Power Stations** and **Medium Power Stations**

Information is to be given on a **Unit** basis, unless otherwise stated. Where references to **CCGT Modules** are made, the columns "G1" etc should be amended to read "M1" etc, as appropriate

□ These data items may be submitted to the **Relevant Transmission Licensees** from **The Company** in respect of the **National Electricity Transmission System**. The data may be submitted to the **Relevant Transmission Licensees** in a summarised form e.g. network model; the data transferred will have been originally derived from data submitted by **Users** to **The Company**.

■ these data items may be submitted to the **Relevant Transmission Licensee** from **The Company** in respect to **Relevant Units** only. The data may be submitted to the **Relevant Transmission Licensee** in a summarised form e.g. network model; the data transferred will have been originally derived from data submitted by **Users** to **The Company**.

SCHEDULE 1 – POWER GENERATING MODULE, GENERATING UNIT (OR CCGT MODULE), POWER PARK MODULE, DC CONNECTED POWER PARK MODULE, HVDC SYSTEM AND DC CONVERTER TECHNICAL DATA

POWER STATION NAME: _____ DATE: _____

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** OR STATION DATA						
		CUSC Contract	CUSC App. Form		F.Yr. 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6
GENERATING STATION DEMANDS: **Demand** associated with the **Power Station** supplied through the **National Electricity Transmission System** or the **Generator's User System** *(PC.A.5.2)*											
- The maximum **Demand** that could occur.	MW	□		**DPD I**							
	MVAr	□		**DPD I**							
- **Demand** at specified time of annual peak half hour of **National Electricity Transmission System Demand** at **Annual ACS Conditions**.	MW	□		**DPD II**							
	MVAr	□		**DPD II**							
- **Demand** at specified time of annual minimum half-hour of **National Electricity Transmission System Demand**.	MW			**DPD II**							
	MVAr	□		**DPD II**							
		□									
(Additional **Demand** supplied through the unit transformers to be provided below)											
INDIVIDUAL **GENERATING UNIT** (OR AS THE CASE MAY BE, **SYNCHRONOUS POWER GENERATING MODULE** OR **CCGT MODULE**) DATA					G1	G2	G3	G4	G5	G6	STN
Point of connection to the **National Electricity Transmission System** (or the **Total System** if embedded) of the **Generating Unit** or **Synchronous Power Generating Module** (other than a **CCGT Unit**) or the **CCGT Module**, as the case may be in terms of geographical and electrical location and system voltage *(PC.A.3.4.1)*	Text	□	■	**SPD**							
If the busbars at the **Connection Point** are normally run in separate sections identify the section to which the **Generating Unit** (other than a **CCGT Unit**) or **Synchronous Power Generating Module** or **CCGT Module**, as the case may be is connected *(PC.A.3.1.5)*	Section Number	□	■	**SPD**							

Type of **Unit** (steam, **Gas Turbine Combined Cycle Gas Turbine Unit**, tidal, wind, storage type etc.) *(PC.A.3.2.2 (h), PC.A.3.4.4)*		□										

					G1	G2	G3	G4	G5	G6	STN
INDIVIDUAL **SYNCHRONOUS POWER GENERATING MODULE GENERATING UNIT** (OR AS THE CASE MAY BE, **CCGT MODULE**) DATA											
A list of the Generating Units and **CCGT Units** within a **Synchronous Power Generating Module** or **CCGT Module**, identifying each **CCGT Unit**, and the **Power Generating Module** or **CCGT Module** of which it forms part, unambiguously. In the case of a **Range CCGT Module**, details of the possible configurations should also be submitted. *(PC.A.3.2.2 (g))*		□	■	**SPD**							

.

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** (OR CCGT MODULE, AS THE CASE MAY BE)						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Rated MVA *(PC.A.3.3.1)*	MVA	□	■	**SPD+**							
Rated MW *(PC.A.3.3.1)*	MW	□	■	**SPD+**							
Rated terminal voltage *(PC.A.5.3.2.(a) & PC.A.5.4.2 (b))*	kV	□		**DPD I**							
*Performance Chart at **Onshore Synchronous Generating Unit** stator terminals *(PC.A.3.2.2(f)(i))*				**SPD**	(see **OC2** for specification)						
* Performance Chart of the **Offshore Synchronous Generating Unit** at the **Offshore Grid Entry Point** *(PC.A.3.2.2(f)(ii))*											
* *Synchronous Generating Unit Performance Chart (PC.A.3.2.2(f))*											
* *Power Generating Module Performance Chart of the Synchronous Power Generating Module (PC.A.3.2.2(f))*											
* Maximum terminal voltage set point *(PC.A.5.3.2.(a) & PC.A.5.4.2 (b))*	kV	□		**DPD I**							
* Terminal voltage set point step resolution – if not continuous *(PC.A.5.3.2.(a) & PC.A.5.4.2 (b))*	kV	□		**DPD I**							
***Output Usable** (on a monthly basis) *(PC.A.3.2.2(b))*	MW			**SPD**	(except in relation to **CCGT Modules** when required on a unit basis under the **Grid Code**, this data item may be supplied under Schedule 3)						
Turbo-Generator inertia constant (for synchronous machines) *(PC.A.5.3.2(a))*	MW secs /MVA	□	■	**SPD+**							
Short circuit ratio (synchronous machines) *(PC.A.5.3.2(a))*		□	■	**SPD+**							
Normal auxiliary load supplied by the **Generating Unit** at rated MW output *(PC.A.5.2.1)*	MW MVAr	□ □		**DPD II** **DPD II**							
Rated field current at rated MW and MVAr output and at rated terminal voltage *(PC.A.5.3.2 (a))*	A	□		**DPD II**							
Field current open circuit saturation curve (as derived from appropriate manufacturers' test certificates): *(PC.A.5.3.2 (a))*											
120% rated terminal volts	A	□		**DPD II**							
110% rated terminal volts	A	□		**DPD II**							
100% rated terminal volts	A	□		**DPD II**							
90% rated terminal volts	A	□		**DPD II**							
80% rated terminal volts	A	□		**DPD II**							
70% rated terminal volts	A	□		**DPD II**							
60% rated terminal volts	A	□		**DPD II**							
50% rated terminal volts	A	□		**DPD II**							
IMPEDANCES: (Unsaturated)											
Direct axis synchronous reactance *(PC.A.5.3.2(a))*	% on MVA	□		**DPD I**							
Direct axis transient reactance *(PC.A.3.3.1(a)& PC.A.5.3.2(a)*	% on MVA	□	■	**SPD+**							
Direct axis sub-transient reactance *(PC.A.5.3.2(a))*	% on MVA	□		**DPD I**							
Quad axis synch reactance *(PC.A.5.3.2(a))*	% on MVA	□		**DPD I**							
Quad axis sub-transient reactance *(PC.A.5.3.2(a))*	% on MVA	□		**DPD I**							
Stator leakage reactance *(PC.A.5.3.2(a))*	% on MVA	□		**DPD I**							
Armature winding direct current resistance. *(PC.A.5.3.2(a))*	% on MVA	□		**DPD I**							

In Scotland, negative sequence resistance *(PC.A.2.5.6 (a) (iv)*	% on MVA	□		**DPD I**								

Note:- the above data item relating to armature winding direct-current resistance need only be provided by **Generators** in relation to **Generating Units** or **Synchronous Generating Units** within **Power Generating Modules** commissioned after 1st March 1996 and in cases where, for whatever reason, the **Generator** is aware of the value of the data item.

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
TIME CONSTANTS (Short-circuit and Unsaturated)											
Direct axis transient time constant *(PC.A.5.3.2(a))*	S	□		**DPD I**							
Direct axis sub-transient time constant *(PC.A.5.3.2(a))*	S	□		**DPD I**							
Quadrature axis sub-transient time constant *(PC.A.5.3.2(a))*	S	□		**DPD I**							
Stator time constant *(PC.A.5.3.2(a))*	S	□		**DPD I**							
MECHANICAL PARAMETERS *(PC.A.5.3.2(a))*											
The number of turbine generator masses		□		DPD II							
Diagram showing the Inertia and parameters for each turbine generator mass for the complete drive train	Kgm^2	□		DPD II DPD II							
Diagram showing Stiffness constants and parameters between each turbine generator mass for the complete drive train	Nm/rad	□		DPD II DPD II							
Number of poles		□		DPD II							
Relative power applied to different parts of the turbine	%	□		DPD II							
Torsional mode frequencies	Hz	□		DPD II							
Modal damping decrement factors for the different mechanical modes		□		DPD II							
GENERATING UNIT STEP-UP TRANSFORMER											
Rated MVA *(PC.A.3.3.1 & PC.A.5.3.2)*	MVA	□	■	**SPD+**							
Voltage Ratio *(PC.A.5.3.2)*	-	□		**DPD I**							
Positive sequence reactance: *(PC.A.5.3.2)*											
Max tap	% on MVA	□	■	**SPD+**							
Min tap	% on MVA	□	■	**SPD+**							
Nominal tap	% on MVA	□	■	**SPD+**							
Positive sequence resistance: *(PC.A.5.3.2)*											
Max tap	% on MVA	□		**DPD II**							
Min tap	% on MVA	□		**DPD II**							
Nominal tap	% on MVA	□		**DPD II**							
Zero phase sequence reactance *(PC.A.5.3.2)*	% on MVA	□		**DPD II**							
Tap change range *(PC.A.5.3.2)*	+% / -%	□		**DPD II**							
Tap change step size *(PC.A.5.3.2)*	%	□		**DPD II**							
Tap changer type: on-load or off-circuit *(PC.A.5.3.2)*	On/Off	□		**DPD II**							

SCHEDULE 1 – POWER GENERATING MODULE, GENERATING UNIT (OR CCGT MODULE), POWER PARK MODULE, DC CONNECTED POWER PARK MODULE, HVDC SYSTEM AND DC CONVERTER TECHNICAL DATA

DATA DESCRIPTION	UNITS	DATA to **RTL** CUSC Contract	DATA to **RTL** CUSC App. Form	DATA CAT.	**GENERATING UNIT** OR STATION DATA G1	G2	G3	G4	G5	G6	STN
EXCITATION:											
Note: The data items requested under Option 1 below may continue to be provided by **Generators** in relation to **Generating Units** on the **System** at 9 January 1995 (in this paragraph, the "relevant date") or they may provide the new data items set out under Option 2. **Generators** must supply the data as set out under Option 2 (and not those under Option 1) for **Generating Unit** and **Synchronous Power Generating Unit** excitation control systems commissioned after the relevant date, those **Generating Unit** or **Synchronous Power Generating Unit** excitation control systems recommissioned for any reason such as refurbishment after the relevant date and **Generating Unit** or **Synchronous Power Generating Unit** excitation control systems where, as a result of testing or other process, the **Generator** is aware of the data items listed under Option 2 in relation to that **Generating Unit** or **Synchronous Power Generating Unit**.											
Option 1											
DC gain of **Excitation Loop** *(PC.A.5.3.2(c))*		□		**DPD II**							
Max field voltage *(PC.A.5.3.2(c))*	V	□		**DPD II**							
Min field voltage *(PC.A.5.3.2(c))*	V	□		**DPD II**							
Rated field voltage *(PC.A.5.3.2(c))*	V	□		**DPD II**							
Max rate of change of field volts: *(PC.A.5.3.2(c))*											
Rising	V/Sec	□		**DPD II**							
Falling	V/Sec	□		**DPD II**							
Details of **Excitation Loop** *(PC.A.5.3.2(c))* Described in block diagram form showing transfer functions of individual elements	Diagram	□		**DPD II**	(please attach)						
Dynamic characteristics of over- excitation limiter *(PC.A.5.3.2(c))*		□		**DPD II**							
Dynamic characteristics of under-excitation limiter *(PC.A.5.3.2(c))*		□		**DPD II**							
Option 2											
Exciter category, e.g. **Rotating Exciter**, or **Static Exciter** etc *(PC.A.5.3.2(c))*	Text	□	■	**SPD**							
Excitation System Nominal Response V_E *(PC.A.5.3.2(c))*	Sec^{-1}	□		**DPD II**							
Rated Field Voltage *(PC.A.5.3.2(c))* U_{fN}	V	□		**DPD II**							
No-load Field Voltage *(PC.A.5.3.2(c))* U_{fO}	V	□		**DPD II**							
Excitation System On-Load *(PC.A.5.3.2(c))* **Positive Ceiling Voltage** U_{pL+}	V	□		**DPD II**							
Excitation System No-Load *(PC.A.5.3.2(c))* **Positive Ceiling Voltage** U_{pO+}	V	□		**DPD II**							
Excitation System No-Load *(PC.A.5.3.2(c))* **Negative Ceiling Voltage** U_{pO-}	V	□		**DPD II**							
Power System Stabiliser (PSS) fitted *(PC.A.3.4.2)*	Yes/No	□	■	**SPD**							
Stator Current Limit (PC.A.5.3.2(c))	A	□		**DPD II**							
Details of **Excitation System** *(PC.A.5.3.2(c))* (including **PSS** if fitted) described in block diagram form showing transfer functions of individual elements.	Diagram	□		**DPD II**							
Details of **Over-excitation Limiter** *(PC.A.5.3.2(c))* described in block diagram form showing transfer functions of individual elements.	Diagram	□		**DPD II**							
Details of **Under-excitation Limiter** *(PC.A.5.3.2(c))* described in block diagram form showing	Diagram	□		**DPD II**							

transfer functions of individual elements.											

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
GOVERNOR AND ASSOCIATED PRIME MOVER PARAMETERS											
Note: The data items requested under Option 1 below may continue to be provided by **Generators** in relation to **Generating Units** on the **System** at 9 January 1995 (in this paragraph, the "relevant date") or they may provide the new data items set out under Option 2. **Generators** must supply the data as set out under Option 2 (and not those under Option 1) for **Generating Unit** and **Synchronous Power Generating Unit** governor control systems commissioned after the relevant date, those **Generating Unit** and **Synchronous Power Generating Unit** governor control systems recommissioned for any reason such as refurbishment after the relevant date and **Generating Unit** and **Synchronous Power Generating Unit** governor control systems where, as a result of testing or other process, the **Generator** is aware of the data items listed under Option 2 in relation to that **Generating Unit** and **Synchronous Power Generating Unit**.											
Option 1											
GOVERNOR PARAMETERS (REHEAT UNITS) *(PC.A.5.3.2(d) – Option 1(i))*											
HP Governor average gain	MW/Hz	□		**DPD II**							
Speeder motor setting range	Hz	□		**DPD II**							
HP governor valve time constant	S	□		**DPD II**							
HP governor valve opening limits		□		**DPD II**							
HP governor valve rate limits		□		**DPD II**							
Re-heat time constant (stored **Active Energy** in reheater)	S	□		**DPD II**							
IP governor average gain	MW/Hz	□		**DPD II**							
IP governor setting range	Hz	□		**DPD II**							
IP governor time constant	S	□		**DPD II**							
IP governor valve opening limits		□		**DPD II**							
IP governor valve rate limits		□		**DPD II**							
Details of acceleration sensitive elements HP & IP in governor loop		□		**DPD II**	(please attach)						
Governor block diagram showing transfer functions of individual elements		□		**DPD II**	(please attach)						
GOVERNOR (Non-reheat steam and Gas Turbines) *(PC.A.5.3.2(d) – Option 1(ii))*											
Governor average gain	MW/Hz	□		**DPD II**							
Speeder motor setting range		□		**DPD II**							
Time constant of steam or fuel governor valve	S	□		**DPD II**							
Governor valve opening limits		□		**DPD II**							
Governor valve rate limits		□		**DPD II**							
Time constant of turbine	S	□		**DPD II**							
Governor block diagram		□		**DPD II**	(please attach)						

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
(PC.A.5.3.2(d) – Option1(iii))											
BOILER & STEAM TURBINE DATA*											
Boiler time constant (Stored **Active Energy**)	S			**DPD II**							
HP turbine response ratio: (Proportion of **Primary Response** arising from HP turbine)	%			**DPD II**							
HP turbine response ratio: (Proportion of **High Frequency Response** arising from HP turbine)	%			**DPD II**							
		End of Option 1									
Option 2											
All **Generating Units** and **Synchronous Power Generating Units**											
Governor Block Diagram showing transfer function of individual elements including acceleration sensitive elements		□		**DPD II**							
Governor Time Constant *(PC.A.5.3.2(d) – Option2(i))*	Sec	□		**DPD II**							
# Governor Deadband *(PC.A.5.3.2(d) – Option2(i))*											
- Maximum Setting	±Hz			**DPD II**							
- Normal Setting	±Hz			**DPD II**							
- Minimum Setting	±Hz			**DPD II**							
Speeder Motor Setting Range *(PC.A.5.3.2(d) – Option2(i))*	%	□		**DPD II**							
Average Gain *(PC.A.5.3.2(d) – Option2(i))*	MW/Hz	□		**DPD II**							
Steam Units *(PC.A.5.3.2(d) – Option2(ii))*											
HP Valve Time Constant	sec	□		**DPD II**							
HP Valve Opening Limits	%	□		**DPD II**							
HP Valve Opening Rate Limits	%/sec	□		**DPD II**							
HP Valve Closing Rate Limits	%/sec	□		**DPD II**							
HP Turbine Time Constant *(PC.A.5.3.2(d) – Option2(ii))*	sec	□		**DPD II**							
IP Valve Time Constant	sec	□		**DPD II**							
IP Valve Opening Limits	%	□		**DPD II**							
IP Valve Opening Rate Limits	%/sec	□		**DPD II**							
IP Valve Closing Rate Limits	%/sec	□		**DPD II**							
IP Turbine Time Constant *(PC.A.5.3.2(d) – Option2(ii))*	sec	□		**DPD II**							
LP Valve Time Constant	sec	□		**DPD II**							
LP Valve Opening Limits	%	□		**DPD II**							
LP Valve Opening Rate Limits	%/sec	□		**DPD II**							
LP Valve Closing Rate Limits	%/sec	□		**DPD II**							
LP Turbine Time Constant *(PC.A.5.3.2(d) – Option2(ii))*	sec	□		**DPD II**							
Reheater Time Constant	sec			**DPD II**							
Boiler Time Constant	sec			**DPD II**							
HP Power Fraction	%			**DPD II**							
IP Power Fraction	%			**DPD II**							

Where the generating unit or synchronous power generating unit governor does not have a selectable deadband facility, then the actual value of the deadband need only be provided.

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Gas Turbine Units											
(PC.A.5.3.2(d) – Option 2(iii))											
Inlet Guide Vane Time Constant	sec	□		**DPD II**							
Inlet Guide Vane Opening Limits	%	□		**DPD II**							
Inlet Guide Vane Opening Rate Limits	%/sec	□		**DPD II**							
Inlet Guide Vane Closing Rate Limits	%/sec	□		**DPD II**							
(PC.A.5.3.2(d) – Option 2(iii))											
Fuel Valve Time Constant	sec	□		**DPD II**							
Fuel Valve Opening Limits	%	□		**DPD II**							
Fuel Valve Opening Rate Limits	%/sec	□		**DPD II**							
Fuel Valve Closing Rate Limits	%/sec	□		**DPD II**							
(PC.A.5.3.2(d) – Option 2(iii))											
Waste Heat Recovery Boiler Time Constant											
Hydro **Generating Units**											
(PC.A.5.3.2(d) – Option 2(iv))											
Guide Vane Actuator Time Constant	sec	□		**DPD II**							
Guide Vane Opening Limits	%	□		**DPD II**							
Guide Vane Opening Rate Limits	%/sec	□		**DPD II**							
Guide Vane Closing Rate Limits	%/sec	□		**DPD II**							
Water Time Constant	sec	□		**DPD II**							
Synchronous Electricity Storage Units and **Modules** (PC.A.5.3.2(d) – Option 2(v)											
Valve Actuator Time Constant	sec	□		DPD II							
Valve Opening Limits	%	□		DPD II							
Valve Opening Rate Limits	%/sec	□		DPD II							
Valve Closing Rate Limits	%/sec	□		DPD II							
For **Synchronous Electricity Storage Modules** which are derived from compressed air energy storage systems the above data should be provided. For other **Synchronous Electricity Storage Modules** data should be supplied as required by **The Company** in accordance with PC.A.7.											
		End of Option 2									
UNIT CONTROL OPTIONS*											
(PC.A.5.3.2(e)											
Maximum droop	%			**DPD II**							
Normal droop	%	□		**DPD II**							
Minimum droop	%			**DPD II**							
Maximum **Governor Deadband**				**DPD II**							
Normal **Governor Deadband**				**DPD II**							
Minimum **Governor Deadband**											
Maximum **Frequency Response Deadband**[1]	±Hz			**DPD II**							
Normal **Frequency Response Deadband**[1]	±Hz			**DPD II**							
Minimum **Frequency Response Deadband**[1]	±Hz			**DPD II**							
Maximum **Frequency Response Insensitivity**[1]	±Hz			**DPDII**							
Normal **Frequency Response Insensitivity**[1]	±Hz			**DPDII**							
Minimum **Frequency Response Insensitivity**[1]	±Hz			**DPDII**							

	±Hz										
	±Hz										
	±Hz										
Frequency settings between which Unit Load Controller droop applies:											
Maximum	Hz			**DPD II**							
Normal	Hz			**DPD II**							
Minimum	Hz			**DPD II**							
Sustained response normally selected	Yes/No			**DPD II**							
[1] Data required only in respect of **Large Power Stations** comprising **Type C** and **Type D Power Generating Modules** owned and operated by **EU Code Generators**.											

SCHEDULE 1 – POWER GENERATING MODULE, GENERATING UNIT (OR CCGT MODULE), POWER PARK MODULE, DC CONNECTED POWER PARK MODULE, HVDC SYSTEM AND DC CONVERTER TECHNICAL DATA

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**POWER PARK UNIT** (OR **POWER PARK MODULE**, AS THE CASE MAY BE)						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Power Park Module Rated MVA *(PC.A.3.3.1(a))*	MVA	□	■	**SPD+**							
Power Park Module Rated MW *(PC.A.3.3.1(a))*	MW	□	■	**SPD+**							
*Performance Chart of a **Power Park Module** at the connection point *(PC.A.3.2.2(f)(ii))*				**SPD**	(see **OC2** for specification)						
***Output Usable** (on a monthly basis) *(PC.A.3.2.2(b))*	MW			**SPD**	(except in relation to **CCGT Modules** when required on a unit basis under the **Grid Code**, this data item may be supplied under Schedule 3)						
Number & Type of **Power Park Units** within each **Power Park Module** *(PC.A.3.2.2(k))*		□		**SPD**							
Number & Type of **Offshore Power Park Units** within each **Offshore Power Park String** and the number of **Offshore Power Park Strings** and connection point within each **Offshore Power Park Module** *(PC.A.3.2.2.(k))*				**SPD**							
In the case where an appropriate **Manufacturer's Data & Performance Report** is registered with **The Company** then subject to **The Company's** agreement, the report reference may be given as an alternative to completion of the following sections of this Schedule 1 to the end of page 11 with the exception of the sections marked thus # below.	Reference the **Manufacturer's Data & Performance Report**			**SPD**							
Power Park Unit Model (including **Non Synchronous Electricity Storage Units**) - A validated mathematical model in accordance with PC.5.4.2 (a)	Transfer function block diagram and algebraic equations, simulation and measured test results	□		**DPD II**							

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**POWER PARK UNIT** (OR **POWER PARK MODULE**, AS THE CASE MAY BE)						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Power Park Unit Data (where applicable)											
Rated MVA *(PC.A.3.3.1(e))*	MVA	□	■	**SPD+**							
Rated MW *(PC.A.3.3.1(e))*	MW	□	■	**SPD+**							
Rated terminal voltage *(PC.A.3.3.1(e))*	V	□	■	**SPD+**							
Site minimum air density *(PC.A.5.4.2(b))*	kg/m^3	□	■	**DPD II**							
Site maximum air density	kg/m^3	□	■	**DPD II**							
Site average air density	kg/m^3	□	■	**DPD II**							
Year for which air density data is submitted		□	■	**DPD II**							
Number of pole pairs		□		**DPD II**							
Blade swept area	m^2	□		**DPD II**							
Gear Box Ratio		□		**DPD II**							
Stator Resistance *(PC.A.5.4.2(b))*	% on MVA	□	■	**SPD+**							
Stator Reactance *(PC.A.3.3.1(e))*	% on MVA	□	■	**SPD+**							
Magnetising Reactance *(PC.A.3.3.1(e))*	% on MVA	□	■	**SPD+**							
Rotor Resistance (at starting). *(PC.A.5.4.2(b))*	% on MVA	□		**DPD II**							
Rotor Resistance (at rated running) *(PC.A.3.3.1(e))*	% on MVA	□	■	**SPD+**							
Rotor Reactance (at starting). *(PC.A.5.4.2(b))*	% on MVA	□		**DPD II**							
Rotor Reactance (at rated running) *(PC.A.3.3.1(e))*	% on MVA	□	■	**SPD**							
Equivalent inertia constant of the first mass (e.g. wind turbine rotor and blades) at minimum speed *(PC.A.5.4.2(b))*	MW secs /MVA	□	■	**SPD+**							
Equivalent inertia constant of the first mass (e.g. wind turbine rotor and blades) at synchronous speed *(PC.A.5.4.2(b))*	MW secs /MVA	□	■	**SPD+**							
Equivalent inertia constant of the first mass (e.g. wind turbine rotor and blades) at rated speed *(PC.A.5.4.2(b))*	MW secs /MVA	□	■	**SPD+**							
Equivalent inertia constant of the second mass (e.g. generator rotor) at minimum speed *(PC.A.5.4.2(b))*	MW secs /MVA	□	■	**SPD+**							
Equivalent inertia constant of the second mass (e.g. generator rotor) at synchronous speed *(PC.A.5.4.2(b))*	MW secs /MVA	□	■	**SPD+**							
Equivalent inertia constant of the second mass (e.g. generator rotor) at rated speed *(PC.A.5.4.2(b))*	MW secs /MVA	□	■	**SPD+**							
Equivalent shaft stiffness between the two masses *(PC.A.5.4.2(b))*	Nm / electrical radian	□	■	**SPD+**							

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**POWER PARK UNIT** (OR **POWER PARK MODULE**, AS THE CASE MAY BE)						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Minimum generator rotor speed (Doubly Fed Induction Generators) *(PC.A.3.3.1(e))*	RPM	□	■	**SPD+**							
Maximum generator rotor speed (Doubly Fed Induction Generators) *(PC.A.3.3.1(e))*	RPM	□	■	**SPD+**							
The optimum generator rotor speed versus wind speed *(PC.A.5.4.2(b))*	tabular format	□		**DPD II**							
Power Converter Rating (Doubly Fed Induction Generators) *(PC.A.5.4.2(b))*	MVA	□	■	**DPD II**							
The rotor power coefficient (C_p) versus tip speed ratio (λ) curves for a range of blade angles (where applicable) (*PC.A.5.4.2(b)*)	Diagram + tabular format	□		**DPD II**							
# The electrical power output versus generator rotor speed for a range of wind speeds over the entire operating range of the **Power Park Unit**. *(PC.A.5.4.2(b))*	Diagram + tabular format	□		**DPD II**							
The blade angle versus wind speed curve *(PC.A.5.4.2(b))*	Diagram + tabular format	□		**DPD II**							
The electrical power output versus wind speed over the entire operating range of **the Power Park Unit**. *(PC.A.5.4.2(b))*	Diagram + tabular format	□		**DPD II**							
Transfer function block diagram, parameters and description of the operation of the power electronic converter including fault ride though capability (where applicable). *(PC.A.5.4.2(b))*	Diagram	□		**DPD II**							
For a **Power Park Unit** consisting of a synchronous machine in combination with a back to back **DC Converter** or **HVDC Converter**, or for a **Power Park Unit** not driven by a wind turbine, the data to be supplied shall be agreed with **The Company** in accordance with PC.A.7. *(PC.A.5.4.2(b))*		□									

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**POWER PARK UNIT** (OR **POWER PARK MODULE**, AS THE CASE MAY BE)						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Torque / Speed and blade angle control systems and parameters *(PC.A.5.4.2(c))* For the **Power Park Unit**, details of the torque / speed controller and blade angle controller in the case of a wind turbine and power limitation functions (where applicable) described in block diagram form showing transfer functions and parameters of individual elements	Diagram	□		**DPD II**							
# Voltage/**Reactive Power**/**Power Factor** control system parameters *(PC.A.5.4.2(d))* # For the **Power Park Unit** and **Power Park Module** details of **Voltage/Reactive Power/Power Factor** controller (and **PSS** if fitted) described in block diagram form including parameters showing transfer functions of individual elements.	Diagram	□		**DPD II**							
# Frequency control system parameters *(PC.A.5.4.2(e))* # For the **Power Park Unit** and **Power Park Module** details of the **Frequency** controller described in block diagram form showing transfer functions and parameters of individual elements.	Diagram	□		**DPD II**							
As an alternative to PC.A.5.4.2 (a), (b), (c), (d), (e) and (f), is the submission of a single complete model that consists of the full information required under PC.A.5.4.2 (a), (b), (c), (d) (e) and (f) provided that all the information required under PC.A.5.4.2 (a), b), (c), (d), (e) and (f) individually is clearly identifiable. *(PC.A.5.4.2(g))*	Diagram	□		**DPD II**							
# Harmonic Assessment Information *(PC.A.5.4.2(h))* (as defined in IEC 61400-21 (2001)) for each **Power Park Unit**:-											
# Flicker coefficient for continuous operation		□		**DPD I**							
# Flicker step factor		□		**DPD I**							
# Number of switching operations in a 10 minute window		□		**DPD I**							
# Number of switching operations in a 2 hour window		□		**DPD I**							
# Voltage change factor		□		**DPD I**							
# Current Injection at each harmonic for each **Power Park Unit** and for each **Power Park Module**	Tabular format	□		**DPD I**							
Note:- **Generators** who own or operate **DC Connected Power Park Modules** shall supply all data for their **DC Connected Power Park Modules** as applicable to **Power Park Modules**.											

HVDC SYSTEM AND DC CONVERTER STATION TECHNICAL DATA

HVDC SYSTEM OR DC CONVERTER STATION NAME DATE:_____

Data Description	Units	DATA to **RTL**		Data Category	**DC Converter Station** Data
(PC.A.4)		CUSC Contract	CUSC App. Form		
HVDC SYSTEM AND **DC CONVERTER STATION** DEMANDS:					
Demand supplied through **Station Transformers** associated with the **DC Converter Station** and **HVDC System [PC.A.4.1]**	MW MVAr	□ □		**DPD II** **DPD II**	
- **Demand** with all **DC Converters** and **HVDC Converters** within and HVDc System operating at **Rated MW** import.	MW MVAr	□ □		**DPD II** **DPD II**	
- **Demand** with all **DC Converters** and **HVDC Converters** within an HVDC System operating at **Rated MW** export.					
Additional **Demand** associated with the **DC Converter Station or HVDC System** supplied through the **National Electricity Transmission System**. **[PC.A.4.1]**	MW MVAr	□ □		**DPD II** **DPD II**	
- The maximum **Demand** that could occur.	MW MVAr	□ □ □		**DPD II** **DPD II**	
- **Demand** at specified time of annual peak half hour of **The Company Demand** at **Annual ACS Conditions**.	MW MVAr	□ □		**DPD II** **DPD II**	
- **Demand** at specified time of annual minimum half-hour of **The Company Demand**.	Text	□ □	■	**SPD+**	
DC CONVERTER STATION AND **HVDC SYSTEM** DATA	Text	□	■	**SPD+**	
Number of poles, i.e. number of **DC Converters** or **HVDC Converters** within the **HVDC System**		□	■ ■ ■ ■ ■ ■	**SPD+**	
Pole arrangement (e.g. monopole or bipole)		□	■	**SPD**	
Details of each viable operating configuration	Diagram Diagram	□			
Configuration 1	Diagram				
Configuration 2	Diagram	□			
Configuration 3	Diagram	□			

Configuration 4 Configuration 5 Configuration 6 Remote ac connection arrangement	Diagram Diagram	□ □ □ □			

SCHEDULE 1 – POWER PARK MODULE, GENERATING UNIT (OR CCGT MODULE), POWER PARK MODULE, DC CONNECTED POWER PARK MODULE, HVDC SYSTEM AND DC CONVERTER TECHNICAL DATA

Data Description	Units	DATA to **RTL**		Data Category	Operating Configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
DC CONVERTER STATION AND HVDC SYSTEM DATA *(PC.A.3.3.1d)*										
DC Converter or **HVDC Converter** Type (e.g. current or Voltage source)	Text	□	■	**SPD**						
Point of connection to the **National Electricity Transmission System** (or the **Total System** if **Embedded**) of the **DC Converter Station** or **HVDC System** configuration in terms of geographical and electrical location and system voltage	Text	□	■	**SPD**						
If the busbars at the **Connection Point** are normally run in separate sections identify the section to which the **DC Converter Station** or **HVDC System** configuration is connected	Section Number	□	■	**SPD**						
	MW			**SPD +**						
Rated MW import per pole **[PC.A.3.3.1]**	MW	□	■	**SPD +**						
Rated MW export per pole **[PC.A.3.3.1]**		□	■							

Data Description	Units	DATA to **RTL**		Data Category	Operating Configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
ACTIVE POWER TRANSFER CAPABILITY (PC.A.3.2.2)										
Registered Capacity	MW	□	■	**SPD**						
Registered Import Capacity	MW	□	■							
Minimum Generation	MW	□	■	**SPD**						
Minimum Import Capacity	MW	□	■							
Maximum HVDC Active Power Transmission Capacity	MW	□		**SPD**						
Minimum Active Power Transmission Capacity	MW	□		**SPD**						
Import MW available in excess of **Registered Import Capacity** and **Maximum Active Power Transmission Capacity**	MW	□		**SPD**						
Time duration for which MW in excess of **Registered Import Capacity** is available	Min	□		**SPD**						
Export MW available in excess of **Registered Capacity** and **Maximum Active Power Transmission Capacity**.	MW	□		**SPD**						
Time duration for which MW in excess of **Registered Capacity** is available	Min	□		**SPD**						

Data Description	Units	DATA to **RTL**		Data Category	Operating Configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
DC CONVERTER AND **HVDC CONVERTER** TRANSFORMER **[PC.A.5.4.3.1]**										
Rated MVA	MVA	□		**DPD II**						
Winding arrangement										
Nominal primary voltage	kV	□		**DPD II**						
Nominal secondary (converter-side) voltage(s)	kV	□		**DPD II**						
Positive sequence reactance										
Maximum tap	% on MVA	□		**DPD II**						
Nominal tap	% on MVA	□		**DPD II**						
Minimum tap	% on MVA	□		**DPD II**						
Positive sequence resistance										
Maximum tap	% on MVA	□		**DPD II**						
Nominal tap	% on MVA	□		**DPD II**						
Minimum tap	% on MVA	□		**DPD II**						
Zero phase sequence reactance	% on MVA	□		**DPD II**						
Tap change range	+% / -%	□		**DPD II**						
Number of steps				**DPD II**						

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
DC NETWORK [PC.A.5.4.3.1 (c)]										
Rated DC voltage per pole	kV	□		**DPD II**						
Rated DC current per pole	A	□		**DPD II**						
Details of the **DC Network** described in diagram form including resistance, inductance and capacitance of all DC cables and/or DC lines. Details of any line reactors (including line reactor resistance), line capacitors, DC filters, earthing electrodes and other conductors that form part of the **DC Network** should be shown.	Diagram	□		**DPD II**						
DC CONVERTER STATION AND **HVDC SYSTEM** AC HARMONIC FILTER AND REACTIVE COMPENSATION EQUIPMENT **[PC.A.5.4.3.1 (d)]**										
For all switched reactive compensation equipment	Diagram			**DPD II**						
Total number of AC filter banks	Text	□								
Diagram of filter connections	Diagram		■	**DPD II**						
Type of equipment (e.g. fixed or variable)	Text		■	**DPD II**						
Capacitive rating; or	MVAr	□	■	**DPD II**						
Inductive rating; or	MVAr	□		**DPD II**						
Operating range	MVAr	□		**DPD II**						
		□		**DPD II**						
Reactive Power capability as a function of various MW transfer levels	Table	□		**DPD II**						
		□								

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6

CONTROL SYSTEMS **[PC.A.5.4.3.2]**										
Static $V_{DC} - P_{DC}$ (DC voltage – DC power) or Static $V_{DC} - I_{DC}$ (DC voltage – DC current) characteristic (as appropriate) when operating as –Rectifier –Inverter										
Details of rectifier mode control system, in block diagram form together with parameters showing transfer functions of individual elements.	Diagram Diagram	□ □		**DPD II** **DPD II**						
Details of inverter mode control system, in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of converter transformer tap changer control system in block diagram form showing transfer functions of individual elements including parameters. (Only required for **DC Converters** and **HVDC Systems** connected to the **National Electricity Transmission System**.)	Diagram	□		**DPD II**						
Details of AC filter and reactive compensation equipment control systems in block diagram form showing transfer functions of individual elements including parameters. (Only required for **DC Converters** and **HVDC Systems** connected to the **National Electricity Transmission System**.)	Diagram	□		**DPD II**						
Details of any frequency and/or load control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of any large or small signal modulating controls, such as power oscillation damping controls or sub-synchronous oscillation damping controls, that have not been submitted as part of the above control system data.	Diagram	□		**DPD II**						
Details of **HVDC Converter** unit models and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram			**DPD II**						
Details of AC component models and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□ □		**DPD II**						
Details of DC Grid models and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of Voltage and power controller and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of Special control features if applicable (e.g., power oscillation damping (POD) function, subsynchronous torsional interaction (SSTI) control and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of Multi terminal control, if applicable and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of **HVDC System** protection models as agreed between **The Company** the **HVDC System Owner** and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Transfer block diagram representation of the reactive power control at converter ends for a voltage source converter	Diagram	□		**DPD II**						
Transfer block diagram representation of the reactive power control at converter ends for a voltage source converter.		□								

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
		□								
		□								
		□								
		□								
		□								
		□								

SCHEDULE 1 – POWER GENERATING MODULE, GENERATING UNIT (OR CCGT MODULE), POWER PARK MODULE, DC CONNECTED POWER PARK MODULE, HVDC SYSTEM AND DC CONVERTER TECHNICAL DATA

PAGE 19 OF 19

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
LOADING PARAMETERS **[PC.A.5.4.3.3]**										
MW Export										
Nominal loading rate	MW/s			**DPD I**						
Maximum (emergency) loading rate	MW/s			**DPD I**						
MW Import										
Nominal loading rate	MW/s			**DPD I**						
Maximum (emergency) loading rate	MW/s			**DPD I**						
Maximum recovery time, to 90% of pre-fault loading, following an AC system fault or severe voltage depression.	s	□		**DPD II**						
Maximum recovery time, to 90% of pre-fault loading, following a transient DC Network fault.	s	□		**DPD II**						

NOTE: **Users** are referred to Schedules 5 & 14 which set down data required for all **Users** directly connected to the **National Electricity Transmission System**, including **Power Stations**. **Generators** undertaking **OTSDUW Arrangements** and are utilising an **OTSDUW DC Converter** are referred to Schedule 18.

SCHEDULE 2 - GENERATION PLANNING PARAMETERS
PAGE 1 OF 3

This schedule contains the **Genset Generation Planning Parameters** required by **The Company** to facilitate studies in **Operational Planning** timescales.

For a **Generating Unit** including those within a **Power Generating Module** (other than a **Power Park Unit**) at a **Large Power Station**, the information is to be submitted on a unit basis and for a **CCGT Module** or **Power Park Module** at a **Large Power Station** the information is to be submitted on a module basis, unless otherwise stated.

Where references to **CCGT Modules** or **Power Park Modules** at a **Large Power Station** are made, the columns "G1" etc should be amended to read "M1" etc, as appropriate.

Power Station: _____

Generation Planning Parameters

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENSET** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
OUTPUT CAPABILITY *(PC.A.3.2.2)*											
Registered Capacity on a station and unit basis (on a station and module basis in the case of a **CCGT Module** or **Power Park Module** at a **Large Power Station**)	MW	□	■	**SPD**							
Maximum Capacity on a **Power Generating Module basis** and **Synchronous Generating Unit** basis and **Registered Capacity** on a **Power Station** basis**)**	MW	□	■	**SPD**							
Minimum Generation (on a module basis in the case of a **CCGT Module** or **Power Park Module** at a **Large Power Station**)	MW	□	■	**SPD**							
Minimum Stable Operating Level (on a module basis in the case of a **Power Generating Module** at a **Large Power Station**	MW	□	■	**SPD**							
MW available from **Power Generating Modules** and **Generating Units** or **Power Park Modules** in excess of **Registered Capacity** or **Maximum Capacity**	MW	□	■	**SPD**							
REGIME UNAVAILABILITY											
These data blocks are provided to allow fixed periods of unavailability to be registered.											
Expected Running Regime. Is **Power Station** normally available for full output 24 hours per day, 7 days per week? If No please provide details of unavailability below. *(PC.A.3.2.2.)*		□	■	**SPD**							
Earliest **Synchronising** time: *OC2.4.2.1(a)*											
Monday	hr/min	■		**OC2**							-
Tuesday – Friday	hr/min	■		**OC2**							-
Saturday – Sunday	hr/min	■		**OC2**							-
Latest **De-Synchronising** time: *OC2.4.2.1(a)*											
Monday – Thursday	hr/min	■		**OC2**							-
Friday	hr/min	■		**OC2**							-
Saturday – Sunday	hr/min	■		**OC2**							-
SYNCHRONISING PARAMETERS *OC2.4.2.1(a)*											
Notice to Deviate from Zero (NDZ) after 48 hour **Shutdown**	Mins	■		**OC2**							

Station **Synchronising** Intervals (SI) after 48 hour **Shutdown**	Mins	■			-	-	-	-	-	-	
Synchronising Group (if applicable)	1 to 4	■		**OC2**							-

SCHEDULE 2 - GENERATION PLANNING PARAMETERS
PAGE 2 OF 3

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENSET** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
Synchronising Generation (SYG) after 48 hour **Shutdown** *PC.A.5.3.2(f) & OC2.4.2.1(a)*	MW	■		**DPD II & OC2**							-
De-Synchronising Intervals (Single value) *OC2.4.2.1(a)*	Mins	■		**OC2**	-	-	-	-	-	-	
RUNNING AND **SHUTDOWN** PERIOD LIMITATIONS:											
Minimum Non Zero time (MNZT) after 48 hour **Shutdown** *OC2.4.2.1(a)*	Mins	■		**OC2**							
Minimum Zero time (MZT) *OC2.4.2.1(a)*	Mins			**OC2**							
Existing AGR Plant Flexibility Limit (**Existing AGR Plant** only)	No.			**OC2**							
80% Reactor Thermal Power (expressed as Gross-Net MW) (**Existing AGR Plant** only)	MW			**OC2**							
Frequency Sensitive AGR Unit Limit (**Frequency Sensitive AGR Units** only)	No.			**OC2**							
RUN-UP PARAMETERS *PC.A.5.3.2(f) & OC2.4.2.1(a)*											
Run-up rates (RUR) after 48 hour **Shutdown**: (See note 2 page 3)	(Note that for DPD only a single value of run-up rate from Synch Gen to Registered Capacity is required)										
MW Level 1 (MWL1)	MW	■		**DPD II OC2**							-
MW Level 2 (MWL2)	MW	■		**DPD II OC2**							-
RUR from Synch. Gen to MWL1	MW/Mins	■		**DPD II OC2**							
RUR from MWL1 to MWL2	MW/Mins	■		**OC2**							
RUR from MWL2 to RC	MW/Mins	■		**OC2**							
Run-Down Rates (RDR):	(Note that for DPD only a single value of run-down rate from Registered Capacity to de-synch is required)										
MWL2	MW	■		**DPD II OC2**							
RDR from RC to MWL2	MW/Min	■		**DPD II OC2**							
MWL1	MW	■		**DPD II OC2**							
RDR from MWL2 to MWL1	MW/Min	■		**DPD II OC2**							
RDR from MWL1 to de-synch	MW/Min	■		**DPD II OC2**							

SCHEDULE 2 - GENERATION PLANNING PARAMETERS
PAGE 3 OF 3

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENSET** OR STATION DATA						
		CUSC Contract	CUSC App. Form		G1	G2	G3	G4	G5	G6	STN
REGULATION PARAMETERS *OC2.4.2.1(a)*											
Regulating Range	MW	■		**DPD II**							
Load rejection capability while still **Synchronised** and able to supply **Load**.	MW	■		**DPD II**							
GAS TURBINE LOADING PARAMETERS: *OC2.4.2.1(a)*											
Fast loading	MW/Min	■		**OC2**							
Slow loading	MW/Min	■		**OC2**							
CCGT MODULE PLANNING MATRIX				**OC2**	(please attach)						
POWER PARK MODULE PLANNING MATRIX				**OC2**	(please attach)						
Power Park Module Active Power Output/ Intermittent Power Source Curve (e.g., MW output / Wind speed)				**OC2**	(please attach)						

NOTES:

(1) To allow for different groups of **Gensets** within a **Power Station** (e.g., **Gensets** with the same operator) each **Genset** may be allocated to one of up to four **Synchronising Groups**. Within each such **Synchronising Group** the single synchronising interval will apply but between **Synchronising Groups** a zero synchronising interval will be assumed.

(2) The run-up of a **Genset** from synchronising block load to **Registered Capacity** or **Maximum Capacity** is represented as a three stage characteristic in which the run-up rate changes at two intermediate loads, MWL1 and MWL2. The values MWL1 & MWL2 can be different for each **Genset**.

SCHEDULE 3 - LARGE POWER STATION OUTAGE PROGRAMMES, OUTPUT USABLE AND INFLEXIBILITY INFORMATION

(Also outline information on contracts involving **External Interconnections**)

For a **Generating Unit** at a **Large Power Station** the information is to be submitted on a unit basis and for a **CCGT Module** or **Power Park Module** at a **Large Power Station** the information is to be submitted on a module basis, unless otherwise stated.

DATA DESCRIPTION		UNITS	TIME COVERED	UPDATE TIME	DATA CAT.	DATA to **RTL**	
Power Station name:…… **Generating Unit** (or **CCGT Module** or **Power Park Module** at a **Large Power Station**) number:… **Registered Capacity**:……							
Large Power Station OUTAGE PROGRAMME	**Large Power Station OUTPUT USABLE**						
PLANNING FOR YEARS 3 - 7 AHEAD *(OC2.4.1.2.1(a)(i), (e) & (j))*							
						CUSC Contract	CUSC App. Form
	Monthly average OU	MW	F. yrs 5 - 7	Week 24	**SPD**		
Provisional outage programme comprising:			C. yrs 3 - 5	Week 2	**OC2**		
duration		weeks	"	"	"	■	
preferred start		date	"	"	"	■	
earliest start		date	"	"	"	■	
latest finish		date	"	"	"	■	
	Weekly OU	MW	"	"	"	■	
(**The Company** response as detailed in **OC2**			C. yrs 3 - 5	Week12)		■	
(**Users**' response to **The Company** suggested changes or potential outages)			C. yrs 3 - 5	Week14)		■	
Updated provisional outage programme comprising:			C. yrs 3 - 5	Week 25	**OC2**		
duration		weeks	"	"	"	■	
preferred start		date	"	"	"	■	
earliest start		date	"	"	"	■	
latest finish		date	"	"	"	■	
	Updated weekly OU	MW	"	"	"	■	
(**The Company** response as detailed in **OC2** for			C. yrs 3 - 5	Week28)			
(**Users**' response to **The Company** suggested changes or update of potential outages)			C. yrs 3 - 5	Week31)		■	
(**The Company** further suggested revisions etc.				)		■	
(as detailed in **OC2** for			C. yrs 3 - 5	Week42)			
Agreement of final **Generation Outage Programme**			C. yrs 3 - 5	Week 45	**OC2**	■	

SCHEDULE 3 - LARGE POWER STATION OUTAGE PROGRAMMES, OUTPUT USABLE AND INFLEXIBILITY INFORMATION

PAGE 2 OF 3

DATA DESCRIPTION		UNITS	TIME COVERED	UPDATE TIME	DATA CAT	DATA to **RTL**
	PLANNING FOR YEAR 0					
Updated Final **Generation Outage Programme**			C. yr 0 Week 2 ahead to year end	1600 Weds.	**OC2**	
	OU at weekly peak	MW	"	"	"	
(**The Company** response as detailed in **OC2** for			C. yrs 0	1600)		
(			Weeks 2 to 52 ahead	Friday)		
(				)		
(**The Company** response as detailed in **OC2** for			Weeks 2 - 7 ahead	1600)		
(				Thurs)		
Forecast return to services (Planned Outage or breakdown)		date	days 2 to 14 ahead	0900 daily	**OC2**	
	OU (all hours)	MW	"	"	**OC2**	
(**The Company** response as detailed in **OC2** for			days 2 to 14 ahead	1600)		
(				daily)		
	INFLEXIBILITY					
	Genset inflexibility	Min MW (Weekly)	Weeks 2 - 8 ahead	1600 Tues	**OC2**	
(**The Company** response on **Negative Reserve Active** (**Power Margin**			"	1200) Friday)		
	Genset inflexibility	Min MW (daily)	days 2 -14 ahead	0900 daily	**OC2**	
(**The Company** response on **Negative Reserve Active** (**Power Margin**			"	1600) daily)		

SCHEDULE 3 - LARGE POWER STATION OUTAGE PROGRAMMES, OUTPUT USABLE AND INFLEXIBILITY INFORMATION
PAGE 3 OF 3

DATA DESCRIPTION	UNITS	TIME COVERED	UPDATE TIME	DATA CAT	DATA to **RTL**	
OUTPUT PROFILES						
					CUSC Contract	CUSC App. Form
In the case of **Large Power Stations** whose output may be expected to vary in a random manner (e.g., wind power) or to some other pattern (e.g., Tidal) sufficient information is required to enable an understanding of the possible profile	MW	F. yrs 1 - 7	Week 24	**SPD**		

Notes: 1. The week numbers quoted in the Update Time column refer to standard weeks in the current year.

GOVERNOR DROOP AND RESPONSE *(PC.A.5.5 ■ CUSC Contract)*

The Data in this Schedule 4 is to be supplied by **Generators** with respect to all **Large Power Stations**, **HVDC System Owners** and by **DC Converter Station** owners (where agreed), whether directly connected or **Embedded**

DATA DESCRIPTION	NORMAL VALUE	MW	DATA CAT	DROOP%			RESPONSE CAPABILITY		
				Unit 1	Unit 2	Unit 3	**Primary**	**Secondary**	**High Frequency**
MLP1	**Designed Minimum Operating Level** or **Minimum Regulating Level** (for a **CCGT Module** or **Power Park Module**, on a modular basis assuming all units are **Synchronised**)								
MLP2	**Minimum Generation** or **Minimum Stable Operating Level** (for a **CCGT Module** or **Power Park Module**, or **Power Generating Module** on a modular basis assuming all units are **Synchronised**)								
MLP3	70% of **Registered Capacity or Maximum Capacity**								
MLP4	80% of **Registered Capacity or Maximum Capacity**								
MLP5	95% of **Registered Capacity or Maximum Capacity**								
MLP6	**Registered Capacity or Maximum Capacity**								

Notes:

1. The data provided in this Schedule 4 is not intended to constrain any **Ancillary Services Agreement.**
2. **Registered Capacity or Maximum Capacity** should be identical to that provided in Schedule 2.
3. The Governor **Droop** should be provided for each **Generating Unit(**excluding **Power Park Units), Power Park Module**, **HVDC Converter** or **DC Converter**. The Response Capability should be provided for each **Genset** or **DC Converter**.
4. **Primary, Secondary** and **High Frequency Response** are defined in CC.A.3.2 or ECC.A.3.2 and are based on a frequency ramp of 0.5Hz over 10 seconds. **Primary Response** is the minimum value of response between 10s and 30s after the frequency ramp starts, **Secondary Response** between 30s and 30 minutes, and **High Frequency Response** is the minimum value after 10s on an indefinite basis.
5. For plants which have not yet **Synchronised**, the data values of MLP1 to MLP6 should be as described above. For plants which have already **Synchronised**, the values of MLP1 to MLP6 can take any value between **Designed Operating Minimum Level** or **Minimum Regulating Level a**nd **Registered Capacity** or **Maximum Capacity**. If MLP1 is not provided at the **Designed Minimum Operating Level**, the value of the **Designed Minimum Operating Level** should be separately stated.
6. For the avoidance of doubt **Transmission DC Converters** and **OTSDUW DC Converters** must be capable of providing a continuous signal indicating the real time frequency measured at the **Transmission Interface Point** to the **Offshore Grid Entry Point** (as detailed in CC.6.3.7(e)(vii) and CC.6.3.7(e)(viii) or ECC.6.3..3.1.1(f) to enable **Offshore Power Generating Modules Offshore Generating Units**, **Offshore Power Park Modules** and/or **Offshore DC Converters** to satisfy the frequency response requirements of CC.6.3.7 or ECC.6.3.7.

SCHEDULE 5 - USERS SYSTEM DATA
PAGE 1 OF 11

The data in this Schedule 5 is required from **Users** who are connected to the **National Electricity Transmission System** via a **Connection Point** (or who are seeking such a connection). **Generators** undertaking **OTSDUW** should use **DRC** Schedule 18 although they should still supply data under Schedule 5 in relation to their **User's System** up to the **Offshore Grid Entry Point**.

Table 5 (a)

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CATEGORY
		CUSC Contract	CUSC App. Form	
USERS SYSTEM LAYOUT *(PC.A.2.2)*				
A **Single Line Diagram** showing all or part of the **User's System** is required. This diagram shall include:-				**SPD**
(a) all parts of the **User's System**, whether existing or proposed, operating at **Supergrid Voltage**, and in Scotland and **Offshore**, also all parts of the **User System** operating at 110kV and greater,		■	■	
(b) all parts of the **User's System** operating at a voltage of 50kV and greater, and in Scotland and **Offshore** greater than 30kV, or higher which can interconnect **Connection Points**, or split bus-bars at a single **Connection Point**,		■	■	
(c) all parts of the **User's System** between **Embedded Medium Power Stations** or **Large Power Stations** or **Offshore Transmission Systems** connected to the **User's Subtransmission System** and the relevant **Connection Point** or **Interface Point**,		■	■	
(d) all parts of the **User's System** at a **Transmission Site**.		■	■	
The **Single Line Diagram** may also include additional details of the **User's Subtransmission System**, and the transformers connecting the **User's Subtransmission System** to a lower voltage. With **The Company**'s agreement, it may also include details of the **User's System** at a voltage below the voltage of the **Subtransmission System**.		■	■	
This **Single Line Diagram** shall depict the arrangement(s) of all of the existing and proposed load current carrying **Apparatus** relating to both existing and proposed **Connection Points**, showing electrical circuitry (i.e., overhead lines, underground cables, power transformers and similar equipment), operating voltages. In addition, for equipment operating at a **Supergrid Voltage**, and in Scotland and **Offshore** also at 110kV and greater, circuit breakers and phasing arrangements shall be shown.		■	■	

Table 5(b)

DATA DESCRIPTION	UNITS	DATA EXCH		DATA CATEGORY
		CUSC Contract	CUSC App. Form	
REACTIVE COMPENSATION *(PC.A.2.4)*				
For independently switched reactive compensation equipment not owned by a **Relevant Transmission Licensee** connected to the **User's System** at 132kV and above, and also in Scotland and **Offshore**, connected at 33kV and above, other than power factor correction equipment associated with a customer's **Plant** or **Apparatus**:				
Type of equipment (e.g., fixed or variable)	Text	■	■	**SPD**
Capacitive rating; or	MVAr	■	■	**SPD**
Inductive rating; or	MVAr	■	■	**SPD**
Operating range	MVAr	■	■	**SPD**
Details of automatic control logic to enable operating characteristics to be determined	text and/or diagrams	■	■	**SPD**
Point of connection to **User's System** (electrical location and system voltage)	Text	■	■	**SPD**
SUBSTATION INFRASTRUCTURE *(PC.A.2.2.6(b))*				
For the infrastructure associated with any **User's** equipment at a Substation owned by a **Relevant Transmission Licensee** or operated or managed by **The Company**:-				
Rated 3-phase rms short-circuit withstand current	kA	■	■	**SPD**
Rated 1-phase rms short-circuit withstand current	kA	■	■	**SPD**
Rated Duration of short-circuit withstand	s	■	■	**SPD**
Rated rms continuous current	A	■	■	**SPD**

Table 5 (c)

DATA DESCRIPTION		UNITS	DATA EXCH		DATA CATEGORY
LUMPED SUSCEPTANCES *(PC.A.2.3)*			CUSC Contract	CUSC App. Form	
Equivalent Lumped Susceptance required for all parts of the **User's Subtransmission System** which are not included in the **Single Line Diagram**.			■	■	
This should not include:			■	■	
(a)	independently switched reactive compensation equipment identified above.		■	■	
(b)	any susceptance of the **User's System** inherent in the **Demand** (**Reactive Power**) data provided in Schedule 1 (**Generator** Data) or Schedule 11 (**Connection Point** data).		■	■	
Equivalent lumped shunt susceptance at nominal **Frequency**.		% on 100 MVA	■	■	**SPD**

USER'S SYSTEM DATA

Circuit Parameters *(PC.A.2.2.4)* (■ *CUSC Contract &* ■ CUSC Application Form)

The data below is all **Standard Planning Data**. Details are to be given for all circuits shown on the **Single Line Diagram**
Table 5 (d)

Years Valid	Node 1	Node 2	Rated Voltage kV	Operating Voltage kV	Positive Phase Sequence % on 100 MVA			Zero Phase Sequence (self) % on 100 MVA			Zero Phase Sequence (mutual) % on 100 MVA		
					R	X	B	R	X	B	R	X	B

Notes

1. Data should be supplied for the current, and each of the seven succeeding Financial Years. This should be done by showing for which years the data is valid in the first column of the Table.

USERS SYSTEM DATA

Transformer Data *(PC.A.2.2.5)* (■ *CUSC Contract &* ■ CUSC Application Form)

The data below is all **Standard Planning Data**, and details should be shown below of all transformers shown on the **Single Line Diagram**. Details of Winding Arrangement, Tap Changer and earthing details are only required for transformers connecting the **User's** higher voltage system with its **Primary Voltage System**.

Table 5 (e)

Years valid	Name of Node or Conn-ection	Trans-former	Rating MVA	Voltage Ratio		Positive Phase Sequence Reactance % on Rating			Positive Phase Sequence Resistance % on Rating			Zero Sequence React-ance % on Rating	Winding Arr.	Tap Changer			Earthing Details (delete as app.) *
				HV	LV	Max. Tap	Min. Tap	Nom. Tap	Max. Tap	Min. Tap	Nom. Tap			range +% to -%	step size %	type (delete	
																ON/ OFF ON/ OFF ON/ OFF ON/ OFF ON/ OFF ON/ OFF ON/OFF	Direct/ Res/ Rea Direct/ Res/ Rea Direct /Res/ Rea Direct/ Res/ Rea Direct/ Res/ Rea Direct/ Res/ Rea

*If Resistance or Reactance please give impedance value

Notes

1. Data should be supplied for the current, and each of the seven succeeding Financial Years. This should be done by showing for which years the data is valid in the first column of the Table
2. For a transformer with two secondary windings, the positive and zero phase sequence leakage impedances between the HV and LV1, HV and LV2, and LV1 and LV2 windings are required.

USER'S SYSTEM DATA

Switchgear Data *(PC.A.2.2.6(a))* (■ *CUSC Contract & CUSC Application Form* ■)

The data below is all **Standard Planning Data**, and should be provided for all switchgear (i.e., circuit breakers, load disconnectors and disconnectors) operating at a **Supergrid Voltage**, and also in Scotland and **Offshore**, operating at 132kV. In addition, data should be provided for all circuit breakers irrespective of voltage located at a **Connection Site** which is owned by a **Relevant Transmission Licensee** or operated or managed by **The Company**.

Table 5(f)

Years Valid	**Connect-ion Point**	Switch No.	Rated Voltage kV rms	Operating Voltage kV rms	Rated short-circuit breaking current		Rated short-circuit peak making current		Rated rms continuous current (A)	DC time constant at testing of asymmetrical breaking ability(s)
					3 Phase kA rms	1 Phase kA rms	3 Phase kA peak	1 Phase kA peak		

Notes

1. Rated Voltage should be as defined by IEC 694.

2. Data should be supplied for the current, and each of the seven succeeding Financial Years. This should be done by showing for which years the data is valid in the first column of the Table

Table 5(g)

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CATEGORY
		CUSC Contract	CUSC App. Form	
PROTECTION SYSTEMS *(PC.A.6.3)* The following information relates only to **Protection** equipment which can trip or inter-trip or close any **Connection Point** circuit breaker or any **Transmission** circuit breaker. The information need only be supplied once, in accordance with the timing requirements set out in PC.A.1.4 (b) and need not be supplied on a routine annual basis thereafter, although **The Company** should be notified if any of the information changes.				
(a) A full description, including estimated settings, for all relays and Protection systems installed or to be installed on the **User's System**;		■		**DPD II**
(b) A full description of any auto-reclose facilities installed or to be installed on the **User's System**, including type and time delays;		■		**DPD II**
(c) A full description, including estimated settings, for all relays and **Protection** systems installed or to be installed on the **Power Generating Module**, **Power Park Module** or **Generating Unit's** generator transformer, unit transformer, station transformer and their associated connections;		■		**DPD II**
(d) For **Generating Units** (other than **Power Park Units**) having a circuit breaker at the generator terminal voltage clearance times for electrical faults within the **Generating Unit** zone must be declared.		■		**DPD II**
(e) Fault Clearance Times: Most probable fault clearance time for electrical faults on any part of the **Users System** directly connected to the **National Electricity Transmission System**.	mSec	■		**DPD II**

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CATEGORY
		CUSC Contract	CUSC App. Form	
POWER PARK MODULE/UNIT PROTECTION SYSTEMS Details of settings for the **Power Park Module/Unit** protection relays (to include): *(PC.A.5.4.2(f))*				
(a) Under frequency,		■		**DPD II**
(b) Over Frequency,		■		**DPD II**
(c) Under Voltage, Over Voltage,		■		**DPD II**
(d) Rotor Over current,		■		**DPD II**
(e) Stator Over current,		■		**DPD II**
(f) High Wind Speed Shut Down Level,		■		**DPD II**
(g) Rotor Underspeed,		■		**DPD II**
(h) Rotor Overspeed.		■		**DPD II**

Information for Transient Overvoltage Assessment (**DPD I**) *(PC.A.6.2 ■ CUSC Contract)*

The information listed below may be requested by **The Company** from each **User** with respect to any **Connection Site** between that **User** and the **National Electricity Transmission System**. The impact of any third party **Embedded** within the **Users System** should be reflected.

(a) Busbar layout plan(s), including dimensions and geometry showing positioning of any current and voltage transformers, through bushings, support insulators, disconnectors, circuit breakers, surge arresters, etc. Electrical parameters of any associated current and voltage transformers, stray capacitances of wall bushings and support insulators, and grading capacitances of circuit breakers;

(b) Electrical parameters and physical construction details of lines and cables connected at that busbar. Electrical parameters of all plant e.g., transformers (including neutral earthing impedance or zig-zag transformers if any), series reactors and shunt compensation equipment connected at that busbar (or to the tertiary of a transformer) or by lines or cables to that busbar;

(c) Basic insulation levels (BIL) of all **Apparatus** connected directly, by lines or by cables to the busbar;

(d) Characteristics of overvoltage **Protection** devices at the busbar and at the termination points of all lines, and all cables connected to the busbar;

(e) Fault levels at the lower voltage terminals of each transformer connected directly or indirectly to the **National Electricity Transmission System** without intermediate transformation;

(f) The following data is required on all transformers operating at **Supergrid Voltage** throughout **Great Britain** and, in Scotland and **Offshore**, also at greater than 110kV: three or five limb cores or single phase units to be specified, and operating peak flux density at nominal voltage.

(g) An indication of which items of equipment may be out of service simultaneously during **Planned Outage** conditions.

Harmonic Studies (**DPD I**) (PC.A.6.4 ■ CUSC Contract)

The information given below, both current and forecast, where not already supplied in this Schedule 5 may be requested by **The Company** from each **User** if it is necessary for **The Company** to evaluate the production/magnification of harmonic distortion on the **National Electricity Transmission System** and **User's** systems. The impact of any third party **Embedded** within the **User's System** should be reflected:

(a) Overhead lines and underground cable circuits of the **User's Subtransmission System** must be differentiated and the following data provided separately for each type:

Positive phase sequence resistance

Positive phase sequence reactance

Positive phase sequence susceptance

(b) for all transformers connecting the **User's Subtransmission System** to a lower voltage:

Rated MVA

Voltage Ratio

Positive phase sequence resistance

Positive phase sequence reactance

(c) at the lower voltage points of those connecting transformers:

Equivalent positive phase sequence susceptance

Connection voltage and MVAr rating of any capacitor bank and component design parameters if configured as a filter

Equivalent positive phase sequence interconnection impedance with other lower voltage points

The minimum and maximum **Demand** (both MW and MVAr) that could occur

Harmonic current injection sources in Amps at the Connection voltage points

Details of traction loads, e.g., connection phase pairs, continuous variation with time, etc.

(d) an indication of which items of equipment may be out of service simultaneously during **Planned Outage** conditions

Voltage Assessment Studies (**DPD I**) *(PC.A.6.5 ■ CUSC Contract)*

The information listed below, where not already supplied in this Schedule 5, may be requested by **The Company** from each **User** with respect to any **Connection Site** if it is necessary for **The Company** to undertake detailed voltage assessment studies (e.g., to examine potential voltage instability, voltage control co-ordination or to calculate voltage step changes). The impact of any third party **Embedded** within the **Users System** should be reflected:

(a) For all circuits of the **User's Subtransmission System**:

Positive Phase Sequence Reactance

Positive Phase Sequence Resistance

Positive Phase Sequence Susceptance

MVAr rating of any reactive compensation equipment

(b) for all transformers connecting the **User's Subtransmission System** to a lower voltage:

Rated MVA

Voltage Ratio

Positive phase sequence resistance

Positive Phase sequence reactance

Tap-changer range

Number of tap steps

Tap-changer type: on-load or off-circuit

AVC/tap-changer time delay to first tap movement

AVC/tap-changer inter-tap time delay

(c) at the lower voltage points of those connecting transformers:-

Equivalent positive phase sequence susceptance

MVAr rating of any reactive compensation equipment

Equivalent positive phase sequence interconnection impedance with other lower voltage points

The maximum **Demand** (both MW and MVAr) that could occur

Estimate of voltage insensitive (constant power) load content in % of total load at both winter peak and 75% off-peak load conditions

Short Circuit Analyses:(**DPD I**) *(PC.A.6.6 ■ CUSC Contract)*

The information listed below, both current and forecast, and where not already supplied under this Schedule 5, may be requested by **The Company** from each **User** with respect to any **Connection Site** where prospective short-circuit currents on equipment owned by a **Relevant Transmission Licensee** or operated or managed by **The Company** are close to the equipment rating. The impact of any third party **Embedded** within the **User's System** should be reflected:-

(a) For all circuits of the **User's Subtransmission System**:

Positive phase sequence resistance

Positive phase sequence reactance

Positive phase sequence susceptance

Zero phase sequence resistance (both self and mutuals)

Zero phase sequence reactance (both self and mutuals)

Zero phase sequence susceptance (both self and mutuals)

(b) for all transformers connecting the **User's Subtransmission System** to a lower voltage:

Rated MVA

Voltage Ratio

Positive phase sequence resistance (at max, min and nominal tap)

Positive phase sequence reactance (at max, min and nominal tap)

Zero phase sequence reactance (at nominal tap)

Tap changer range

Earthing method: direct, resistance or reactance

Impedance if not directly earthed

(c) at the lower voltage points of those connecting transformers:-

The maximum **Demand** (in MW and MVAr) that could occur

Short-circuit infeed data in accordance with PC.A.2.5.6(a) unless the **User's** lower voltage network runs in parallel with the **Subtransmission System**, when to prevent double counting in each node infeed data, a π equivalent comprising the data items of PC.A.2.5.6(a) for each node together with the positive phase sequence interconnection impedance between the nodes shall be submitted.

Dynamic Models: (**DPD II**) *(PC.A.6.7 ■ CUSC Contract)*

The information listed below, both current and forecast, and where not already supplied under this Schedule 5, may be requested by **The Company** from each **EU Code User** or in respect of each **EU Grid Supply Point** with respect to any **Connection Site**

(a) Dynamic model structure and block diagrams including parameters, transfer functions and individual elements (as applicable)

(b) Power control functions and block diagrams including parameters, transfer functions and individual elements (as applicable)

(c) Voltage control functions and block diagrams including parameters, transfer functions and individual elements (as applicable)

(d) Converter control models and block diagrams including parameters, transfer functions and individual elements (as applicable)

SCHEDULE 6 – USERS OUTAGE INFORMATION

PAGE 1 OF 2

DATA DESCRIPTION	UNITS	DATA to **RTL**		TIMESCALE COVERED	UPDATE TIME	DATA CAT.
		CUSC Contract	CUSC App. Form			
Details are required from **Network Operators** of proposed outages in their **User Systems** and from **Generators** with respect to their outages, which may affect the performance of the **Total System** (e.g., at a **Connection Point** or constraining **Embedded Large Power Stations** or constraints to the **Maximum Import Capacity** or **Maximum Export Capacity** at an **Interface Point**) *(OC2.4.1.3.2(a) & (b))*		■		Years 2-5	Week 8 (**Network Operator** etc) Week 13 (Generators)	**OC2** **OC2**
(**The Company** advises **Network Operators** of **National Electricity Transmission System** outages affecting their **Systems**)				Years 2-5	Week 28)	
Network Operator informs **The Company** if unhappy with proposed outages)		■		"	Week 30	**OC2**
(**The Company** draws up revised **National Electricity Transmission System** (outage plan advises **Users** of operational effects)				"	Week 34)	
Generators and **Non-Embedded Customers** provide Details of **Apparatus** owned by them (other than **Gensets**) at each **Grid Supply Point** *(OC2.4.1.3.3)*		■		Year 1	Week 13	**OC2**
(**The Company** advises **Network Operators** of outages affecting their **Systems**) (OC2.4.1.3.3)				Year 1	Week 28)	
Network Operator details of relevant outages affecting the **Total System** *(OC2.4.1.3.3)*		■		Year 1	Week 32	**OC2**
Details of:- **Maximum Import Capacity** for each **Interface Point** **Maximum Export Capacity** for each **Interface Point** Changes to previously declared values of the **Interface Point Target Voltage/Power Factor** *(OC2.4.1.3.3(c)).*	 MVA / MW MVA / MW V (unless power factor control			Year 1	Week 32	**OC2**
(**The Company** informs **Users** of aspects that may affect their **Systems**) (OC2.4.1.3.3)				Year 1	Week 34)	
Users inform **The Company** if unhappy with aspects as notified *(OC2.4.1.3.3)*		■		Year 1	Week 36	**OC2**
(**The Company** issues final **National Electricity Transmission System** (outage plan with advice of operational) *(OC2.4.1.3.3)* (effects on **Users System**)		■		Year 1	Week 49	**OC2**
Generator, **Network Operator** and **Non-Embedded Customers** to inform **The Company** of changes to outages previously requested				Week 8 ahead to year end	As occurring	**OC2**
Details of load transfer capability of 12MW or more between **Grid Supply Points** in England and Wales and 10MW or more between **Grid Supply Points** in Scotland.				Within Yr 0	As **The Company** request	**OC2**
Details of:- **Maximum Import Capacity** for each **Interface Point** **Maximum Export Capacity** for each **Interface Point** Changes to previously declared values of the **Interface Point Target Voltage/Power Factor**	MVA / MW MVA / MW V (unless power factor control			Within Yr 0	As occurring	**OC2**

Note: **Users** should refer to **OC2** for full details of the procedure summarised above and for the information which **The Company** will provide on the **Programming Phase**.

SCHEDULE 6 – USERS OUTAGE INFORMATION
PAGE 2 OF 2

The data below is to be provided to **The Company** as required for compliance with the European Commission Regulation No 543/2013 (OC2.4.2.3). Data provided under Article Numbers 7.1(a), 7.1(b), 15.1(a), 15.1(b), and 15.1(c) and 15.1(d) is to be provided using **MODIS.**

ECR ARTICLE No.	DATA DESCRIPTION	USERS PROVIDING DATA	FREQUENCY OF SUBMISSION
7.1(a)	Planned unavailability of the **Apparatus** belonging to a **Non-Embedded Customer** where OC2.4.7 (a) applies - Energy Identification Code (EIC)* - Unavailable demand capacity during the event (MW) - Estimated start date and time (dd.mm.yy hh:mm) - Estimated end date and time (dd.mm.yy hh:mm) - Reason for unavailability from the list below: . Maintenance . Failure . Shutdown . Other	**Non-Embedded Customer**	To be received by **The Company** as soon as reasonably possible but in any case, to facilitate publication of data no later than 1 hour after **a decision has been made by the Non-Embedded Customer** regarding the planned unavailability
7.1(b)	Changes in actual availability of the **Apparatus** belonging to a **Non-Embedded Customer** where OC2.4.7 (b) applies - Energy Identification Code (EIC)* - Unavailable demand capacity during the event (MW) - Start date and time (dd.mm.yy hh:mm) - Estimated end date and time (dd.mm.yy hh:mm) - Reason for unavailability from the list below : . Maintenance . Failure . Shutdown . Other	**Non-Embedded Customer**	To be received by **The Company** as soon as reasonably possible but in any case, to facilitate publication of data no later than 1 hour after the change in actual availability
8.1	Year Ahead Forecast Margin information as provided in accordance with OC2.4.1.2.2 - **Output Usable**	**Generator**	In accordance with OC2.4.1.2.2
14.1(a)	**Registered Capacity** or **Maximum Capacity** for **Generating Units** or **Power Generating Modules** with greater than 1 MW **Registered Capacity** or **Maximum Capacity** provided in accordance with PC.4.3.1 and PC.A.3.4.3 or PC.A.3.1.4 - **Registered Capacity** or **Maximum Capacity** (MW) - Production type (from that listed under PC.A.3.4.3)	**Generator**	Week 24
14.1(b)	**Power Station Registered Capacity** for units with equal or greater than 100 MW **Registered Capacity** provided in accordance with PC.4.3.1 and PC.A.3.4.3 - **Power Station** name - Location of **Generating Unit** - Production type (from that listed under PC.A.3.4.3) - Voltage connection levels - **Registered Capacity** or **Maximum Capacity** (MW)	**Generator**	Week 24
14.1(c)	Estimated output of **Active Power** of a **BM Unit** or **Generating Unit** for each per **Settlement Period** of the next **Operational Day** provided in accordance with BC1.4.2 - **Physical Notification**	**Generator**	In accordance with BC1.4.2

15.1(a)	Planned unavailability of a **Generating Unit** where OC2.4.7(c) applies - **Power Station** name - **Generating Unit** and/or **Power Generating Module** name - Location of **Generating Unit and/or Power Generating Module** - **Generating Unit Registered Capacity** (MW) - Production type (from that listed under PC.A.3.4.3) - **Output Usable** (MW) during the event - Start date and time (dd.mm.yy hh:mm) - Estimated end date and time (dd.mm.yy hh:mm) - Reason for unavailability from the list below: . Maintenance . Shutdown . Other	**Generator**	To be received by **The Company** as soon as reasonably possible but in any case, to facilitate publication of data no later than 1 hour after a decision has been made by the **Generator** regarding the planned unavailability
15.1(b)	Changes in availability of a **Generating Unit** and/or **Power Generating Module** where OC2.4.7 (d) applies - **Power Station** name - **Generating Unit** and/or **Power Generating Module** name - Location of **Generating Unit and/or Power Generating Module** - **Generating Unit Registered Capacity** and **Power Generating Module Maximum Capacity** (MW) - Production type (from that listed under PC.A.3.4.3) - Maximum Export Limit (MW) during the event - Start date and time (dd.mm.yy hh:mm) - Estimated end date and time (dd.mm.yy hh:mm) - Reason for unavailability from the list below: . Maintenance . Shutdown . Other	**Generator**	To be received by **The Company** as soon as reasonably possible but in any case, to facilitate publication of data no later than 1 hour after the change in actual availability
15.1(c)	Planned unavailability of a **Power Station** where OC2.4.7(e) applies - **Power Station** name - Location of **Power Station** - **Power Station Registered Capacity** (MW) - Production type (from that listed under PC.A.3.4.3) - **Power Station** aggregated **Output Usable** (MW) during the event - Start date and time (dd.mm.yy hh:mm) - Estimated end date and time (dd.mm.yy hh:mm) - Reason for unavailability from the list below: . Maintenance . Shutdown . Other	**Generator**	To be received by **The Company** as soon as reasonably possible but in any case, to facilitate publication of data no later than 1 hour after a decision has been made by the **Generator** regarding the planned unavailability
15.1(d)	Changes in actual availability of a **Power Station** where OC2.4.7 (f) applies - **Power Station** name - Location of **Power Station** - **Power Station Registered Capacity** (MW) - Production type (from that listed under PC.A.3.4.3) - **Power Station** aggregated Maximum Export Limit (MW) during the event - Start date and time (dd.mm.yy hh:mm) - Estimated end date and time (dd.mm.yy hh:mm) - Reason for unavailability from the list below: . Maintenance . Shutdown . Other	**Generator**	To be received by **The Company** as soon as reasonably possible but in any case, to facilitate publication of data no later than 1 hour after the change in actual availability

* Energy Identification Coding (EIC) is a coding scheme that is approved by ENTSO-E for standardised electronic data interchanges and is utilised for reporting to the Central European Transparency Platform. The Company will act as the Local Issuing Office for EIC in respect of GB.

SCHEDULE 7 - LOAD CHARACTERISTICS AT GRID SUPPLY POINTS

All data in this schedule 7 is categorised as **Standard Planning Data** (**SPD**) and is required for existing and agreed future connections. This data is only required to be updated when requested by **The Company**.

				DATA FOR FUTURE YEARS						
DATA DESCRIPTION	UNITS	DATA to **RTL**		Yr 1	Yr 2	Yr 3	Yr 4	Yr 5	Yr 6	Yr 7
		CUSC Contract	CUSC App. Form							
FOR ALL TYPES OF **DEMAND** FOR EACH **GRID SUPPLY POINT**										
The following information is required infrequently and should only be supplied, wherever possible, when requested by **The Company** *(PC.A.4.7)*		□								
Details of individual loads which have Characteristics significantly different from the typical range of domestic or commercial and industrial load supplied: *(PC.A.4.7(a))*		□		(Please Attach)						
Sensitivity of demand to fluctuations in voltage And frequency on **National Electricity Transmission System** at time of peak **Connection Point Demand (Active Power)** *(PC.A.4.7(b))*		□								
Voltage Sensitivity *(PC.A.4.7(b))*	MW/kV MVAr/kV	□								
Frequency Sensitivity *(PC.A.4.7(b))*	MW/Hz MVAr/Hz	□								
Reactive Power sensitivity should relate to the **Power Factor** information given in Schedule 11 (or for **Generators**, Schedule 1) and note 6 on Schedule 11 relating to **Reactive Power** therefore applies: *(PC.A.4.7(b))*		□								
Phase unbalance imposed on the **National Electricity Transmission System** *(PC.A.4.7(d))*										
- maximum	%	□								
- average	%	□								
Maximum Harmonic Content imposed on **National Electricity Transmission System** *(PC.A.4.7(e))*	%	□								
Details of any loads which may cause **Demand** Fluctuations greater than those permitted under Engineering Recommendation P28, Stage 1 at the **Point of Common Coupling** including **Flicker Severity** (**Short Term**) and **Flicker Severity** (**Long Term**) *(PC.A.4.7(f))*		□								

SCHEDULE 8 - DATA SUPPLIED BY BM PARTICIPANTS

CODE	DESCRIPTION
BC1	**Physical Notifications**
BC1 & **BC2**	**Export and Import Limits**
BC1	**Bid-Offer Data**
BC1	**Dynamic Parameters** (Day Ahead)
BC2	**Dynamic Parameters** (For use in **Balancing Mechanism**)
BC1 & **BC2**	**Other Relevant Data**

- No information collated under this Schedule will be transferred to the **Relevant Transmission Licensees**

SCHEDULE 9 - DATA SUPPLIED BY THE COMPANY TO USERS

(Example of data to be supplied)

CODE	DESCRIPTION
CC or **ECC**	Operation Diagram
CC or **ECC**	Site Responsibility Schedules
PC	Day of the peak **National Electricity Transmission System Demand**
	Day of the minimum **National Electricity Transmission System Demand**
OC2	**Surpluses** and **Output Useable** (**OU**) requirements for each **Generator** over varying timescales
	Equivalent networks to **Users** for **Outage Planning**
	Negative Reserve Active Power Margins (when necessary)
	Operating Reserve information
BC1	**Demand** Estimates, **Indicated Margin** and **Indicated Imbalance**, indicative **Synchronising** and **Desynchronising** times of **Embedded Power Stations** to **Network Operators**, special actions.
BC2	**Bid-Offer Acceptances**, **Ancillary Services** instructions to relevant **Users**, **Emergency Instructions**
BC3	Location, amount, and **Low Frequency Relay** settings of any **Low Frequency Relay** initiated **Demand** reduction for **Demand** which is **Embedded**.

- No information collated under this Schedule will be transferred to the **Relevant Transmission Licensees**

DATA TO BE SUPPLIED BY **THE COMPANY** TO **USERS**

PURSUANT TO THE **TRANSMISSION LICENCE**

1. The **Transmission Licence** requires **The Company** to publish annually the **Seven Year Statement** which is designed to provide **Users** and potential **Users** with information to enable them to identify opportunities for continued and further use of the **National Electricity Transmission System**.

   When a **User** is considering a development at a specific site, certain additional information may be required in relation to that site which is of such a level of detail that it is inappropriate to include it in the **Seven Year Statement**. In these circumstances, the **User** may contact **The Company** who will be pleased to arrange a discussion and the provision of such additional information relevant to the site under consideration as the **User** may reasonably require.

2. The **Transmission Licence** also requires **The Company** to offer terms for an agreement for connection to and use of the **National Electricity Transmission System** and further information will be given by **The Company** to the potential **User** in the course of the discussions of the terms of such an agreement.

SCHEDULE 10 - DEMAND PROFILES AND ACTIVE ENERGY DATA
PAGE 1 OF 2

The following information is required from each **Network Operator** and from each **Non-Embedded Customer**. The data should be provided in calendar week 24 each year (although **Network Operators** may delay the submission until calendar week 28).

DATA DESCRIPTION	F. Yr. 0	F. Yr. 1	F. Yr. 2	F. Yr. 3	F. Yr. 4	F. Yr. 5	F. Yr. 6	F. Yr. 7	UPDATE TIME	DATA CAT
Demand Profiles	*(PC.A.4.2) (■ – CUSC Contract & ■ CUSC Application Form)*									
Total User's system profile (please delete as applicable)	Day of **User's** annual Maximum demand at **Annual ACS Conditions** (MW) Day of annual peak of **National Electricity Transmission System Demand** at **Annual ACS Conditions** (MW) Day of annual minimum **National Electricity Transmission System Demand** at average conditions (MW)									
0000 : 0030									Wk.24	**SPD**
0030 : 0100									:	
0100 : 0130									:	
0130 : 0200									:	:
0200 : 0230									:	:
0230 : 0300									:	:
0300 : 0330									:	:
0330 : 0400									:	:
0400 : 0430									:	:
0430 : 0500									:	:
0500 : 0530									:	:
0530 : 0600									:	:
0600 : 0630									:	:
0630 : 0700									:	:
0700 : 0730									:	:
0730 : 0800									:	:
0800 : 0830									:	:
0830 : 0900									:	:
0900 : 0930									:	:
0930 : 1000									:	:
1000 : 1030									:	:
1030 : 1100									:	:
1100 : 1130									:	:
1130 : 1200									:	:
1200 : 1230									:	:
1230 : 1300									:	:
1300 : 1330									:	:
1330 : 1400									:	:
1400 : 1430									:	:
1430 : 1500									:	:
1500 : 1530									:	:
1530 : 1600									:	:
1600 : 1630									:	:
1630 : 1700									:	:
1700 : 1730									:	:
1730 : 1800									:	:
1800 : 1830									:	:
1830 : 1900									:	:
1900 : 1930									:	:
1930 : 2000									:	:
2000 : 2030									:	:
2030 : 2100									:	:
2100 : 2130									:	:
2130 : 2200									:	:
2200 : 2230									:	:
2230 : 2300									:	:
2300 : 2330									:	:
2330 : 0000									:	:

SCHEDULE 10 - DEMAND PROFILES AND ACTIVE ENERGY DATA
PAGE 2 OF 2

DATA DESCRIPTION	Out-turn		F.Yr.	Update	Data Cat	DATA to **RTL**	
	Actual	Weather Corrected.	0	Time			
(PC.A.4.3)						CUSC Contract	CUSC App. Form
Active Energy Data				Week 24	**SPD**	■	■
Total annual **Active Energy** requirements under average conditions of each **Network Operator** and each **Non-Embedded Customer** in the following categories of **Customer** Tariff:-						■	■
LV1						■	■
LV2						■	■
LV3						■	■
EHV						■	■
HV						■	■
Traction						■	■
Lighting						■	■
User System Losses						■	■
Active Energy from **Embedded Small Power Stations** and **Embedded Medium Power Stations**						■	■

NOTES:

1. 'F. yr.' means '**Financial Year**'

2. **Demand** and **Active Energy** Data (General)

   Demand and **Active Energy** data should relate to the point of connection to the **National Electricity Transmission System** and should be net of the output (as reasonably considered appropriate by the **User**) of all **Embedded Small Power Stations**, **Medium Power Stations** and **Customer Generating Plant**. Auxiliary demand of **Embedded Power Stations** should be included in the demand data submitted by the **User** at the **Connection Point**. **Users** should refer to the **PC** for a full definition of the **Demand** to be included.

3. **Demand** profiles and **Active Energy** data should be for the total **System** of the **Network Operator**, including all **Connection Points**, and for each **Non-Embedded Customer**. **Demand Profiles** should give the numerical maximum demand that in the **User**'s opinion could reasonably be imposed on the **National Electricity Transmission System**.

4. In addition the demand profile is to be supplied for such days as **The Company** may specify, but such a request is not to be made more than once per calendar year.

SCHEDULE 11 - CONNECTION POINT DATA
PAGE 1 OF 5

The following information is required from each **Network Operator** and from each **Non-Embedded Customer**. The data should be provided in calendar week 24 each year (although **Network Operators** may delay the submission until calendar week 28).

Table 11(a)

Connection Point:

Connection Point Demand at the time of - (select each one in turn) (Provide data for each Access Period associated with the Connection Point)	a) maximum **Demand** b) peak **National Electricity Transmission System Demand** *(specified by **The Company**)* c) minimum **National Electricity Transmission System Demand** *(specified by **The Company**)* d) maximum **Demand** during **Access Period** e) specified by either **The Company** or a **User**	
Name of **Transmission Interface Circuit** out of service during **Access Period** *(if reqd)*.		**PC.A.4.1.4.2**

DATA DESCRIPTION *(CUSC Contract □ & CUSC Application Form ■)*	Outturn	Outturn Weather Corrected	F.Yr 1	F.Yr 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr 6	F.Yr 7	F.Yr 8	DATA CAT
Date of a), b), c), d) or e) as denoted above.											**PC.A.4.3.3**
Time of a), b), c), d) or e) as denoted above.											**PC.A.4.3.3**
Connection Point Demand (MW)											**PC.A.4.3.1**
Connection Point Demand (MVAr)											**PC.A.4.3.1**
Deduction made at **Connection Point** for **Small Power Stations**, **Medium Power Stations** and **Customer Generating Plant** (MW)											**PC.A.4.3.2(a)**
Reference to valid **Single Line Diagram**											**PC.A.4.3.5**
Reference to node and branch data.											**PC.A.2.2**

Note: The following data block can be repeated for each post fault network revision that may impact on the Transmission System.

Reference to post-fault revision of **Single Line Diagram**											**PC.A.4.5**
Reference to post-fault revision of the node and branch data associated with the **Single Line Diagram**											**PC.A.4.5**
Reference to the description of the actions and timescales involved in effecting the post-fault actions (e.g. auto-switching, manual, teleswitching, overload protection operation etc)											**PC.A.4.5**

Access Group:		

*Note: The following data block to be repeated for each **Connection Point** with the **Access Group**.*

Name of associated **Connection Point** within the same **Access Group:**											**PC.A.4.3.1**
Demand at associated **Connection Point** (MW)											**PC.A.4.3.1**
Demand at associated **Connection Point** (MVAr)											**PC.A.4.3.1**
Deduction made at associated **Connection Point** for **Small Power Stations**, **Medium Power Stations** and **Customer Generating Plant** (MW)											**PC.A.4.3.2(a)**

Table 11(b)

Embedded Generation Data											
Connection Point:											
DATA DESCRIPTION	Outturn	Outturn Weather Corrected	F.Yr 1	F.Yr 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr 6	F.Yr 7	F.Yr 8	DATA CAT
Small Power Station, **Medium Power Station** and **Customer** Generation Summary	For each **Connection Point** where there are **Embedded Small Power Stations**, **Medium Power Stations** or **Customer Generating Stations** the following information is required:										
No. of **Small Power Stations**, **Medium Power Stations** or **Customer Power Stations**											**PC.A.3.1 .4(a)**
Number of **Generating Units** within these stations											**PC.A.3.1 .4(a)**
Summated Capacity of all these **Generating Units**											**PC.A.3.1 .4(a)**
Where the **Network Operator's System** places a constraint on the capacity of an **Embedded Large Power Station**											
Station Name											**PC.A.3.2 .2(c)**
Generating Unit											**PC.A.3.2 .2(c)**
System Constrained Capacity											**PC.A.3.2 .2(c)(i)**
Reactive Despatch Network Restriction											**PC.A.3.2 .2(c)(ii)**

Where the **Network Operator's System** places a constraint on the capacity of an **Offshore Transmission System** at an **Interface Point**											
Offshore Transmission System Name											**PC.A.3.2. 2(c)**
Interface Point Name											**PC.A.3.2. 2(c)**
Maximum Export Capacity											**PC.A.3.2. 2(c)**
Maximum Import Capacity											**PC.A.3.2. 2(c)**

SCHEDULE 11 - CONNECTION POINT DATA

PAGE 3 OF 5

Table 11(c)

For each **Embedded Small Power Station** of 1MW and above, the following information is required, effective 2015 in line with the Week 24 data submissions.												
DATA DESCRIPTION	An **Embedded Small Power Station** reference unique to each **Network Operator**	Connection Date (**Financial Year** for generator connecting after week 24 2015)	Generator unit Reference	Technology Type / Production type	CHP (Y/N)	Registered capacity in MW (as defined in the **Distribution Code**)	Lowest voltage node on the most up-to-date **Single Line Diagram** to which it connects or where it will export most of its power	Where it exports electricity from wind PV or storage, the geographical location of the primary or higher voltage substation to which it connects	Control mode	Control mode voltage target and reactive range or target pf (as appropriate)	Loss of mains protection type	Loss of mains protection settings
DATA CAT	PC.A.3.1.4 (a)		PC.A.3.1.4 (a)	PC.A.3.1.4 (a)	PC.A.3.1.4	PC.A.3.1.4 (a)	PC.A.3.1.4 (a)	PC.A.3.1.4 (a)	PC.A.3.1.4 (a)	PC.A.3.1.4 (a)	PC.A.3.1.4 (a)	PC.A.3.1.4 (a)

SCHEDULE 11 - CONNECTION POINT DATA
PAGE 4 OF 5

NOTES:

1. 'F.Yr.' means '**Financial Year**'. F.Yr. 1 refers to the current financial year.

2. All **Demand** data should be net of the output (as reasonably considered appropriate by the **User**) of all **Embedded Small Power Stations**, **Embedded Medium Power Stations** and **Customer Generating Plant**. Generation and / or Auxiliary demand of **Embedded Large Power Stations** should not be included in the demand data submitted by the **User**. **Users** should refer to the **PC** for a full definition of the **Demand** to be included.

3. Peak **Demand** should relate to each **Connection Point** individually and should give the maximum demand that in the **User's** opinion could reasonably be imposed on the **National Electricity Transmission System**. **Users** may submit the **Demand** data at each node on the **Single Line Diagram** instead of at a **Connection Point** as long as the **User** reasonably believes such data relates to the peak (or minimum) at the **Connection Point**.

   In deriving **Demand** any deduction made by the **User** (as detailed in note 2 above) to allow for **Embedded Small Power Stations**, **Embedded Medium Power Stations** and **Customer Generating Plant** is to be specifically stated as indicated on the Schedule.

4. **The Company** may at its discretion require details of any **Embedded Small Power Stations** or **Embedded Medium Power Stations** whose output can be expected to vary in a random manner (e.g. wind power) or according to some other pattern (e.g. tidal power)

5. Where more than 95% of the total **Demand** at a **Connection Point** is taken by synchronous motors, values of the **Power Factor** at maximum and minimum continuous excitation may be given instead. **Power Factor** data should allow for series reactive losses on the **User's System** but exclude reactive compensation network susceptance specified separately in Schedule 5.

6. Where a **Reactive Despatch Network Restriction** is in place which requires the generator to maintain a target voltage set point this should be stated as an alternative to the size of the **Reactive Despatch Network Restriction**.

Table 11 (d)

Embedded Small Power Stations <1MW

Network Operator	

Fuel Type	**Aggregate Registered Capacity** Total MW	**Number of PGMs**	**Comments**
Biomass			
Fossil brown coal/lignite			
Fossil coal-derived gas			
Fossil gas			
Fossil hard coal			
Fossil oil			
Fossil oil shale			
Fossil peat			
Geothermal			
Hydro pumped storage			
Hydro run-of-river and poundage			
Hydro water reservoir			
Marine			
Nuclear			
Other renewable			
Solar			
Waste			
Wind offshore			
Wind onshore			
Other			

SCHEDULE 12 - DEMAND CONTROL
PAGE 1 OF 2

The following information is required from each **Network Operator** and where indicated with an asterisk from **Externally Interconnected System Operators** and/or **Interconnector Users** and a **Pumped Storage Generator** and **Generators** in respect of **Electricity Storage Modules**. Where indicated with a double asterisk, the information is only required from **Suppliers**.

DATA DESCRIPTION	UNITS		UPDATE TIME	
Demand Control **Demand** met or to be relieved by **Demand Control** (averaging at the **Demand Control Notification Level** or more over a half hour) at each **Connection Point**. **Demand Control** at time of **National Electricity Transmission System** weekly peak demand Amount Duration	 MW Min	)F.yrs 0 to 5)	 Week 24	 **OC1**
For each half hour	MW	Wks 2-8 ahead	1000 Mon	**OC1**
For each half hour	MW	Days 2-12 ahead	1200 Wed	**OC1**
For each half hour	MW	Previous calendar day	0600 daily	**OC1**
****Customer Demand Management** (at the **Customer Demand Management Notification Level** or more at the **Connection Point**)				
For each half hour	MW	Any time in Control Phase		**OC1**
For each half hour	MW	Remainder of period	When changes occur to previous plan	**OC1**
For each half hour	MW	Previous calendar day	0600 daily	**OC1**
In Scotland, **Load Management Blocks For each block of 5MW or more, for each half hour	MW	For the next day	11:00	**OC1**

SCHEDULE 12 - DEMAND CONTROL
PAGE 2 OF 2

DATA DESCRIPTION	UNITS	TIME COVERED	UPDATE TIME	DATA CAT.
*__**Demand Control** or Pump Tripping Offered as Reserve__				
Magnitude of **Demand** or pumping load or **Electricity Storage** charging load which is tripped	MW	Year ahead from week 24	Week 24	**DPD I**
System Frequency at which tripping is initiated	Hz	"	"	"
Time duration of **System Frequency** below trip setting for tripping to be initiated	S	"	"	"
Time delay from trip initiation to Tripping	S	"	"	"
Electricity Storage Module data				
Maximum Capacity	MW	"	"	"
		"	"	"
Maximum Import Power	MW	"	"	"
Registered Import Capability	MW	"	"	"
Charge Time	Min	"	"	"
		"	"	"
Discharge time	Min	"	"	"
Operating periods	Min	"	"	"
__Emergency Manual Load Disconnection__				
Method of achieving load disconnection	Text	Year ahead from week 24	Annual in week 24	OC6
Annual ACS Peak Demand (**Active Power**) at **Connection Point** (requested under Schedule 11 - repeated here for reference)	MW	"	"	"
Cumulative percentage of **Connection Point Demand** (**Active Power**) which can be disconnected by the following times from an instruction from **The Company**				
5 mins	%	"	"	"
10 mins	%	"	"	"
15 mins	%	"	"	"
20 mins	%	"	"	"
25 mins	%	"	"	"
30 mins	%	"	"	"

Notes:

1. **Network Operators** may delay the submission until calendar week 28.
2. No information collated under this Schedule will be transferred to the **Relevant Transmission Licensees** (or **Generators** undertaking **OTSDUW**).

SCHEDULE 12A - AUTOMATIC LOW FREQUENCY DEMAND DISCONNECTION

Time Covered: Year ahead from week 24 Data Category: OC6
Update Time: Annual in week 24

	GSP	Low Frequency Demand Disconnection Blocks MW									Residual
	Demand	1	2	3	4	5	6	7	8	9	demand
Grid Supply Point	MW	48.8Hz	48.75Hz	48.7Hz	48.6Hz	48.5Hz	48.4Hz	48.2Hz	48.0Hz	47.8Hz	MW
GSP1 GSP2 GSP3											
Total demand disconnected MW per block %											
Total demand disconnection		MW (	% of aggregate demand of		MW)						

Note: All demand refers to that at the time of forecast **National Electricity Transmission System** peak demand.

Network Operators may delay the submission until calendar week 28

No information collated under this schedule will be transferred to the **Relevant Transmission Licensees** (or **Generators** undertaking **OTSDUW**).

SCHEDULE 13 - FAULT INFEED DATA
PAGE 1 OF 2

The data in this Schedule 13 is all **Standard Planning Data**, and is required from all **Users** other than **Generators** who are connected to the **National Electricity Transmission System** via a **Connection Point** (or who are seeking such a connection). A data submission is to be made each year in Week 24 (although **Network Operators** may delay the submission until Week 28). A separate submission is required for each node included in the **Single Line Diagram** provided in Schedule 5.

DATA DESCRIPTION	UNITS	F.Yr 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	
SHORT CIRCUIT INFEED TO THE **NATIONAL ELECTRICITY TRANSMISSION SYSTEM** FROM **USERS SYSTEM** AT A **CONNECTION POINT**										CUSC Contract	CUSC App. Form
(PC.A.2.5)											
Name of node or **Connection Point**										□	■
Symmetrical three phase short-circuit current infeed											
- at instant of fault	kA									□	■
- after subtransient fault current contribution has substantially decayed	Ka									□	■
Zero sequence source impedances as seen from the **Point of Connection** or node on the **Single Line Diagram** (as appropriate) consistent with the maximum infeed above:											
- Resistance	% on 100									□	■
- Reactance	% on 100									□	■
Positive sequence X/R ratio at instance of fault										□	■
Pre-Fault voltage magnitude at which the maximum fault currents were calculated	p.u.									□	■

SCHEDULE 13 - FAULT INFEED DATA
PAGE 2 OF 2

DATA DESCRIPTION	UNITS	F.Yr 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	
SHORT CIRCUIT INFEED TO THE **NATIONAL ELECTRICITY TRANSMISSION SYSTEM** FROM **USERS SYSTEM** AT A **CONNECTION POINT**										CUSC Contract	CUSC App. Form
Negative sequence impedances of **User's System** as seen from the **Point of Connection** or node on the **Single Line Diagram** (as appropriate). If no data is given, it will be assumed that they are equal to the positive sequence values.											
- Resistance	% on 100									□	■
- Reactance	% on 100									□	■

SCHEDULE 14 - FAULT INFEED DATA (GENERATORS INCLUDING UNIT TRANSFORMERS AND STATION TRANSFORMERS)

The data in this Schedule 14 is all **Standard Planning Data**, and is to be provided by **Generators**, with respect to all directly connected **Power Stations**, all **Embedded Large Power Stations** and all **Embedded Medium Power Stations** connected to the **Subtransmission System**. A data submission is to be made each year in Week 24.

Fault infeeds via **Unit Transformers**

A submission should be made for each **Generating Unit** (including those which are part of a **Synchronous Power Generating Module**) with an associated **Unit Transformer**. Where there is more than one **Unit Transformer** associated with a **Generating Unit**, a value for the total infeed through all **Unit Transformers** should be provided. The infeed through the **Unit Transformer(s)** should include contributions from all motors normally connected to the **Unit Board**, together with any generation (e.g. **Auxiliary Gas Turbines**) which would normally be connected to the **Unit Board**, and should be expressed as a fault current at the **Generating Unit** terminals for a fault at that location.

DATA DESCRIPTION	UNITS	F.Yr. 0	F.Yr. 1	F.Yr 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	
(PC.A.2.5)										CUSC Contract	CUSC App. Form
Name of **Power Station**										□	■
Number of **Unit Transformers**										□	■
Symmetrical three phase short-circuit current infeed through the **Unit Transformers**(s) for a fault at the **Generating Unit** terminals											
- at instant of fault	kA									□	■
- after subtransient fault current contribution has substantially decayed	kA									□	■
Positive sequence X/R ratio at instance of fault										□	■
Subtransient time constant (if significantly different from 40ms)	ms									□	■
Pre-fault voltage at fault point (if different from 1.0 p.u.)										□	■
The following data items need only be supplied if the **Generating Unit** Step-up Transformer can supply zero sequence current from the **Generating Unit** side to the **National Electricity Transmission System**											
Zero sequence source impedances as seen from the **Generating Unit** terminals consistent with the maximum infeed above:											
- Resistance	% on 100									□	■
- Reactance	% on 100									□	■

SCHEDULE 14 - FAULT INFEED DATA (GENERATORS INCLUDING UNIT TRANSFORMERS AND STATION TRANSFORMERS)

Fault infeeds via Station Transformers

A submission is required for each **Station Transformer** directly connected to the **National Electricity Transmission System**. The submission should represent normal operating conditions when the maximum number of **Gensets** are **Synchronised** to the **System**, and should include the fault current from all motors normally connected to the **Station Board**, together with any Generation (e.g. **Auxiliary Gas Turbines**) which would normally be connected to the **Station Board**. The fault infeed should be expressed as a fault current at the hv terminals of the **Station Transformer** for a fault at that location.

If the submission for normal operating conditions does not represent the worst case, then a separate submission representing the maximum fault infeed that could occur in practice should be made.

DATA DESCRIPTION	UNITS	F.Yr. 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	
(PC.A.2.5)										CUSC Contract	CUSC App. Form
Name of **Power Station**										□	■
Number of **Station Transformers**										□	■
Symmetrical three phase short-circuit current infeed for a fault at the **Connection Point**											
- at instant of fault	kA									□	■
- after subtransient fault current contribution has substantially decayed	kA									□	■
Positive sequence X/R ratio At instance of fault										□	■
Subtransient time constant (if significantly different from 40ms)	ms									□	■
Pre-fault voltage (if different from 1.0 p.u.) at fault point (See note 1)										□	■
Zero sequence source Impedances as seen from the **Point of Connection** Consistent with the maximum Infeed above:											
- Resistance	% on 100									□	■
- Reactance	% on 100									□	■

Note 1. The pre-fault voltage provided above should represent the voltage within the range 0.95 to 1.05 that gives the highest fault current

Note 2. % on 100 is an abbreviation for % on 100 MVA

SCHEDULE 14 - FAULT INFEED DATA (GENERATORS INCLUDING UNIT TRANSFORMERS AND STATION TRANSFORMERS)

Fault infeeds from **Power Park Modules**

A submission is required for the whole **Power Park Module** and for each **Power Park Unit** type or equivalent. The submission shall represent operating conditions that result in the maximum fault infeed. The fault current from all motors normally connected to the **Power Park Unit's** electrical system shall be included. The fault infeed shall be expressed as a fault current at the terminals of the **Power Park Unit**, or the **Common Collection Busbar** if an equivalent **Single Line Diagram** and associated data as described in PC.A.2.2.2 is provided, and the **Grid Entry Point**, or **User System Entry Point** if **Embedded**, for a fault at the **Grid Entry Point**, or **User System Entry Point** if **Embedded**.

Should actual data in respect of fault infeeds be unavailable at the time of the application for a **CUSC Contract** or **Embedded Development Agreement**, a limited subset of the data, representing the maximum fault infeed that may result from all of the plant types being considered, shall be submitted. This data will, as a minimum, represent the root mean square of the positive, negative and zero sequence components of the fault current for both single phase and three phase solid faults at the **Grid Entry Point** (or **User System Entry Point** if **Embedded**) at the time of fault application and 50ms following fault application. Actual data in respect of fault infeeds shall be submitted to **The Company** as soon as it is available, in line with PC.A.1.2

DATA DESCRIPTION	UNITS	F.Yr. 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	
(PC.A.2.5)										CUSC Contract	CUSC App. Form
Name of **Power Station**										□	■
Name of Power Park Module										□	■
Power Park Unit type										□	■
A submission shall be provided for the contribution of the entire **Power Park Module** and each type of **Power Park Unit** or equivalent to the positive, negative and zero sequence components of the short circuit current at the **Power Park Unit** terminals, or **Common Collection Busbar**, and **Grid Entry Point** or **User System Entry Point** if **Embedded** for											
(i) a solid symmetrical three phase short circuit										□	■
(ii) a solid single phase to earth short circuit										□	■
(iii) a solid phase to phase short circuit										□	■
(iv) a solid two phase to earth short circuit										□	■
at the **Grid Entry Point** or **User System Entry Point** if **Embedded**.										□	■
If protective controls are used and active for the above conditions, a submission shall be provided in the limiting case where the protective control is not active. This case may require application of a non-solid fault, resulting in a retained voltage at the fault point.										□	■

SCHEDULE 14 - FAULT INFEED DATA (GENERATORS INCLUDING UNIT TRANSFORMERS AND STATION TRANSFORMERS)

PAGE 4 OF 5

DATA DESCRIPTION	UNITS	F.Yr. 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	DATA DESCRIPTION
										CUSC Contract	CUSC App. Form
- A continuous time trace and table showing the root mean square of the positive, negative and zero sequence components of the fault current from the time of fault inception to 140ms after fault inception at 10ms intervals	Graphical and tabular kA versus s									□	■
- A continuous time trace and table showing the positive, negative and zero sequence components of retained voltage at the terminals or **Common Collection Busbar**, if appropriate	pu versus s									□	■
- A continuous time trace and table showing the root mean square of the positive, negative and zero sequence components of retained voltage at the fault point, if appropriate	pu versus s									□	■

SCHEDULE 14 - FAULT INFEED DATA (GENERATORS INCLUDING UNIT TRANSFORMERS AND STATION TRANSFORMERS)

DATA DESCRIPTION	UNITS	F.Yr. 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	DATA DESCRIPTION
										CUSC Contract	CUSC App. Form
For **Power Park Units** that utilise a protective control, such as a crowbar circuit,											
- additional rotor resistance applied to the **Power Park Unit** under a fault situation	% on MVA									□	■
										□	■
- additional rotor reactance applied to the **Power Park Unit** under a fault situation.	% on MVA										
Positive sequence X/R ratio of the equivalent at time of fault at the **Common Collection Busbar**										□	■
Minimum zero sequence impedance of the equivalent at a **Common Collection Busbar**										□	■
Active Power generated pre-fault	MW									□	■
Number of **Power Park Units** in equivalent generator										□	■
Power Factor (lead or lag)										□	■
Pre-fault voltage (if different from 1.0 pu) at fault point (See note 1)	pu									□	■
Items of reactive compensation switched in pre-fault										□	■

Note 1. The pre-fault voltage provided above should represent the voltage within the range 0.95 pu to 1.05 pu that gives the highest fault current

SCHEDULE 15 – MOTHBALLED POWER GENERATING MODULE, MOTHBALLED GENERATING UNIT, MOTHBALLED POWER PARK MODULE (INCLUDING MOTHBALLED DC CONNECTED POWER PARK MODULES), MOTHBALLED HVDC SYSTEMS, MOTHBALLED HVDC CONVERTERS, MOTHBALLED DC CONVERTERS AT A DC CONVERTER STATION AND ALTERNATIVE FUEL DATA

MOTHBALLED POWER GENERATING MODULES, MOTHBALLED GENERATING UNIT, MOTHBALLED POWER PARK MODULE (INCLUDING **MOTHBALLED DC CONNECTED POWER PARK MODULES**), **MOTHBALLED HVDC** SYSTEMS, **MOTHBALLED HVDC CONVERTERS** OR **MOTHBALLED DC CONVERTER AT A DC CONVERTER STATION** AND ALTERNATIVE FUEL DATA

The following data items must be supplied with respect to each **Mothballed Power Generating Module**, **Mothballed Generating Unit**, **Mothballed Power Park Module** (including **Mothballed DC Connected Power Park Modules**), **Mothballed HVDC Systems**, **Mothballed HVDC Converters** or **Mothballed DC Converters at a DC Converter station**

Power Station_____ **Generating Unit, Power Park Module** or **DC Converter** Name (e.g. Unit 1)

DATA DESCRIPTION	UNITS	DATA CAT	**GENERATING UNIT** DATA						
			<1 month	1-2 months	2-3 months	3-6 months	6-12 months	>12 months	Total MW being returned
MW output that can be returned to service	MW	DPD II							

Notes

1. The time periods identified in the above table represent the estimated time it would take to return the **Mothballed Power Generating Module**, **Mothballed Generating Unit, Mothballed Power Park Module (Mothballed DC Connected Power Park Modules**), **Mothballed HVDC Systems**, **Mothballed HVDC Converters** or **Mothballed DC Converter** at a **DC Converter Station** to service once a decision to return has been made.
2. Where a **Mothballed Power Generating Module**, **Mothballed Generating Unit, Mothballed Power Park Module** (including a Mothballed **DC Connected Power Park Module**), **Mothballed HVDC System**, **Mothballed HVDC Converter** or **Mothballed DC Converter** at a **DC Converter Station** can be physically returned in stages covering more than one of the time periods identified in the above table then information should be provided for each applicable time period.
3. The estimated notice to physically return MW output to service should be determined in accordance with **Good Industry Practice** assuming normal working arrangements and normal plant procurement lead times.
4. The MW output values in each time period should be incremental MW values, e.g. if 150MW could be returned in 2 – 3 months and an additional 50MW in 3 – 6 months then the values in the columns should be Nil, Nil, 150, 50, Nil, Nil, 200 respectively.
5. Significant factors which may prevent the **Mothballed Power Generating Module**, **Mothballed Generating Unit**, **Mothballed Power Park Module (Mothballed DC Connected Power Park Module). Mothballed HVDC System, Mothballed HVDC Converter** or **Mothballed DC Converter** at a **DC Converter Station** achieving the estimated values provided in this table, excluding factors relating to **Transmission Entry Capacity**, should be appended separately.

ALTERNATIVE FUEL INFORMATION

The following data items for alternative fuels need only be supplied with respect to each **Generating Unit** whose primary fuel is gas including those which form part of a **Power Generating Module**.

Power Station _____ **Generating Unit** Name (e.g. Unit 1)

DATA DESCRIPTION	UNITS	DATA CAT	**GENERATING UNIT** DATA			
			1	2	3	4
Alternative Fuel Type (*please specify)	Text	DPD II	Oil distillate	Other gas*	Other*	Other*
CHANGEOVER TO ALTERNATIVE FUEL						
For off-line changeover:						
Time to carry out off-line fuel changeover	Minutes	DPD II				
Maximum output following off-line changeover	MW	DPD II				
For on-line changeover:						
Time to carry out on-line fuel changeover	Minutes	DPD II				
Maximum output during on-line fuel changeover	MW	DPD II				
Maximum output following on-line changeover	MW	DPD II				
Maximum operating time at full load assuming:						
Typical stock levels	Hours	DPD II				
Maximum possible stock levels	Hours	DPD II				
Maximum rate of replacement of depleted stocks of alternative fuels on the basis of **Good Industry Practice**	MWh(electrical) /day	DPD II				
Is changeover to alternative fuel used in normal operating arrangements?	Text	DPD II				
Number of successful changeovers carried out in the last **Financial Year** (** delete as appropriate)	Text	DPD II	0 / 1-5 / 6-10 / 11-20 / >20 **	0 / 1-5 / 6-10 / 11-20 / >20 **	0 / 1-5 / 6-10 / 11-20 / >20 **	0 / 1-5 / 6-10 / 11-20 / >20 **

DATA DESCRIPTION	UNITS	DATA CAT	**GENERATING UNIT** DATA			
			1	2	3	4
CHANGEOVER BACK TO MAIN FUEL						
For off-line changeover:						
Time to carry out off-line fuel changeover	Minutes					
For on-line changeover:						
Time to carry out on-line fuel changeover	Minutes					
Maximum output during on-line fuel changeover	MW					

Notes

1. Where a **Generating Unit** has the facilities installed to generate using more than one alternative fuel type details of each alternative fuel should be given.
2. Significant factors and their effects which may prevent the use of alternative fuels achieving the estimated values provided in this table (e.g. emissions limits, distilled water stocks etc.) should be appended separately.

SCHEDULE 16 - BLACK START INFORMATION
PAGE 1 OF 2
PART I

BLACK START INFORMATION

The following data/text items are required from each **Generator** for each **BM Unit** at a **Large Power Station** as detailed in PC.A.5.7. Data is not required for **Generating Units** that are contracted to provide **Black Start Capability, or Electricity Storage Modules** which have short cycle times. The data should be provided in accordance with PC.A.1.2 and also, where possible, upon request from **The Company** during a **Black Start**.

Data Description *(PC.A.5.7) (■ CUSC Contract)*	Units	Data Category
Assuming all **BM Units** were running immediately prior to the **Total Shutdown** or **Partial Shutdown** and in the event of loss of all external power supplies, provide the following information:		
a) Expected time for the first and subsequent **BM Units** to be **Synchronised**, from the restoration of external power supplies, assuming external power supplies are not available for up to 24hrs	Tabular or Graphical	DPD II
b) Describe any likely issues that would have a significant impact on a **BM Unit's** time to be **Synchronised** arising as a direct consequence of the inherent design or operational practice of the **Power Station** and/or **BM Unit**, e.g. limited barring facilities, time from a **Total Shutdown** or **Partial Shutdown** at which batteries would be discharged.	Text	DPD II
Block Loading Capability:		
c) Provide estimated **Block Loading Capability** from 0MW to **Registered Capacity** of each **BM Unit** based on the unit being 'hot' (run prior to shutdown) and also 'cold' (not run for 48hrs or more prior to the shutdown). The **Block Loading Capability** should be valid for a frequency deviation of 49.5Hz – 50.5Hz. The data should identify any required 'hold' points.	Tabular or Graphical	DPD II

SCHEDULE 16 - BLACK START INFORMATION

PAGE 1 OF 2

PART II

BLACK START INFORMATION The following data/text items are required from each **HVDC System Owner** or **DC Converter Station Owner** for each **HVDC System** and **DC Converter Station** as detailed in PC.A.5.7. Data is not required for **HVDC Systems** and **DC Converter Stations** that are contracted to provide a **Black Start Capability**. The data should be provided in accordance with PC.A.1.2 and also, where possible, upon request from **The Company** during a **Black Start**.	Data Description *(PC.A.5.7) (■ CUSC Contract)*	Units	Data Category
	Assuming all **BM Units** were running immediately prior to the **Total Shutdown** or **Partial Shutdown** and in the event of loss of all external power supplies, provide the following information:		
	a) Expected time for the first and subsequent **BM Units** to be **Synchronised**, from the restoration of external power supplies, assuming external power supplies are not available for up to 24hrs	Tabular or Graphical	DPD II
	b) Describe any likely issues that would have a significant impact on a **BM Units** time to be **Synchronised** arising as a direct consequence of the inherent design or operational practice of the **HVDC System** or **DC Converter Station** and/or **BM Unit**, e.g. time from a **Total Shutdown** or **Partial Shutdown** at which batteries would be discharged.	Text	DPD II
	Block Loading Capability:		
	c) Provide estimated incremental **Active Power** steps, form no load to **Rated MW** which an **HVDC System** or **DC Converter Station** can instantaneously supply without causing it to trip or go outside the **Frequency** range of 47.5Hz – 52Hz (or an otherwise agreed **Frequency** range). The time between each incremental step shall also be provided. In addition data should be provided from 0MW to **Registered Capacity** of each **BM Unit** based on the **HVDC System** or **DC Converter Station** being (not run for 48hrs or more prior to the shutdown) or run immediately before the **Partial Shutdown** or **Total Shutdown**. The data supplied should be valid for a **Frequency** deviation of 49.5Hz – 50.5Hz and should identify any required 'hold' points.	Tabular or Graphical	DPD II

SCHEDULE 17 - ACCESS PERIOD DATA

PAGE 1 OF 1

(PC.A.4 - CUSC Contract ■)

Submissions by **Users** using this Schedule 17 shall commence in 2011 and shall then continue in each year thereafter

Access Group	

Asset Identifier	Start Week	End Week	Maintenance Year (1, 2 or 3)	Duration	Potential Concurrent Outage (Y/N)

Comments

SCHEDULE 18 - OFFSHORE TRANSMISSION SYSTEM DATA
PAGE 1 OF 24

The data in this Schedule 18 is required from **Generators** who are undertaking **OTSDUW** and connecting to a **Transmission Interface Point**.

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CAT.	**GENERATING UNIT** OR STATION DATA						
		CUSC Contract	CUSC App. Form		F.Yr0	F.Yr1	F.Yr2	F.Yr3	F.Yr4	F.Yr5	F.Yr 6
INDIVIDUAL **OTSDUW** DATA											
Interface Point Capacity (PC.A.3.2.2 (a))	MW MVAr	□	■								
Performance Chart at the **Transmission Interface Point** for **OTSDUW Plant and Apparatus** (PC.A.3.2.2(f)(iv)		□	■								
OTSDUW DEMANDS											
Demand associated with the **OTSDUW Plant and Apparatus** (excluding **OTSDUW DC Converters** – see Note 1)) supplied at each **Interface Point**. The **User** should also provide the **Demand** supplied to each **Connection Point** on the **OTSDUW Plant and Apparatus**. *(PC.A.5.2.5)*											
- The maximum **Demand** that could occur.	MW MVAr	□ □		**DPD I** **DPD I**							
- **Demand** at specified time of annual peakhalf hour of **National Electricity Transmission System Demand** at **Annual ACS Conditions**.	MW MVAr	□ □		**DPD II** **DPD II**							
- **Demand** at specified time of annual minimum half-hour of **National Electricity Transmission System Demand**.	MW MVAr	□ □		**DPD II** **DPD II**							
(Note 1 – **Demand** required from **OTSDUW DC Converters** should be supplied under page 2 of Schedule 18).											

SCHEDULE 18 - OFFSHORE TRANSMISSION SYSTEM DATA
PAGE 2 OF 24

OTSDUW USERS SYSTEM DATA

DATA DESCRIPTION	UNITS	DATA to **RTL**		DATA CATEGORY
		CUSC Contract	CUSC App. Form	
OFFSHORE TRANSMISSION SYSTEM LAYOUT *(PC.A.2.2.1, PC.A.2.2.2 and P.C.A.2.2.3)*				
A **Single Line Diagram** showing connectivity of all of the **Offshore Transmission System** including all **Plant and Apparatus** between the **Interface Point** and all Connection **Points** is required.		■	■	**SPD**
This **Single Line Diagram** shall depict the arrangement(s) of all of the existing and proposed load current carrying **Apparatus** relating to both existing and proposed **Interface Points** and **Connection Points**, showing electrical circuitry (i.e. overhead lines, underground cables (including subsea cables), power transformers and similar equipment), operating voltages, circuit breakers and phasing arrangements		■	■	**SPD**
Operational Diagrams of all substations within the **OTSDUW Plant and Apparatus**		■	■	**SPD**
SUBSTATION INFRASTRUCTURE *(PC.A.2.2.6)*				
For the infrastructure associated with any **OTSDUW Plant and Apparatus**				
Rated 3-phase rms short-circuit withstand current	kA	■	■	**SPD**
Rated 1-phase rms short-circuit withstand current	kA	■	■	**SPD**
Rated Duration of short-circuit withstand	s	■	■	**SPD**
Rated rms continuous current	A	■	■	**SPD**
LUMPED SUSCEPTANCES *(PC.A.2.3)*				
Equivalent Lumped Susceptance required for all parts of the User's Subtransmission System (including OTSDUW Plant and Apparatus) which are not included in the Single Line Diagram.		■	■	
This should not include:		■	■	
(a) independently switched reactive compensation equipment identified above.		■	■	
(b) any susceptance of the **OTSDUW Plant and Apparatus** inherent in the **Demand** (**Reactive Power**) data provided on Page 1 and 2 of this Schedule 14.		■	■	
Equivalent lumped shunt susceptance at nominal **Frequency**.	% on 100 MVA	■	■	

OFFSHORE TRANSMISSION SYSTEM DATA
Branch Data (PC.A.2.2.4)

Node 1	Node 2	Rated Voltage (kV)	Operating Voltage (kV)	Circuit	PPS PARAMETERS			ZPS PARAMETERS			Maximum Continuous Ratings			Length (km)
					R1 %100 MVA	X1 %100 MVA	B 1 %100 MVA	R0 %100 MVA	X0 %100M VA	B0 %100M VA	Winter (MVA)	Spring Autumn (MVA)	Summer (MVA)	

Notes

1. For information equivalent STC Reference: STCP12-1m Part 3 – 2.1 Branch Data
2. In the case where an overhead line exists within the OTSDUW Plant and Apparatus the Mutual inductances should also be provided.

OFFSHORE TRANSMISSION SYSTEM DATA

2 Winding Transformer Data (PC.A.2.2.5)

The data below is **Standard Planning Data**, and details should be shown below of all transformers shown on the **Single Line Diagram**

HV Node	HV (kV)	LV Node	LV (kV)	Rating (MVA)	Trans-former	Positive Phase Sequence Reactance % on 100MVA			Positive Phase Sequence Resistance % on 100 MVA			Tap Changer			Winding Arr.	Earthing Method (Direct /Res /Reac)	Earthing Imped Ance method
						Max Tap	Min Tap	Nom Tap	Max Tap	Min Tap	Nom Tap	Range +% to -%	Step size %	type			

Notes

1 For information the corresponding STC Reference is STCP12-1: Part 3 – 2.4 Transformers

USERS SYSTEM DATA (OTSUA)

Auto Transformer Data 3-Winding (PC.A.2.2.5)

The data below is all **Standard Planning Data**, and details should be shown below of all transformers shown on the **Single Line Diagram**.

HV NODE	V_H (kV)	LV NODE	V_L (kV)	PSS/E Circuit	Rating (MVA)	Transformer	Positive Phase Sequence Reactance % on 100MVA			Positive Phase Sequence Resistance % on 100 MVA			Taps				Earthing Impedance Method	EQUIVALENT T ZPS PARAMETERS (FLIP)						The Company Sheet	The Company Code
							Max Tap	Min Tap	Nom Tap	Max Tap	Min Tap	Nom Tap	Range +% to -%	Step size %	Type (onload Offload	Winding Arrangement		ZOH		ZOL		ZOT Dflt X/R =20			
																		R_{0H} % 100 MVA	X_{0H} % 100 MVA	R_{0L} % 100 MVA	X_{0L} % 100 MVA	R_{0T} % 100 MVA	X_{0T} % 100 MVA		

Notes

1. For information STC Reference: STCP12-1: Part 3 - 2.4 Transformers

OFFSHORE TRANSMISSION SYSTEM DATA

Circuit Breaker Data (PC.A.2.2.6(a))

The data below is all **Standard Planning Data**, and should be provided for all **OTSUA** switchgear (i.e. circuit breakers, load disconnectors and disconnectors)

	Circuit Breaker Data							Assumed Operating Times				3 Phase				1 Phase				
Location	Name	Rated Voltage	Operating Voltage	Make	Model	Type	Year Commissioned	Circuit Breaker (mS)	Minimum Protection & Trip Relay (mS)	Total Time (mS)	Continuous Rating (A)	Fault Rating (RMS Symmetrical) (3 phase) (MVA)	Fault Break Rating (RMS Symmetrical) (3 phase) (kA)	Fault Break Rating (Peak Asymmetrical) (3 phase) (kA)	Fault Make Rating (Peak Asymmetrical) (3 phase) (kA)	Fault Rating (RMS Symmetrical) (1 phase) (MVA)	Fault Break Rating (RMS Symmetrical) (1 phase) (kA)	Fault Break Rating (Peak Asymmetrical) (1 phase) (kA)	Fault Make Rating (Peak Asymmetrical) (1 phase) (kA)	DC time constant at testing of asymmetrical breaking ability (s)

OFFSHORE TRANSMISSION SYSTEM DATA

REACTIVE COMPENSATION EQUIPMENT (PC.A.2.4(e))

Item	Node	kV	Device No.	Rating (MVAr)	P Loss (kW)	Tap range	Connection Arrangement

Notes:

1.For information STC Reference: STCP12-1: Part 3 - 2.5 Reactive Compensation Equipment

2. Data relating to continuously variable reactive compensation equipment (such as statcoms or SVCs) should be entered on the SVC Modelling table.

3. For the avoidance of doubt this includes any AC Reactive Compensation equipment included within the OTSDUW DC Converter other than harmonic filter data which is to be entered in the harmonic filter data table.

PC.A.2.4.1(e)	A mathematical representation in block diagram format to model the control of any dynamic compensation plant. The model should be suitable for RMS dynamic stability type studies in which the time constants used should not be less than 10ms.

OFFSHORE TRANSMISSION SYSTEM DATA

REACTIVE COMPENSATION - SVC Modelling Data (PC.A.2.4.1(e)(iii))

HV Node	LV Node	Control Node	Nominal Voltage (kV)	Target Voltage (kV)	Max MVAr at HV	Min MVAr at HV	Slope %	Voltage Dependant Q Limit	Normal Running Mode	R1 PPS_R	X1 PPS_X	R0 ZPS_R	X0 ZPS_X	Transf. Winding Type	Connection (Direct/Tertiary)

Notes:

1.For information the equivalent STC Reference is: STCP12-1: Part 3 - 2.7 SVC Modelling Data

OFFSHORE TRANSMISSION SYSTEM DATA
Harmonic Filter Data (including **OTSDUW DC Converter** harmonic Filter Data)
(PC.A.5.4.3.1(d) and PC.A.6.4.2)

Site Name	SLD Reference	Point of Filter Connection		
Filter Description				
Manufacturer	Model	Filter Type	Filter connection type (Delta/Star, Grounded/ Ungrounded)	Notes
Bus Voltage	Rating	Q factor	Tuning Frequency	Notes
Component Parameters (as per SLD)				
	Parameter as applicable			
Filter Component (R, C or L)	Capacitance (micro-Farads)	Inductance (milli-Henrys)	Resistance (Ohms)	Notes
Filter frequency characteristics (graphs) detailing for frequency range up to 10kHz and higher				
1. Graph of impedance (ohm) against frequency (Hz) 2. Graph of angle (degree) against frequency (Hz) 3. Connection diagram of Filter & Elements				

Notes:
1. For information STC Reference: STCP12-1: Part 3 - 2.8 Harmonic Filter Data

Information for Transient Overvoltage Assessment (**DPD I**) *(PC.A.6.2 ■ CUSC Contract)*

The information listed below may be requested by **The Company** from each **User** undertaking **OTSDUW** with respect to any **Interface Point** or **Connection Point** to enable **The Company** to assess transient overvoltage on the **National Electricity Transmission System**.

(a) Busbar layout plan(s), including dimensions and geometry showing positioning of any current and voltage transformers, through bushings, support insulators, disconnectors, circuit breakers, surge arresters, etc. Electrical parameters of any associated current and voltage transformers, stray capacitances of wall bushings and support insulators, and grading capacitances of circuit breakers;

(b) Electrical parameters and physical construction details of lines and cables connected at that busbar. Electrical parameters of all plant e.g., transformers (including neutral earthing impedance or zig-zag transformers if any), series reactors and shunt compensation equipment connected at that busbar (or to the tertiary of a transformer) or by lines or cables to that busbar;

(c) Basic insulation levels (BIL) of all **Apparatus** connected directly, by lines or by cables to the busbar;

(d) Characteristics of overvoltage **Protection** devices at the busbar and at the termination points of all lines, and all cables connected to the busbar;

(e) Fault levels at the lower voltage terminals of each transformer connected to each **Interface Point** or **Connection Point** without intermediate transformation;

(f) The following data is required on all transformers within the **OTSDUW Plant and Apparatus**.

(g) An indication of which items of equipment may be out of service simultaneously during **Planned Outage** conditions.

Harmonic Studies (**DPD I**) *(PC.A.6.4 ■ CUSC Contract)*

The information given below, both current and forecast, where not already supplied in this Schedule 14 may be requested by **The Company** from each **User** if it is necessary for **The Company** to evaluate the production/magnification of harmonic distortion on **National Electricity Transmission System**. The impact of any third party **Embedded** within the **User's System** should be reflected:-

(a) Overhead lines and underground cable circuits (including subsea cables) of the **User's OTSDUW Plant and Apparatus** must be differentiated and the following data provided separately for each type:-

Positive phase sequence resistance
Positive phase sequence reactance
Positive phase sequence susceptance

(b) for all transformers connecting the **OTSDUW Plant and Apparatus** to a lower voltage:-

Rated MVA
Voltage Ratio
Positive phase sequence resistance
Positive phase sequence reactance

(c) at the lower voltage points of those connecting transformers:-

Equivalent positive phase sequence susceptance
Connection voltage and MVAr rating of any capacitor bank and component design parameters if configured as a filter

Equivalent positive phase sequence interconnection impedance with other lower voltage points
The minimum and maximum **Demand** (both MW and MVAr) that could occur
Harmonic current injection sources in Amps at the Connection Points and Interface Points

(d) an indication of which items of equipment may be out of service simultaneously during **Planned Outage** conditions

Voltage Assessment Studies (**DPD I**) *(PC.A.6.5 ■ CUSC Contract)*

The information listed below, where not already supplied in this Schedule 14, may be requested by **The Company** from each **User** undertaking **OTSDUW** with respect to any **Connection Point** or **Interface Point** if it is necessary for **The Company** to undertake detailed voltage assessment studies (e.g. to examine potential voltage instability, voltage control co-ordination or to calculate voltage step changes on the **National Electricity Transmission System**).

(a) For all circuits of the **User's OTSDUW Plant and Apparatus**:-

Positive Phase Sequence Reactance
Positive Phase Sequence Resistance
Positive Phase Sequence Susceptance
MVAr rating of any reactive compensation equipment

(b) for all transformers connecting the **User's OTSDUW Plant and Apparatus** to a lower voltage:-

Rated MVA
Voltage Ratio
Positive phase sequence resistance
Positive Phase sequence reactance
Tap-changer range
Number of tap steps
Tap-changer type: on-load or off-circuit
AVC/tap-changer time delay to first tap movement
AVC/tap-changer inter-tap time delay

(c) at the lower voltage points of those connecting transformers

Equivalent positive phase sequence susceptance
MVAr rating of any reactive compensation equipment
Equivalent positive phase sequence interconnection impedance with other lower voltage points
The maximum **Demand** (both MW and MVAr) that could occur
Estimate of voltage insensitive (constant power) load content in % of total load at both winter peak and 75% off-peak load conditions

Short Circuit Analyses:(**DPD I**) *(PC.A.6.6 ■ CUSC Contract)*

The information listed below, both current and forecast, and where not already supplied under this Schedule 14, may be requested by **The Company** from each **User** undertaking **OTSDUW** with respect to any **Connection Point** or **Interface Point** where prospective short-circuit currents on **Transmission** equipment are close to the equipment rating.

(a) For all circuits of the **User's OTSDUW Plant and Apparatus**:-
Positive phase sequence resistance
Positive phase sequence reactance
Positive phase sequence susceptance
Zero phase sequence resistance (both self and mutuals)
Zero phase sequence reactance (both self and mutuals)
Zero phase sequence susceptance (both self and mutuals)

(b) For all transformers connecting the **User's OTSDUW Plant and Apparatus** to a lower voltage:-
Rated MVA
Voltage Ratio
Positive phase sequence resistance (at max, min and nominal tap)
Positive Phase sequence reactance (at max, min and nominal tap)
Zero phase sequence reactance (at nominal tap)
Tap changer range
Earthing method: direct, resistance or reactance
Impedance if not directly earthed

(c) At the lower voltage points of those connecting transformers:-

The maximum **Demand** (in MW and MVAr) that could occur
Short-circuit infeed data in accordance with PC.A.2.5.6(a) unless the **User's OTSDUW Plant and Apparatus** runs in parallel with the **Subtransmission System**, when to prevent double counting in each node infeed data, a π equivalent comprising the data items of PC.A.2.5.6(a) for each node together with the positive phase sequence interconnection impedance between the nodes shall be submitted**.**

Fault infeed data to be submitted by **OTSDUW Plant and Apparatus** providing a fault infeed (including **OTSDUW DC Converters**) (PC.A.2.5.5)

A submission is required for **OTSDUW Plant and Apparatus** (including **OTSDUW DC Converters** at each **Transmission Interface Point** and **Connection Point**. The submission shall represent operating conditions that result in the maximum fault infeed. The fault current from all auxiliaries of the **OTSDUW Plant and Apparatus** at the **Transmission Interface Point** and **Connection Point** shall be included. The fault infeed shall be expressed as a fault current at the **Transmission Interface Point** and also at each **Connection Point**.

Should actual data in respect of fault infeeds be unavailable at the time of the application for a **CUSC Contract** or **Embedded Development Agreement**, a limited subset of the data, representing the maximum fault infeed that may result from the **OTSDUW Plant and Apparatus**, shall be submitted. This data will, as a minimum, represent the root mean square of the positive, negative and zero sequence components of the fault current for both single phase and three phase solid faults at each **Connection Point** and **Interface Point** at the time of fault application and 50ms following fault application. Actual data in respect of fault infeeds shall be submitted to **The Company** as soon as it is available, in line with PC.A.1.2.

DATA DESCRIPTION	UNITS	F.Yr. 0	F.Yr. 1	F.Yr. 2	F.Yr. 3	F.Yr. 4	F.Yr. 5	F.Yr. 6	F.Yr. 7	DATA to **RTL**	
(PC.A.2.5)										CUSC Contract	CUSC App. Form
Name of **OTSDUW Plant and Apparatus**											
OTSDUW DC Converter type (i.e. voltage or current source)											
A submission shall be provided for the contribution of each **OTSDUW** Plant and Apparatus to the positive, negative and zero sequence components of the short circuit current at the **Interface Point** and each **Connection Point** for (i) a solid symmetrical three phase short circuit (ii) a solid single phase to earth short circuit (iii) a solid phase to phase short circuit (iv) a solid two phase to earth short circuit										□	■
If protective controls are used and active for the above conditions, a submission shall be provided in the limiting case where the protective control is not active. This case may require application of a non-solid fault, resulting in a retained voltage at the fault point.										□ □ □ □	■ ■ ■ ■

DATA DESCRIPTION	UNITS	F. Yr. 0	F. Yr. 1	F. Yr. 2	F. Yr. 3	F. Yr. 4	F. Yr. 5	F. Yr. 6	F. Yr. 7	DATA to **RTL**	
										CUSC Contract	CUSC App. Form
-A continuous time trace and table showing the root mean square of the positive, negative and zero sequence components of the fault current from the time of fault inception to 140ms after fault inception at 10ms intervals	Graphical and tabular kA versus s									□	■
- A continuous time trace and table showing the positive, negative and zero sequence components of retained voltage at the **Interface Point** and each **Connection Point**, if appropriate	p.u. versus s									□	■
- A continuous time trace and table showing the root mean square of the positive, negative and zero sequence components of retained voltage at the fault point, if appropriate	p.u. versus s									□	■
Positive sequence X/R ratio of the equivalent at time of fault at the **Interface Point** and each **Connection Point**										□	■
Minimum zero sequence impedance of the equivalent at the **Interface Point** and each **Connection Point**										□	■
Active Power transfer at the Interface Point and each Connection Point pre-fault	MW									□	■
Power Factor (lead or lag)										□	■
Pre-fault voltage (if different from 1.0 p.u.) at fault point (See note 1)	p.u.									□	■
Items of reactive compensation switched in pre-fault										□	■

Note 1. The pre-fault voltage provided above should represent the voltage within the range 0.95 to 1.05 that gives the highest fault current

Thermal Ratings Data (PC.A.2.2.4)

CIRCUIT RATING SCHEDULE

Voltage	***Offshore TO Name***
132kV	

Issue Date

CIRCUIT *Name from Site A – Site B*

		Winter				Spring/Autumn				Summer			
OVERALL CCT RATINGS		%Nom	Limit	Amps	MVA	%Nom	Limit	Amps	MVA	%Nom	Limit	Amps	MVA
Pre-Fault Continuous		84%	Line	485	111	84%	Line	450	103	84%	Line	390	89
Post-Fault Continuous		100%	Line	580	132	100%	Line	540	123	100%	Line	465	106
Pref ault load exceeds line pref ault continuous rating	6hr	95%	Line	580	132	95%	Line	540	123	95%	Line	465	106
	20m		Line	580	132		Line	540	123		Line	465	106
	10m	mva	Line	580	132	mva	Line	540	123	mva	Line	465	106
	5m	125	Line	580	132	116	Line	540	123	100	Line	465	106
	3m		Line	580	132		Line	540	123		Line	465	106
Short Term Overloads	6hr	90%	Line	580	132	90%	Line	540	123	90%	Line	465	106
	20m		Line	580	132		Line	540	123		Line	465	106
	10m	mva	Line	580	132	mva	Line	540	123	mva	Line	465	106
	5m	118	Line	580	132	110	Line	540	123	95	Line	465	106
	3m		Line	580	132		Line	540	123		Line	465	106
Limiting Item and permitted overload values for different times and pre-fault loads	6hr	84%	Line	580	132	84%	Line	540	123	84%	Line	465	106
	20m		Line	590	135		Line	545	125		Line	470	108
	10m	mva	Line	630	144	mva	Line	580	133	mva	Line	495	113
	5m	110	Line	710	163	103	Line	655	149	89	Line	555	126
	3m		Line	810	185		Line	740	170		Line	625	143
	6hr	75%	Line	580	132	75%	Line	540	123	75%	Line	465	106
	20m		Line	595	136		Line	555	126		Line	475	109
	10m	mva	Line	650	149	mva	Line	600	137	mva	Line	510	116
	5m	99	Line	760	173	92	Line	695	159	79	Line	585	134
	3m		Line	885	203		Line	810	185		Line	685	156
	6hr	60%	Line	580	132	60%	Line	540	123	60%	Line	465	106
	20m		Line	605	138		Line	560	128		Line	480	110
	10m	mva	Line	675	155	mva	Line	620	142	mva	Line	530	121
	5m	79	Line	820	187	73	Line	750	172	63	Line	635	145
	3m		Line	985	226		Line	900	206		Line	755	173
	6hr	30%	Line	580	132	30%	Line	540	123	30%	Line	465	106
	20m		Line	615	141		Line	570	130		Line	490	112
	10m	mva	Line	710	163	mva	Line	655	150	mva	Line	555	127
	5m	39	Line	895	205	36	Line	820	187	31	Line	690	158
	3m		Line	1110	255		Line	1010	230		Line	845	193

	6hr 20m 10m 5m 3m												
	6hr 20m 10m 5m 3m												
Notes or Restrictions Detailed													

Notes: 1. For information the equivalent STC Reference: STCP12-1: Part 3 - 2.6 Thermal Ratings
2. The values shown in the above table is example data.

Protection Policy *(PC.A.6.3)*

To include details of the protection policy

Protection Schedules*(PC.A.6.3)*

Data schedules for the protection systems associated with each primary plant item including:
Protection, Intertrip Signalling & operating times
Intertripping and protection unstabilisation initiation
Synchronising facilities
Delayed Auto Reclose sequence schedules

Automatic Switching Scheme Schedules *(PC.A.2.2.7)*

A diagram of the scheme and an explanation of how the system will operate and what plant will be affected by the scheme's operation.

GENERATOR INTERTRIP SCHEMES (PC.A.2.2.7(b))

Substation: _____

Details of Generator Intertrip Schemes:

A diagram of the scheme and an explanation of how the system will operate and what plant will be effected by the schemes operation.

DEMAND INTERTRIP SCHEMES (PC.A.2.2.7(b))

Substation:_____

Details of Demand Intertrip Schemes:

A diagram of the scheme and an explanation of how the system will operate and what plant will be effected by the schemes operation

Specific Operating Requirements (CC.5.2.1 or ECC.5.2.1)

SUBSTATION OPERATIONAL GUIDE

Substation: _____

Location Details:

Postal Address:	**Telephone Nos.**	**Map Ref.**
Transmission Interface		
Generator Interface		

1. **Substation Type:**

2. **Voltage Control:** *(short description of voltage control system. To include mention of modes i.e. Voltage, manual etc. Plus control step increments i.e. 0.5% or 0.33kV)*

3. **Energisation Switching Information:** *(The standard energisation switching process from dead.)*

4. **Intertrip Systems:**

5. **Reactive Plant Outage:** *(A short explanation of any system re-configurations required to facilitate the outage of any reactive plant which form part of the OTSDUW Plant and Apparatus equipment. Also any generation restrictions required).*

6. **Harmonic Filter Outage:** *(An explanation as to any OTSDUW Plant and Apparatus reconfigurations required to facilitate the outage and maintain the system within specified Harmonic limits, also any generation restrictions required).*

OTSDUW DC CONVERTER TECHNICAL DATA

OTSDUW DC CONVERTER NAME DATE:_____

Data Description	Units	DATA to **RTL**		Data Category	**DC Converter Station** Data
(PC.A.4 and PC.A.5.2.5)		CUSC Contract	CUSC App. Form		
OTSDUW DC CONVERTER (**CONVERTER** DEMANDS):					
Demand supplied through **Station Transformers** associated with the **OTSDUW DC Converter** at each **Interface Point** and each **Offshore Connection Point Grid Entry Point [PC.A.4.1]**					
- **Demand** with all **OTSDUW DC Converters** operating at **Interface Point Capacity** .	MW MVAr	□ □		**DPD II** **DPD II**	
- **Demand** with all **OTSDUW DC Converters** operating at maximum **Interface Point** flow from the **Interface Point** to each **Offshore Grid Entry Point** .	MW MVAr	□ □		**DPD II** **DPD II**	
- The maximum **Demand** that could occur.	MW MVAr	□ □		**DPD II** **DPD II**	
- **Demand** at specified time of annual peak half hour of **The Company Demand** at **Annual ACS Conditions**.	MW MVAr	□ □		**DPD II** **DPD II**	
- **Demand** at specified time of annual minimum half-hour of **The Company Demand**.	MW MVAr	□ □		**DPD II**	
OTSDUW DC CONVERTER DATA	Text	□	■	**SPD+**	
Number of poles, i.e. number of **OTSDUW DC Converters**	Text	□	■	**SPD+**	
Pole arrangement (e.g. monopole or bipole)	Diagram	□			
Return path arrangement					
Details of each viable operating configuration		□	■		
Configuration 1	Diagram	□	■	**SPD+**	
Configuration 2	Diagram	□	■		
Configuration 3	Diagram	□	■		
Configuration 4	Diagram	□	■		
Configuration 5	Diagram	□			
Configuration 6	Diagram				

Data Description	Units	DATA to **RTL**		Data Category	Operating Configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
OTSDUW DC CONVERTER DATA *(PC.A.3.3.1(d))*										
OTSDUW DC Converter Type (e.g. current or Voltage source)	Text	□	■	**SPD**						
If the busbars at the **Interface Point** or Connection Point are normally run in separate sections identify the section to which the **OTSDUW DC Converter** configuration is connected	Section Number	□	■	**SPD**						
Rated MW import per pole (PC.A.3.3.1)	MW	□	■	**SPD+**						
Rated MW export per pole (PC.A.3.3.1)	MW	□	■	**SPD+**						
ACTIVE POWER TRANSFER CAPABILITY (PC.A.3.2.2)										
Interface Point Capacity	MW	□	■	**SPD**						
	MVAr	□	■	**SPD**						
OTSDUW DC CONVERTER TRANSFORMER (PC.A.5.4.3.1)										
Rated MVA	MVA	□		**DPD II**						
Winding arrangement	kV	□		**DPD II**						
Nominal primary voltage	kV	□		**DPD II**						
Nominal secondary (converter-side) voltage(s)		□								
Positive sequence reactance	% on	□		**DPD II**						
Maximum tap	MVA	□		**DPD II**						
Nominal tap	% on			**DPD II**						
Minimum tap	MVA									
Positive sequence resistance	% on	□		**DPD II**						
Maximum tap	MVA	□		**DPD II**						
Nominal tap		□		**DPD II**						
Minimum tap	% on	□		**DPD II**						
Zero phase sequence reactance	MVA	□		**DPD II**						
Tap change range	% on			**DPD II**						
Number of steps	MVA									
	% on									
	MVA									
	% on									
	MVA									
	+% / -%									

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
OTSDUW DC CONVERTER NETWORK DATA (PC.A.5.4.3.1 (c))										
	kV	□		**DPD II**						
Rated DC voltage per pole	A	□		**DPD II**						
Rated DC current per pole										
Details of the **OTSDUW DC Network** described in diagram form including resistance, inductance and capacitance of all DC cables and/or DC lines. Details of any line reactors (including line reactor resistance), line capacitors, DC filters, earthing electrodes and other conductors that form part of the **OTSDUW DC Network** should be shown.	Diagram	□		**DPD II**						

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6

OTSDUW DC CONVERTER CONTROL SYSTEMS (PC.A.5.4.3.2)										
Static V_{DC} – P_{DC} (DC voltage – DC power) or Static V_{DC} – I_{DC} (DC voltage – DC current) characteristic (as appropriate) when operating as –Rectifier –Inverter	Diagram Diagram Diagram	□ □ □		**DPD II** **DPD II** **DPD II**						
Details of rectifier mode control system, in block diagram form together with parameters showing transfer functions of individual elements.	Diagram	□		**DPD II**						
Details of inverter mode control system, in block diagram form showing transfer functions of individual elements including parameters (as applicable).	Diagram	□		**DPD II**						
Details of **OTSDUW DC Converter** transformer tap changer control system in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of AC filter control systems in block diagram form showing transfer functions of individual elements including parameters	Diagram	□		**DPD II**						
Details of any frequency and/or load control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
Details of any large or small signal modulating controls, such as power oscillation damping controls or sub-synchronous oscillation damping controls, that have not been submitted as part of the above control system data.	Diagram	□		**DPD II**						
Transfer block diagram representation of the reactive power control at converter ends for a voltage source converter.	Diagram	□		**DPD II**						
For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of **OTSDUW DC Converter** unit models and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of AC component models and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□ □		**DPD II**						
For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of DC Grid models and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of Voltage and power controller and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram	□		**DPD II**						
For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of Special control features if applicable (e.g. power oscillation	Diagram	□		**DPD II**						

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
damping (POD) function, subsynchronous torsional interaction (SSTI) control and/or control systems in block diagram form showing transfer functions of individual elements including parameters. For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of Multi terminal control, if applicable and/or control systems in block diagram form showing transfer functions of individual elements including parameters. For **Generators** in respect of **OTSDUW** who are also **EU Code Users** details of **OTSDUW DC Converter** protection models as agreed between **The Company** and the **Generator** (in respect of **OTSDW**) and/or control systems in block diagram form showing transfer functions of individual elements including parameters.	Diagram Diagram	□ □		**DPD II** **DPD II**						

Data Description	Units	DATA to **RTL**		Data Category	Operating configuration					
		CUSC Contract	CUSC App. Form		1	2	3	4	5	6
LOADING PARAMETERS (PC.A.5.4.3.3)										
MW Export from the **Offshore Grid Entry Point** to the **Transmission Interface Point**	MW/s	□		**DPD I**						
Nominal loading rate	MW/s	□		**DPD I**						
Maximum (emergency) loading rate				**DPD II**						
Maximum recovery time, to 90% of pre-fault loading, following an AC system fault or severe voltage depression.	s	□								
Maximum recovery time, to 90% of pre-fault loading, following a transient DC Network fault.	s	□		**DPD II**						

SCHEDULE 19 – USER DATA FILE STRUCTURE

The structure of the **User Data File Structure** is given below.

i.d.	Folder name	Description of contents
Part A: Commercial & Legal		
A2	Commissioning	Commissioning & Test Programmes
A3	Statements	Statements of Readiness
A9	AS Monitoring	Ancillary Services Monitoring
A10	Self-Certification	User Self Certification of Compliance
A11	Compliance statements	Compliance Statement
Part 1: Safety & System Operation		
1.1	Interface Agreements	Interface Agreements
1.2	Safety Rules	Safety Rules
1.3	Switching Procedures	Local Switching Procedures
1.4	Earthing	Earthing
1.5	SRS	Site Responsibility Schedules
1.6	Diagrams	Operational and Gas Zone Diagrams
1.7	Drawings	Site Common Drawings
1.8	Telephony	Control Telephony
1.9	Safety Procedures	Local Safety Procedures
1.10	Co-ordinators	Safety Co-ordinators
1.11	RISSP	Record of Inter System Safety Precautions
1.12	Tel Numbers	Telephone Numbers for Joint System Incidents
1.13	Contact Details	Contact Details (fax, tel, email)
1.14	Restoration Plan	Local Joint Restoration Plan (incl. black start if applicable)
1.15	Maintenance	Maintenance Standards
Part 2: Connection Technical Data		
2.1	DRC Schedule 5	DRC Schedule 5 – Users System Data
2.2	Protection Report	Protection Settings Reports
2.3	Special Automatic Facilities	Special Automatic Facilities e.g. intertrip
2.4	Operational Metering	Operational Metering
2.5	Tariff Metering	Tariff Metering
2.6	Operational Comms	Operational Communications
2.7	Monitoring	Performance Monitoring
2.8	Power Quality	Power Quality Test Results (if required)

Part 3: Generator Technical Data		
3.1	DRC Schedule 1	DRC Schedule 1 - Generating Unit, Power Generating Module, HVDC System and DC Converter Technical Data
3.2	DRC Schedule 2	DRC Schedule 2 - Generation Planning Data
3.3	DRC Schedule 4	DRC Schedule 4 – Frequency Droop & Response
3.4	DRC Schedule 14	DRC Schedule 14 – Fault Infeed Data – Generators
3.5	Special Generator Protection	Special Generator Protection e.g. Pole slipping; islanding
3.6	Compliance Tests	Compliance Tests & Evidence
3.7	Compliance Studies	Compliance Simulation Studies
3.8	Site Specific	Bilateral Connections Agreement Technical Data & Compliance
Part 4: General DRC Schedules		
4.1	DRC Schedule 3	DRC Schedule 3 – Large Power Station Outage Information
4.2	DRC Schedule 6	DRC Schedule 6 – Users Outage Information
4.3	DRC Schedule 7	DRC Schedule 7 – Load Characteristics
4.4	DRC Schedule 8	DRC Schedule 8 – BM Unit Data (if applicable)
4.5	DRC Schedule 10	DRC Schedule 10 –Demand Profiles
4.6	DRC Schedule 11	DRC Schedule 11 – Connection Point Data
Part 5: OTSDUW Data And Information (if applicable and prior to **OTSUA Transfer Time**)		
		Diagrams Circuits Plant and Apparatus Circuit Parameters Protection Operation and Autoswitching Automatic Control Systems
		Mathematical model of dynamic compensation plant

< END OF DATA REGISTRATION CODE

GENERAL CONDITIONS
(GC)

CONTENTS

(This contents page does not form part of the Grid Code)

GC.1 INTRODUCTION

GC.1.1 The **General Conditions** contain provisions which are of general application to all provisions of the Grid Code. Their objective is to ensure, to the extent possible, that the various sections of the Grid Code work together and work in practice for the benefit of all **Users**.

GC.2 SCOPE

GC.2.1 The **General Conditions** apply to all **Users** (including, for the avoidance of doubt, **The Company**).

GC.3 UNFORESEEN CIRCUMSTANCES

GC.3.1 If circumstances arise which the provisions of the Grid Code have not foreseen, **The Company** shall, to the extent reasonably practicable in the circumstances, consult promptly and in good faith all affected **Users** in an effort to reach agreement as to what should be done. If agreement between **The Company** and those **Users** as to what should be done cannot be reached in the time available, **The Company** shall determine what is to be done. Wherever **The Company** makes a determination, it shall do so having regard, wherever possible, to the views expressed by **Users** and, in any event, to what is reasonable in all the circumstances. Each **User** shall comply with all instructions given to it by **The Company** following such a determination provided that the instructions are consistent with the then current technical parameters of the particular **User's System** registered under the Grid Code. **The Company** shall promptly refer all such unforeseen circumstances and any such determination to the **Panel** for consideration in accordance with GC.4.2(e).

GC.4 NOT USED

GC.5 COMMUNICATION BETWEEN THE COMPANY AND USERS

GC.5.1 Unless otherwise specified in the Grid Code, all instructions given by **The Company** and communications (other than relating to the submission of data and notices) between **The Company** and **Users** (other than **Generators**, **DC Converter Station** owners or **Suppliers**) shall take place between the **The Company Control Engineer** based at the **Transmission Control Centre** notified by **The Company** to each **User** prior to connection, and the relevant **User Responsible Engineer/Operator**, who, in the case of a **Network Operator**, will be based at the **Control Centre** notified by the **Network Operator** to **The Company** prior to connection.

GC.5.2 Unless otherwise specified in the Grid Code, all instructions given by **The Company** and communications (other than relating to the submission of data and notices) between **The Company** and **Generators** and/or **DC Converter Station** owners and/or **Suppliers**, shall take place between the **The Company Control Engineer** based at the **Transmission Control Centre** notified by **The Company** to each **Generator** or **DC Converter Station** owner prior to connection, or to each **Supplier** prior to submission of **BM Unit Data**, and either the relevant **Generator's** or **DC Converter Station** owner's or **Supplier's Trading Point** (if it has established one) notified to **The Company** or the **Control Point** of the **Supplier** or the **Generator's Power Station** or **DC Converter Station**, as specified in each relevant section of the Grid Code. In the absence of notification to the contrary, the **Control Point** of a **Generator's Power Station** will be deemed to be the **Power Station** at which the **Generating Units** or **Power Park Modules** are situated.

GC.5.3 Unless otherwise specified in the Grid Code, all instructions given by **The Company** and communications (other than relating to the submission of data and notices) between **The Company** and **Users** will be given by means of the **Control Telephony** referred to in CC.6.5.2.

GC.5.4 If the **Transmission Control Centre** notified by **The Company** to each **User** prior to connection, or the **User Control Centre**, notified in the case of a **Network Operator** to **The Company** prior to connection, is moved to another location, whether due to an emergency or for any other reason, **The Company** shall notify the relevant **User** or the **User** shall notify **The Company**, as the case may be, of the new location and any changes to the **Control Telephony** or **System Telephony** necessitated by such move, as soon as practicable following the move.

GC.5.5 If any **Trading Point** notified to **The Company** by a **Generator** or **DC Converter Station** owner prior to connection, or by a **Supplier** prior to submission of **BM Unit Data**, is moved to another location or is shut down, the **Generator**, **DC Converter Station** owner or **Supplier** shall immediately notify **The Company**.

GC.5.6 The recording (by whatever means) of instructions or communications given by means of **Control Telephony** or **System Telephony** will be accepted by **The Company** and **Users** as evidence of those instructions or communications.

GC.6 MISCELLANEOUS

GC.6.1 Data and Notices

GC.6.1.1 Data and notices to be submitted either to **The Company** or to **Users** under the Grid Code (other than data which is the subject of a specific requirement of the Grid Code as to the manner of its delivery) shall be delivered in writing either by hand or sent by first-class pre-paid post, or by facsimile transfer or by electronic mail to a specified address or addresses previously supplied by **The Company** or the **User** (as the case may be) for the purposes of submitting that data or those notices.

GC.6.1.2 References in the Grid Code to "in writing" or "written" include typewriting, printing, lithography, and other modes of reproducing words in a legible and non-transitory form and in relation to submission of data and notices includes electronic communications.

GC.6.1.3 Data delivered pursuant to paragraph GC.6.1.1, in the case of data being submitted to **The Company**, shall be addressed to the **Transmission Control Centre** at the address notified by **The Company** to each **User** prior to connection, or to such other Department within **The Company** or address, as **The Company** may notify each **User** from time to time, and in the case of notices to be submitted to **Users**, shall be addressed to the chief executive of the addressee (or such other person as may be notified by the **User** in writing to **The Company** from time to time) at its address(es) notified by each **User** to **The Company** in writing from time to time for the submission of data and service of notices under the Grid Code (or failing which to the registered or principal office of the addressee).

GC.6.1.4 All data items, where applicable, will be referenced to nominal voltage and **Frequency** unless otherwise stated.

GC.7 OWNERSHIP OF PLANT AND/OR APPARATUS

References in the Grid Code to **Plant** and/or **Apparatus** of a **User** include **Plant** and/or **Apparatus** used by a **User** under any agreement with a third party.

GC.8 SYSTEM CONTROL

Where a **User's System** (or part thereof) is, by agreement, under the control of **The Company**, then for the purposes of communication and co-ordination in operational timescales **The Company** can (for those purposes only) treat that **User's System** (or part thereof) as part of the **National Electricity Transmission System**, but, as between **The Company** and **Users**, it shall remain to be treated as the **User's System** (or part thereof).

GC.9 EMERGENCY SITUATIONS

Users should note that the provisions of the Grid Code may be suspended, in whole or in part, during a Security Period, as more particularly provided in the **Fuel Security Code**, or pursuant to any directions given and/or orders made by the **Secretary of State** under section 96 of the **Act** or under the Energy Act 1976.

GC.10 MATTERS TO BE AGREED

Save where expressly stated in the Grid Code to the contrary where any matter is left to **The Company** and **Users** to agree and there is a failure so to agree the matter shall not without the consent of both **The Company** and **Users** be referred to arbitration pursuant to the rules of the **Electricity Supply Industry Arbitration Association**.

GC.11 GOVERNANCE OF ELECTRICAL STANDARDS

GC.11.1 In relation to the **Electrical Standards** the following provisions shall apply.

GC.11.2 (a) If a **User**, or in respect of the **Electrical Standards** in (b) to the annex, **The Company**, or in respect of the **Electrical Standards** in (a) to the annex, or in respect of the **Electrical Standards** in (c) or (d) to the annex, the **Relevant Scottish Transmission Licensee**, wishes to:-

(i) raise a change to an **Electrical Standard**;

(ii) add a new standard to the list of **Electrical Standards**;

(iii) delete a standard from being an **Electrical Standard**,

it shall activate the **Electrical Standards** procedure.

(b) The **Electrical Standards** procedure is the notification to the secretary to the **Panel** of the wish to so change, add or delete an **Electrical Standard**. That notification must contain details of the proposal, including an explanation of why the proposal is being made.

GC.11.3 Ordinary Electrical Standards Procedure

(a) Unless it is identified as an urgent **Electrical Standards** proposal (in which case GC.11.4 applies) or unless the notifier requests that it be tabled at the next **Panel** meeting, as soon as reasonably practicable following receipt of the notification, the **Panel** secretary shall forward the proposal, with a covering paper, to **Panel Members**.

(b) If no objections are raised within 20 Business Days of the date of the proposal, then itshall be deemed approved pursuant to the **Electrical Standards** procedure, and **The Company** shall make the change to the relevant **Electrical Standard** or the list of **Electrical Standards** contained in the Annex to this GC.11.

(c) If there is an objection (or if the notifier had requested that it be tabled at the next **Panel** meeting rather than being dealt with in writing), then the proposal will be included in the agenda for the next following **Panel** meeting.

(d) If there is broad consensus at the **Panel** meeting in favour of the proposal, **The Company** will make the change to the **Electrical Standard** or the list of **Electrical Standards** contained in the Annex to this GC.11.

(e) If there is no such broad consensus, including where the **Panel** believes that further consultation is needed, **The Company** will establish a **Panel** working group if this was thought appropriate and in any event **The Company** shall undertake a consultation of **Authorised Electricity Operators** liable to be materially affected by the proposal.

(f) Following such consultation, **The Company** will report back to **Panel Members**, either in writing or at a **Panel** meeting. If there was broad consensus in the consultation, then **The Company** will make the change to the **Electrical Standard** or the list of **Electrical Standards** contained in the Annex to this GC.11.

(g) Where following such consultation there is no broad consensus, the matter will be referred to the **Authority** who will decide whether the proposal should be implemented and will notify **The Company** of its decision. If the decision is to so implement the change, **The Company** will make the change to the **Electrical Standard** or the list of **Electrical Standards** contained in the Annex to this GC.11.

(h) In all cases where a change is made to the list of **Electrical Standards**, **The Company** will publish and circulate a replacement page for the Annex to this GC covering that list and reflecting the change.

GC.11.4 Urgent Electrical Standards Procedure

(a) If the notification is marked as an urgent **Electrical Standards** proposal, the **Panel** secretary will contact **Panel Members** in writing to see whether a majority who are contactable agree that it is urgent and in that notification the secretary shall propose a timetable and procedure which shall be followed.

(b) If such members do so agree, then the secretary will initiate the procedure accordingly, having first obtained the approval of the **Authority**.

(c) If such members do not so agree, or if the **Authority** declines to approve the proposal being treated as an urgent one, the proposal will follow the ordinary **Electrical Standards** procedure as set out in GC.11.3 above.

(d) If a proposal is implemented using the urgent **Electrical Standards** procedure, **The Company** will contact all **Panel Members** after it is so implemented to check whether they wish to discuss further the implemented proposal to see whether an additional proposal should be considered to alter the implementation, such proposal following the ordinary **Electrical Standards** procedure.

GC.12 CONFIDENTIALITY

GC.12.1 **Users** should note that although the Grid Code contains in certain sections specific provisions which relate to confidentiality, the confidentiality provisions set out in the **CUSC** apply generally to information and other data supplied as a requirement of or otherwise under the Grid Code. To the extent required to facilitate the requirements of the **EMR Documents**, **Users** that are party to the Grid Code but are not party to the **CUSC Framework Agreement** agree that the confidentiality provisions of the **CUSC** are deemed to be imported into the Grid Code.

GC.12.2 **The Company** has obligations under the **STC** to inform **Relevant Transmission Licensees** of certain data. **The Company** may pass on **User** data to a **Relevant Transmission Licensee** where:

(a) **The Company** is required to do so under a provision of Schedule 3 of the **STC**; and/or

(b) permitted in accordance with PC.3.4, PC.3.5 and OC2.3.2.

GC.12.3 **The Company** has obligations under the **EMR Documents** to inform **EMR Administrative Parties** of certain data. **The Company** may pass on **User** data to an **EMR Administrative Party** where **The Company** is required to do so under an **EMR Document**.

GC.12.4 **The Company** may use **User** data for the purpose of carrying out its **EMR Functions**.

GC.13 RELEVANT TRANSMISSION LICENSEES

GC.13.1 It is recognised that the **Relevant Transmission Licensees** are not parties to the Grid Code. Accordingly, notwithstanding that Operating Code No. 8 Appendix 1 ("OC8A") and Appendix 2 ("OC8B"), OC7.6, OC9.4 and OC9.5 refer to obligations which will in practice be performed by the **Relevant Transmission Licensees** in accordance with relevant obligations under the **STC**, for the avoidance of doubt all contractual rights and obligations arising under OC8A, OC8B, OC7.6, OC9.4 and OC9.5 shall exist between **The Company** and the relevant **User** and in relation to any enforcement of those rights and obligations OC8A, OC8B, OC7.6, OC9.4 and OC9.5 shall be so read and construed. The **Relevant Transmission Licensees** shall enjoy no enforceable rights under OC8A, OC8B, OC7.6, OC9.4 and OC9.5 nor shall they be liable (other than pursuant to the **STC**) for failing to discharge any obligations under OC8A, OC8B, OC7.6, OC9.4 and OC9.5.

GC.13.2 For the avoidance of doubt nothing in this Grid Code confers on any **Relevant Transmission Licensee** any rights, powers or benefits for the purpose of the Contracts (Rights of Third Parties) Act 1999.

GC.14 BETTA TRANSITION ISSUES

GC.14.1 The provisions of Part A of the Appendix to the **General Conditions** apply in relation to issues arising out of the transition associated with the designation of **GC Modification Proposals** by the **Secretary of State** in accordance with the provisions of the Energy Act 2004 for the purposes of Condition C14 of **The Company's Transmission Licence**.

GC.15 EMBEDDED EXEMPTABLE LARGE AND MEDIUM POWER STATIONS

GC.15.1 This GC.15.1 shall have an effect until and including 31st March 2007.

(i) CC.6.3.2, CC.6.3.7, CC.8.1 and BC3.5.1; and

(ii) Planning Code obligations and other Connection Conditions; shall apply to a **User** who owns or operates an **Embedded Exemptable Large Power Station**, or a **Network Operator** in respect of an **Embedded Exemptable Medium Power Station**, except where and to the extent that, in respect of that **Embedded Exemptable Large Power Station** or **Embedded Exemptable Medium Power Station**, **The Company** agrees or where the relevant **User** and **The Company** fail to agree, where and to the extent that the **Authority** consents.

GC.16 NOT USED

ANNEX TO THE GENERAL CONDITIONS

The **Electrical Standards** are as follows:

(a) **Electrical Standards** applicable for **NGET's Transmission System**

The Relevant Electrical Standards Document (RES)		Reference	Issue	Date
Parts 1 to 3			3.0	March 2018
Part 4 – Specific Requirements				
1	Back-Up Protection Grading across NGET's and other Network Operator Interfaces	PS(T)044(RES)	1.0	September 2014
2	Ratings and General Requirements for Plant, Equipment, Apparatus and Services for the National Grid System and Connections Points to it.	TS 1 (RES)	1.0	February 2018
3	Substations	TS 2.01 (RES)	1.0	February 2018
4	Switchgear	TS 2.02 (RES)	1.0	October 2014
5	Substation Auxiliary Supplies	TS 2.12 (RES)	1.0	October 2014
6	Ancillary Light Current Equipment	TS 2.19 (RES)	1.0	October 2014
7	Substation Interlocking Schemes	TS 3.01.01 (RES)	1.0	February 2018
8	Earthing Requirements	TS 3.01.02 (RES)	1.0	October 2014
9	Circuit Breakers	TS 3.02.01 (RES)	2.0	February 2018
10	Disconnectors and Earthing Switches	TS 3.02.02 (RES)	1.0	October 2014
11	Current Transformers for Protection and General Use on the 132kV, 275kV and 400kV Systems	TS 3.02.04 (RES)	1.0	October 2014
12	Voltage Transformers	TS 3.02.05 (RES)	1.0	September 2016
13	Bushings	TS 3.02.07 (RES)	1.0	October 2014
14	Solid Core Post Insulators for Substations	TS 3.02.09 (RES)	1.0	October 2014
15	Voltage Dividers	TS 3.02.12 (RES)	1.0	September 2016
16	Gas Insulated Switchgear	TS 3.02.14 (RES)	1.0	October 2014
17	Environmental and Test Requirements for Electronic Equipment	TS 3.24.15 (RES)	1.0	October 2014
18	Busbar Protection	TS 3.24.34 (RES)	1.0	October 2014
19	Circuit Breaker Fail Protection	TS 3.24.39 (RES)	1.0	October 2014
20	Synchronising And Voltage Selection	TS.3.24.60 (RES)	2.0	January 2018
21	System Monitor – Dynamic System Monitoring (DSM)	TS 3.24.70 (RES)	2.0	February 2018
22	System Monitoring – Fault Recording	TS 3.24.71 (RES)	1.0	February 2018

23	Protection & Control for HVDC Systems	TS 3.24.90 (RES)	1.0	October 2014
24	Ancillary Services Business Monitoring	TS 3.24.95 (RES)	2.0	February 2018
25	Operational Data Transmission	TS 3.24.100 (RES)	1.0	February 2018
26	Guidance for Working in Proximity to Live Conductors	TGN(E)186 (RES)	1.0	October 2018
Additional Requirements				
Control Telephony Electrical Standard			1.0	17th Sept 2007

(b) Electronic data communications facilities applicable in all **Transmission Areas**.

Communications Standards for Electronic Data Communication Facilities and Automatic Logging Devices	Issue 4	26th Aug 2015
EDT Interface Specification	Issue 4	18th Dec 2000
EDT Submitter Guidance Note	Issue 1	21st Dec 2001
EDL Message Interface Specification	Issue 4	20th Jun 2000
EDL Instruction Interface Valid Reason Codes	Issue 2	23rd Jul 2001
MODIS Interface Specification	Version 4	26th May 2015

(c) Scottish **Electrical Standards** applicable for **SPT's Transmission System**.

RES-01-100	Relevant Electrical Standards for Plant, Equipment and Apparatus for connection to the SP Transmission System	Issue 1

(d) Scottish **Electrical Standards** applicable for **SHETL's Transmission System**.

1.	NGTS 1:	Rating and General Requirements for Plant, Equipment, Apparatus and Services for the National Grid System and Direct Connection to it. Issue 3 March 1999.
2.	NGTS 2.1:	Substations Issue 2 May 1995
3.	NGTS 3.1.1:	Substation Interlocking Schemes. Issue 1 October 1993.
4.	NGTS 3.2.1:	Circuit Breakers and Switches. Issue 1 September 1992.
5.	NGTS 3.2.2:	Disconnectors and Earthing Switches. Issue 1 March 1994.
6.	NGTS 3.2.3:	Metal-Oxide surge arresters for use on 132, 275 and 400kV systems. Issue 2 May 1994.
7.	NGTS 3.2.4:	Current Transformers for protection and General use on the 132, 275 and 400kV systems. Issue 1 September 1992.
8.	NGTS 3.2.5:	Voltage Transformers for use on the 132, 275 and 400 kV systems. Issue 2 March 1994.
9.	NGTS 3.2.6:	Current and Voltage Measurement Transformers for Settlement Metering of 33, 66, 132, 275 and 400kV systems. Issue 1 September 1992.
10.	NGTS 3.2.7:	Bushings for the Grid Systems. Issue 1 September 1992.
11.	NGTS 3.2.9:	Post Insulators for Substations. Issue 1 May 1996.
12.	NGTS 2.6:	Protection Issue 2 June 1994.
13.	NGTS 3.11.1:	Capacitors and Capacitor Banks. Issued 1 March 1993.

APPENDIX TO THE GENERAL CONDITIONS

PART A

GC.A.1 Introduction

GC.A.1.1 This Appendix Part A to the **General Conditions** deals with issues arising out of the transition associated with the designation of amendments to the Grid Code by the **Secretary of State** in accordance with the provisions of the Energy Act 2004 for the purposes of Condition C14 of **The Company's Transmission Licence** at that time. For the purposes of this Appendix to the **General Conditions**, the version of the Grid Code as amended by the changes designated by the **Secretary of State** and as further amended from time to time shall be referred to as the "GB Grid Code". The process and amendments referred to in this Appendix Part A took place before the separation of **The Company** from **NGET** and the introduction into the **Grid Code** of **Offshore Transmission Licencees** and this Part A shall be construed accordingly.

GC.A.1.2 The provisions of this Appendix Part A to the **General Conditions** shall only apply to **Users** (as defined in GC.A.1.4) and **The Company** after **Go-Live** for so long as is necessary for the transition requirements referred to in GC.A.1.1 and cut-over requirements (as further detailed in GC.A.3.1) to be undertaken.

GC.A.1.3 In this Appendix Part A to the **General Conditions**:

(a) **Existing E&W Users** and **E&W Applicants** are referred to as "**E&W Users**";

(b) **Users** who as at 1 January 2005 have entered into an agreement or have accepted an offer for connection to and/or use of the **Transmission System** of **NGET** are referred to as "**Existing E&W Users**";

(c) **Users** (or prospective **Users**) other than **Existing E&W Users** who apply during the **Transition Period** for connection to and/or use of the **Transmission System** of **NGET** are referred to as "**E&W Applicants**";

(d) Existing **Scottish Users** and **Scottish Applicants** are referred to as "**Scottish Users**";

(e) **Users** who as at 1 January 2005 have entered into an agreement or have accepted an offer for connection to and/or use of the **Transmission System** of either **SPT** or **SHETL** are referred to as "**Existing Scottish Users**";

(f) **Users** (or prospective **Users**) other than **Existing Scottish Users** who apply during the **Transition Period** for connection to and/or use of the **Transmission System** of either **SPT** or **SHETL** are referred to as "**Scottish Applicants**";

(g) the term "**Transition Period**" means the period from **Go-Active** to **Go-Live** (unless it is provided to be different in relation to a particular provision), and is the period with which this Appendix Part A to the **General Conditions** deals;

(h) the term "**Interim GB SYS**" means the document of that name referred to in Condition C11 of **The Company's Transmission Licence**;

(i) the term "**Go-Active**" means the date on which the amendments designated by the **Secretary of State** to the Grid Code in accordance with the Energy Act 2004 come into effect; and

(j) the term "**Go-Live**" means the date which the **Secretary of State** indicates in a direction shall be the BETTA go-live date.

GC.A.1.4 The provisions of GC.2.1 shall not apply in respect of this Appendix to the **General Conditions**, and in this Appendix Part A to the **General Conditions** the term "**Users**" means:

(a) **Generators**;

(b) **Network Operators**;

(c) **Non-Embedded Customers**;

(d) **Suppliers**;

(e) **BM Participants**;

(f) **Externally Interconnected System Operators**; and

(g) **DC Converter Station** owners

to the extent that the provisions of this Appendix Part A to the **General Conditions** affect the rights and obligations of such **Users** under the other provisions of the GB Grid Code.

GC.A.1.5 The GB Grid Code has been introduced with effect from **Go-Active** pursuant to the relevant licence changes introduced into **The Company's Transmission Licence**. **The Company** is required to implement and comply, and **Users** to comply, with the GB Grid Code subject as provided in this Appendix Part A to the **General Conditions**, which provides for the extent to which the GB Grid Code is to apply to **The Company** and **Users** during the **Transition Period**.

GC.A.1.6 This Appendix Part A to the **General Conditions** comprises:

(a) this Introduction;

(b) GB Grid Code transition issues; and

(c) Cut-over issues.

GC.A.1.7 Without prejudice to GC.A.1.8, the failure of any **User** or **The Company** to comply with this Appendix Part A to the **General Conditions** shall not invalidate or render ineffective any part of this Appendix Part A to the **General Conditions** or actions undertaken pursuant to this Appendix to the **General Conditions**.

GC.A.1.8 A **User** or **The Company** shall not be in breach of any part of this Appendix Part A to the **General Conditions** to the extent that compliance with that part is beyond its power by reason of the fact that any other **User** or **The Company** is in default of its obligations under this Appendix Part A to the **General Conditions**.

GC.A.1.9 Without prejudice to any specific provision under this Appendix Part A to the **General Conditions** as to the time within which or the manner in which a **User** or **The Company** should perform its obligations under this Appendix to the **General Conditions**, where a **User** or **The Company** is required to take any step or measure under this Appendix Part A to the **General Conditions**, such requirement shall be construed as including any obligation to:

(a) take such step or measure as quickly as reasonably practicable; and

(b) do such associated or ancillary things as may be necessary to complete such step or measure as quickly as reasonably practicable.

GC.A.1.10 **The Company** shall use reasonable endeavours to identify any amendments it believes are needed to the GB Grid Code in respect of the matters referred to for the purposes of Condition C14 of **The Company's Transmission Licence** and in respect of the matters identified in GC.A.1.11, and, having notified the **Authority** of its consultation plans in relation to such amendments, **The Company** shall consult in accordance with the instructions of the **Authority** concerning such proposed amendments.

GC.A.1.11 The following matters potentially require amendments to the GB Grid Code:

(a) The specific detail of the obligations needed to manage implementation in the period up to and following (for a temporary period) **Go-Live** to achieve the change to operation under the GB Grid Code (to be included in GC.A.3).

(b) Information (including data) and other requirements under the GB Grid Code applicable to **Scottish Users** during the **Transition Period** (to be included in GC.A.2).

(c) The conclusions of Ofgem/DTI in relation to small and/or embedded generator issues under BETTA and allocation of access rights on a GB basis.

(d) Any arrangements required to make provision for operational liaison, including **Black Start** and islanding arrangements in Scotland.

(e) Any arrangements required to make provision for cascade hydro **BM Units**.

(f) Any consequential changes to the safety co-ordination arrangements resulting from **STC** and **STC** procedure development.

(g) Any arrangements required to reflect the **Electrical Standards** for the **Transmission Systems** of **SPT** and **SHETL**.

(h) The conclusions of Ofgem/DTI in relation to planning and operating standards.

GC.A.1.12 **The Company** shall notify the **Authority** of any amendments that **The Company** identifies as needed pursuant to GC.A.1.10 and shall make such amendments as the **Authority** approves.

GC.A.2 GB Grid Code Transition

General Provisions

GC.A.2.1 The provisions of the GB Grid Code shall be varied or suspended (and the requirements of the GB Grid Code shall be deemed to be satisfied) by or in accordance with, and for the period and to the extent set out in this GC.A.2, and in accordance with the other applicable provisions in this Appendix Part A to the **General Conditions**.

GC.A.2.2 E&W Users:

In furtherance of the licence provisions referred to in GC.A.1.5, **E&W Users** shall comply with the GB Grid Code during the **Transition Period**, but shall comply with and be subject to it subject to this Appendix to the **General Conditions**, including on the basis that:

(a) during the **Transition Period** the **Scottish Users** are only complying with the GB Grid Code in accordance with this Appendix Part A to the **General Conditions**; and

(b) during the **Transition Period** the **National Electricity Transmission System** shall be limited to the **Transmission System** of **NGET**, and all rights and obligations of **E&W Users** in respect of the **National Electricity Transmission System** under the GB Grid Code shall only apply in respect of the **Transmission System** of **NGET**, and all the provisions of the GB Grid Code shall be construed accordingly.

GC.A.2.3 Scottish Users:

In furtherance of the licence provisions referred to in GC.A.1.5, **Scottish Users** shall comply with the GB Grid Code and the GB Grid Code shall apply to or in relation to them during the **Transition Period** only as provided in this Appendix Part A to the **General Conditions**.

GC.A.2.4 THE COMPANY:

In furtherance of the licence provisions referred to in GC.A.1.5, **The Company** shall implement and comply with the GB Grid Code during the **Transition Period**, but shall implement and comply with and be subject to it subject to, and taking into account, all the provisions of this Appendix Part A to the **General Conditions**, including on the basis that:

(a) during the **Transition Period The Company's** rights and obligations in relation to **E&W Users** in respect of the **National Electricity Transmission System** under the GB Grid Code shall only apply in respect of the **Transmission System** of **NGET**, and all the provisions of the GB Grid Code shall be construed accordingly; and

(b) during the **Transition Period The Company's** rights and obligations in relation to **Scottish Users** in respect of the **National Electricity Transmission System** under the GB Grid Code shall only be as provided in this Appendix Part A to the **General Conditions**.

Specific Provisions

GC.A.2.5 Definitions:

The provisions of the GB Grid Code **Glossary and Definitions** shall apply to and for the purposes of this Appendix Part A to the **General Conditions** except where provided to the contrary in this Appendix Part A to the **General Conditions**.

GC.A.2.6 Identification of Documents:

In the period beginning at **Go-Active**, **Scottish Users** will work with **The Company** to identify and agree with **The Company** any documents needed to be in place in accordance with the GB Grid Code, to apply from **Go-Live** or as earlier provided for under this Appendix Part A to the **General Conditions**, including (without limitation) **Site Responsibility Schedules**, **Gas Zone Diagrams** and **OC9 Desynchronised Island Procedures**.

GC.A.2.7 Data:

Each **Scottish User** must provide, or enable a **SPT** or **SHETL** to provide, **The Company**, as soon as reasonably practicable upon request, with all data which **The Company** needs in order to implement, with effect from **Go-Live**, the GB Grid Code in relation to Scotland. This data will include, without limitation, the data that a new **User** is required to submit to **The Company** under CC.5.2. **The Company** is also entitled to receive data on **Scottish Users** over **SPT** or **SHETL**'s SCADA links to the extent that **The Company** needs it for use in testing and in order to implement, with effect from **Go-Live**, the GB Grid Code in relation to Scotland. After **Go-Live** such data shall, notwithstanding GC.A.1.2, be treated as though it had been provided to **The Company** under the enduring provisions of the GB Grid Code.

GC.A.2.8 Verification of Data etc:

The Company shall be entitled to request from a **Scottish User** (which shall comply as soon as reasonably practicable with such a request) confirmation and verification of any information (including data) that has been received by **SPT** or **SHETL** under an existing Grid Code and passed on to **The Company** in respect of that **Scottish User**. After **Go-Live** such information (including data) shall, notwithstanding GC.A.1.2, be treated as though provided to **The Company** under the enduring provisions of the GB Grid Code.

GC.A.2.9 Grid Code Review Panel:

(a) The individuals whose names are notified to **The Company** by the **Authority** prior to **Go-Active** as **Panel Members** (and **Alternate Members**, if applicable) are agreed by **Users** (including **Scottish Users**) and **The Company** to constitute the **Panel Members** and **Alternate Members** of the **Grid Code Review Panel** as at the first meeting of the **Grid Code Review Panel** after **Go-Active** as if they had been appointed as **Panel Members** (and **Alternate Members**) pursuant to the relevant provisions of the Constitution and Rules of the **Grid Code Review Panel** incorporating amendments equivalent to the amendments to GC.4.2 and GC.4.3 designated by the **Secretary of State** in accordance with the provisions of the Energy Act 2004 for the purposes of Condition C14 of **The Company's Transmission Licence**.

(b) The provisions of GC.4 of the GB Grid Code shall apply to, and in respect of, **Scottish Users** from **Go-Active**.

GC.A.2.10 Interim GB SYS:

Where requirements are stated in, or in relation to, the GB Grid Code with reference to the **Seven Year Statement**, they shall be read and construed as necessary as being with reference to the **Interim GB SYS**.

GC.A.2.11 General Conditions:

The provisions of GC.4, GC.12 and GC.13.2 of the GB Grid Code shall apply to and be complied with by **Scottish Users** in respect of this Appendix Part A to the **General Conditions**.

GC.A.3 Cut-over

GC.A.3.1 It is anticipated that it will be appropriate for arrangements to be put in place for final transition to BETTA in the period up to and following (for a temporary period) **Go-Live**, for the purposes of:

(a) managing the transition from operations under the Grid Code as in force immediately prior to **Go-Active** to operations under the GB Grid Code and the **BSC** as in force on and after **Go-Active**;

(b) managing the transition from operations under the existing Grid Code applicable to **Scottish Users** as in force immediately prior to **Go-Active** to operations under the GB Grid Code as in force on and after **Go-Active**;

(c) managing the transition of certain data from operations under the existing grid code applicable to **Scottish Users** before and after **Go-Active**; and

(d) managing GB Grid Code systems, processes and procedures so that they operate effectively at and from **Go-Live**.

GC.A.3.2 (a) The provisions of **BC1** (excluding BC1.5.1, BC1.5.2 and BC1.5.3) shall apply to and be complied with by **Scottish Users** and by **The Company** in respect of such **Scottish Users** with effect from 11:00 hours on the day prior to **Go-Live**

(b) Notwithstanding (a) above, **Scottish Users** may submit data for **Go-Live** 3 days in advance of **Go-Live** on the basis set out in the **Data Validation**, **Consistency and Defaulting Rules** which shall apply to **Scottish Users** and **The Company** in respect of such **Scottish Users** on that basis and for such purpose.

(c) The **Operational Day** for the purposes of any submissions by **Scottish Users** prior to **Go-Live** under a) and b) above for the day of **Go-Live** shall be 00:00 hours on **Go Live** to 05:00 hours on the following day.

(d) The provisions of **BC2** shall apply to and be complied with by **Scottish Users** and by **The Company** in respect of such **Scottish Users** with effect from 23:00 hours on the day prior to **Go-Live**.

(e) The provisions of **OC7.4.8** shall apply to and be complied with by **Scottish Users** and by **The Company** in respect of such **Scottish Users** with effect from 11:00 hours on the day prior to **Go-Live**.

(f) In order to facilitate cut-over, **Scottish Users** acknowledge and agree that **The Company** will exchange data submitted by such **Scottish Users** under **BC1** prior to Go-Live with the Scottish system operators to the extent necessary to enable the cut-over.

(g) Except in the case of **Reactive Power**, **Scottish Users** should only provide **Ancillary Services** from **Go-Live** where they have been instructed to do so by **The Company**. In the case of **Reactive Power**, at **Go-Live** a **Scottish User's** MVAr output will be deemed to be the level instructed by **The Company** under **BC2**, following this **Scottish Users** should operate in accordance with **BC2.A.2.6** on the basis that MVAr output will be allowed to vary with system conditions.

PART B

GC.B.1 Introduction

GC.B.1.1 This Appendix Part B to the **General Conditions** deals with issues arising out of the transition associated with the approval and implementation of **Grid Code Modification Proposal** GC0112 (Modifications relating to the separation of **System** operations and **Transmission Owner** roles).

GC.B.1.2 This Appendix Part B sets out the arrangements such that:

B.1.2.1 the **Post GC0112 Grid Code** reflects the **Transfer of the System Operator Role**;

B.1.2.2 certain amendments are made to **Grid Code Related Agreements/Documents** to reflect the **Transfer of the System Operator Role**,

B.1.2.2 arrangements can be put in place prior to the **SO Transfer Date** to enable the transition of the operations with **NGET** under the **Pre GC0112 Grid Code** to operations with **The Company** under the **Post GC0112 Grid Code**; and

B.1.2.3 each **User** co-operates in relation to the transition.

GC.B.1.3 The provisions of the **Post GC0112 Grid Code** shall be suspended until the **SO Transfer Date** except for this Appendix Part B (and any related definitions within it) which will take immediate effect on the **Implementation Date** for **GC0112**.

GC.B.1.4 In this (and solely for the purposes of this) Appendix Part B the following terms have the following meaning:

B.1.4.1 the term "**Grid Code Related Agreements/Documents**" shall mean each or any of those agreements or documents entered into under or envisaged by the **Pre GC0112 Grid Code** prior to the **SO Transfer Date** which continue on and after the **SO Transfer Date**;

B.1.4.2 the term "**GC0112**" shall mean **Grid Code Modification Proposal 0112** (Amendments relating to the transfer of the system operator functions from **NGET** to **NGESO**);

B.1.4.3 the term "**NGET**" shall mean National Grid Electricity Transmission plc;

B.1.4.4 the term "**NGESO**" shall mean National Grid Electricity System Operator Limited;

B.1.4.5 the term "**Post GC0112 Grid Code**" means the version of the Grid Code as amended by **GC0112**;

B.1.4.6 the term "**Pre GC Grid Code**" means the version of the Grid Code prior to amendment by **GC0112**;

B.1.4.7 the term "**SO Transfer Date**" means the date on which **NGET's Transmission Licence** is transferred in part to **NGESO** to reflect the **Transfer of the System Operator Role**; and

B.1.4.8 the term "**Transfer of the System Operator Role**" means the the transfer, by means of the transfer in part of **NGET's Transmission Licence**, of the system operator role to **NGESO**.

GC.B.1.5 Without prejudice to any specific provision under this Appendix Part B as to the time within which or the manner in which any party should perform its obligations under this Appendix Part B, where a party is required to take any step or measure under this Appendix Part B, such requirement shall be construed as including any obligation to:

B.1.5.1 take such step or measure as quickly as reasonably practicable; and

B.1.5.2 do such associated or ancillary things as may be necessary to complete such step or measure as quickly as reasonably practicable.

GC.B.2 **GC0112:** Amendments to Existing Agreements and Documents

GC.B.2.1 Each **Grid Code Related Agreement/Document** in place or issued by a party in accordance with the terms of the **Pre GC0112 Grid Code** shall be read and construed, with effect from the **SO Transfer Date**, as if it (and any defined terms within it and the effect of it and those defined terms) recognise and reflect the **Transfer of the SO Functions** and as if any references in it to **NGET** in the context of its system operator role were references to **NGESO/The Company** as appropriate.

GC.B.2.2 In the context of any **Site Responsibility Schedule** in existence at the **SO Transfer Date** and which would require, following the **Transfer of the System Operator Role**, the signature of either **NGESO** instead of **NGET** or both the signature of **NGESO** and **NGET**, **NGESO** and **NGET** acknowledge and the **Users** agree that the signature of **NGET** on such **Site Responsibility Schedule** shall be considered to be the signature of **NGESO** and/or **NGET** as appropriate.

GC.B.3 **GC0112:** Transition

GC.B.3.1 Each party shall take such steps and do such things in relation to the Grid Code and the **Grid Code Related Agreements/Documentation** as are within its power and as are reasonably necessary or appropriate in order to give full and timely effect to the **Transfer of the SO Role** and the transition of the operations, systems, process and procedures and the rights and obligations relating to the **Transfer of the SO Role** under the Grid Code from **NGET** to **NGESO**.

GC. B.3.2 Each party agrees that (a) all things done by **NGET** pursuant to the Grid Code in its system operator role prior to the **SO Transfer Date** shall be deemed to have been done by **NGESO** and (b) all things received by **NGET** pursuant to the Grid Code in its system operator role (including but not limited to notices) shall be deemed to have been received by **NGESO** and (c) all things issued by **NGET** (including but not limited to notices) shall be deemed to have been issued by **NGESO**.

GC.B.3.3 In particular:

B.1.5.1 **Users** acknowledge and agree that **NGET** can exchange information and data submitted by **Users** under the Grid Code prior to the **SO Transfer Date** with **NGESO** to the extent necessary to enable the transition of the system operator role from **NGET** to **NGESO**;

B.1.5.2 **NGET** will identify and publish as soon as practicable and in any event prior to 31 January 2019 any specific requirements (such requirements being reasonable and recognising the timescale) on **Users** necessary to manage the transition of the operations, systems, process and procedures and the rights and obligations relating to the **Transfer of the SO Role** under the Grid Code from **NGET** to **NGESO**;

B.1.5.2 **Users** acknowledge that under the **Pre GC0112 Grid Code NGET** received certain data and information from **Users** which is no longer "live" data or information ("**Legacy Data**") that if it was new data and information of that type would not be available to **NGET** as a **Relevant Transmisison Licence** from the **SO Transfer Date** consent to the retention of such **Legacy Data** by **NGET** where embedded in **NGET** systems or models.

< END OF GENERAL CONDITIONS >

REVISIONS

(R)

(This section does not form part of the Grid Code)

R.1 **The Company's Transmission Licence** sets out the way in which changes to the Grid Code are to be made and reference is also made to **The Company's** obligations under the General Conditions.

R.2 All pages re-issued have the revision number on the lower left hand corner of the page and date of the revision on the lower right hand corner of the page.

R.3 The Grid Code was introduced in March 1990 and the first issue was revised 31 times. In March 2001 the New Electricity Trading Arrangements were introduced and Issue 2 of the Grid Code was introduced which was revised 16 times. At British Electricity Trading and Transmission Arrangements (BETTA) Go-Active Issue 3 of the Grid Code was introduced and subsequently revised 35 times. At Offshore Go-active Issue 4 of the Grid Code was introduced and has been revised 13 times since its original publication. Issue 5 of the Grid Code was published to accommodate the changes made by Grid Code Modification A/10 which has incorporated the **Generator** compliance process into the Grid Code, which was revised 47 times. Issue 6 was published to incorporate all the non-material amendments as a result of modification GC0136.

R.4 This Revisions section provides a summary of the sections of the Grid Code changed by each revision to Issue 5.

R.5 All enquiries in relation to revisions to the Grid Code, including revisions to Issues 1, 2, 3, 4 and 5 should be addressed to the Grid Code development team at the following email address:

Grid.Code@nationalgrideso.com

Revision	Section	Related Modification	Effective Date
0	Glossary Definitions	GC0136	05 March 2021
0	Planning Code	GC0136	05 March 2021
0	Connection Conditions	GC0136	05 March 2021
0	European Connection Conditions	GC0136	05 March 2021
0	Demand Response Services	GC0136	05 March 2021
0	Compliance Processes	GC0136	05 March 2021
0	Europeans Compliance Processes	GC0136	05 March 2021
0	Operating Code 1	GC0136	05 March 2021
0	Operating Code 2	GC0136	05 March 2021
0	Operating Code 5	GC0136	05 March 2021
0	Operating Code 6	GC0136	05 March 2021
0	Operating Code 7	GC0136	05 March 2021
0	Operating Code 8	GC0136	05 March 2021
0	Operating Code 8A	GC0136	05 March 2021
0	Operating Code 8B	GC0136	05 March 2021
0	Operating Code 9	GC0136	05 March 2021
0	Operating Code 11	GC0136	05 March 2021
0	Operating Code 12	GC0136	05 March 2021

Revision	Section	Related Modification	Effective Date
0	Balancing Code 2	GC0136	05 March 2021
0	Balancing Code 3	GC0136	05 March 2021
0	Balancing Code 4	GC0136	05 March 2021
0	Balancing Code 5	GC0136	05 March 2021
0	Data Registration Code	GC0136	05 March 2021
0	General Conditions	GC0136	05 March 2021
0	Governance Rules	GC0136	05 March 2021
1	Glossary Definitions	GC0130	18 March 2021
1	Operating Code 2	GC0130	18 March 2021
1	Data Registration Code	GC0130	18 March 2021
1	General Condidtions	GC0130	18 March 2021

< END OF REVISIONS>